Hot-Water Heating and Fitting.

Hot-Water Heating and Fitting

OR,

WARMING BUILDINGS BY HOT-WATER.

A DESCRIPTION OF

*Modern Hot-Water Heating Apparatus; the Methods of
Their Construction and the Principles Involved,*

WITH

MANY ILLUSTRATIONS, DIAGRAMS AND TABLES.

By WILLIAM J. BALDWIN, *M. Am. Soc. C. E.*,

Member American Society Mechanical Engineers.

AUTHOR OF " STEAM-HEATING FOR BUILDINGS," ETC., ETC.

THIRD EDITION,

(With Corrections, September, 1891.)

NEW YORK :

THE ENGINEERING RECORD.

(*Prior to* 1887, *The Sanitary Engineer.*)

1891.

THE AUTHOR DEDICATES THIS BOOK TO HIS FRIEND

W. WHEELER SMITH, Esq., ARCHITECT, NEW YORK,

IN APPRECIATION OF HIS CONCURRENT INTEREST

IN THE ADVANCEMENT OF

THE SCIENCE OF WARMING AND VENTILATION OF BUILDINGS.

83597

PREFACE.

THE scarcity of *data* as to the theory and practice of warm-
ing buildings by hot-water circulation, has induced me to
lay before the student and workman in this branch of mechanics
as much of the information which I have acquired during more
than twenty years' practical experience in the art of warming
and ventilating buildings that is practicable in a book of this
description.

Its wording and method of expressing and conveying
ideas is not that usually adopted when addressing those who
have received a scientific training. It is not, however, for
purely professional readers that I have written, but for practical
men who are unaccustomed to the abbreviated methods of the
mathematician, which, though they express so much in a few
brief sentences and symbols, are not suited to the wants of the
average workman, or to one who has advanced himself to
the position of foreman, superintendent or proprietor by pass-
ing successively through the lower branches of his calling.

In my intercourse with the mechanic, therefore, I endeavor
to speak to him in terms which my familiarity with him in the
workshop leads me to think he will not misunderstand ; and I
am aware from past experience that it is not well to leave
much to be conjectured ; hence also the occasional repetition of
a problem in another and perhaps simpler manner than at

first or the illustration of the second example of a simple subject by a sum in figures, or by graphic methods.

It is not necessary to explain to the educated engineer that absolute accuracy in scientific *data* is very rare, and that it would be folly to assume that all accepted formulæ are without error. It is, however, necessary to inform the mechanic that the accepted theoretical formulæ are in nearly all cases very close approximations to the truth, and that without them we would be working entirely in the dark, whereas with them we are enabled to determine beforehand, to within a small percentage, one way or the other, what the results will be in actual practice, and that therefore he must look on them as correct for practical purposes.

The formulæ governing the flow of water in pipes herein given are the ordinarily accepted ones of the hydraulic engineer.

Much of the matter in the following pages will be recognized as having originally appeared in *The Engineering Record*, in a series of articles under the *nom de plume* of "Thermus." These articles have, however, been revised, and considerable new matter has been added, and in their present more complete yet more compact form it is hoped they will be more readily available and useful to those who have to design, construct and manage hot-water heating apparatus.

INTRODUCTION.

BEFORE going into the details of the subject of warming buildings by hot-water circulation, I wish to call the attention of the designer of an apparatus to the fact, that it is of nearly as great importance to so plan his work to secure an equal resistance to the flow of the water at all points of an apparatus as it is to have pipes of sufficient capacity to carry the amount of water necessary for a given duty. He has to provide not only pipes of sufficient diameter to carry a given quantity of water through the pipes of an apparatus, but he has to distribute it in proportion to the heating surface through all the branches of the system.

His *first* problem then is to determine the quantity of water to be moved in a given time, through the system as a whole ; and the *second* is to secure its equal distribution.

He may assume any size for his main, and though it may be too small for the duty expected of it, it is still possible for him to divide it into branches that will do equal work at all points, though the result that will follow in such an apparatus will be a very great difference of temperature between the flow and return pipe, and a correspondingly lower temperature in the radiators.

The object of this book is to enable a designer to readily determine, not only the proper diameters and lengths of pipes

for an equal distribution, but to determine the diameters and lengths for any stated duty or loss of temperature, and at the same time secure a practically equal resistance to the flow of the water through all the circuits of an apparatus. For those who have not the time or inclination to study the subject thoroughly, tables and diagrams have been prepared summarizing the requirements for certain ordinary conditions of practice, whereby the diameters and lengths of pipes can be determined offhand for apparatus containing up to sixteen hundred square feet of surface.

TABLE OF CONTENTS.

CHAPTER I.

CHAPTER II.

CHAPTER III.

CHAPTER IV.

CHAPTER V.

CHAPTER VI.

CHAPTER VII.

CHAPTER VIII.

CHAPTER XXI.

CHAPTER XXII.

Chapter XXIII.

Chapter XXIV.

CHAPTER I.

Circulation of Water in Vessels, caused by the Addition or Sub-
traction of Heat—Heat the Primary Cause of Motion
in Water and Gravitation the Negative Cause—
Nomenclature of Circulation in the Pipes and
Boiler of a Hot-Water Apparatus.

THE growing demand for a better general knowledge of
hot-water heating for buildings by architects, engineers,
and the pipe-fitting trades in the United States induces me to
give a description of American practice in hot-water heating,
as I find it, both in this country and in Canada.

In the United States most of the Federal buildings are
warmed by hot water, and a considerable number of private
dwellings throughout the country have been warmed suc-
cessfully by different special hot-water systems, but, as
compared with the amount of steam-heating done, it is
comparatively small, and the knowledge on the subject is
limited and confined to a very few who have made a specialty
of it in connection with green-house warming. In Canada
the hot-water apparatus appears to stand in the highest favor
for house-warming, although the use of steam apparatus is not
rare by any means. At the present time, however, the people

of Canada seem to be considering the question of steem plant more than formerly, and many new buildings are being warmed by steam, while the people of the Northern, Middle, and Eastern States of the Union are studying the problem of warming by hot water and adopting it slowly and cautiously, though in more cases than heretofore, and with every appearance of using it extensively when it is better understood.

Before going into the question of methods employed for the different classes of buildings and their details, it is well, perhaps, to say a few words on the laws of hot-water circulation, that the reader may understand terms and technical applications as they appear and the more readily comprehend and reason by analogy when considering different classes of work, which however much they differ in appearance, are all controlled by a few common laws that must never be lost sight of in constructing a hot-water circulating apparatus ; the chief one of which is that as each particle of water loses its heat by giving it off to the air, etc., through the walls of the pipes and heaters, it becomes heavier than the particles of water surrounding it and falls by the law of gravitation, displacing warmer particles than itself, which, by the interchange of position, rise above it, producing what is called circulation.

This takes place in all waters and in all liquids, without regard to mass or shape. If we have a glass or iron cube filled with warm water, say one foot square, or any convenient size, as shown in Figure 1, with all sides but the lower one presented to the cooling action of the surrounding air, and radiating heat as well—which latter it will do, independently of the air—we find we will have currents in a downward direction on

the four outer sides close to the glass, as shown by the waved arrows, while at the same time there will be noticed a current ascending at the centre, as shown by the darts. This circulation will be noticed to go on in any vessel of water that is removed from its source of supply of heat as long as the water is warmer than the air.

If, however, instead of standing on the table cooling, this

FIGURE 1.

cube was placed over a fire, as on a stove, so as to receive heat through its bottom, it would be found that the circulation or movement of the water would be in just the same direction as before, though possibly much stronger and faster; the only difference being in the *cause* that produces the circulation.

In the first case, the particles are cooled by contact with the sides of the cube, through which their heat was conducted

away from the mass to warm the air on the outside, and in consequence of which they become smaller and more dense than their neighbors immediately behind and about them and which have not as yet come in contact with the outsides of the cube, and they sink, forcing an equal number of particles out of their way; and as the latter cannot escape from the cube they are forced to rise elsewhere within it, which, in the case of a cube exposed on four sides, must be near or at the centre.

In the second case, although the circulation is identical so far as appearances go, we cannot consider that the outer particles are forcing their way down, as in all probability they will be receiving heat from the stove, and would, under such conditions, relatively, have a tendency to go up instead of down, and hence we are forced to the conclusion that it is the light particles in the centre that are forcing their way up, and that the ones at the sides are simply forced down by the greater upward pressure at the centre.

In the one case, then, the force of gravity is bringing down the particles as they cool, and in the other the force must be that of heat, or its mechanical equivalent, which overcomes gravity.

Throughout this book the reasoning as to the cause of circulation will be on the assumption that heat is the prime cause of all motion and that gravitation is negatively the cause of motion in water. Heat destroys the equilibrium of the particles of water and gravitation is ever on the alert and always active in restoring the equilibrium thus destroyed. Hence motion.

In considering the motion of water in the cube we saw how

the loss of heat from the surface of the cube destroyed the equilibrium of the particles of the water, and they therefore descended.   We also saw that an application of heat to the

FIGURE 2.

middle of the bottom produced a like result, by warming the particles near the centre, which gave them an upward movement ; the particles at the side taking their place by gravitation.

If we now take a long cylinder or pipe filled with water, as shown in Figure 2, in which the water is warmer than the air about it, the circulation will be found to go on just the same

FIGURE 3.

as in the cube when it was first laid on the table, and from the same cause—*i. e.*, the gravitation of the heavier particles between the lighter ones.

Again, if we take a long pipe and bend it into the simplest
form of a closed circulating apparatus—say as shown in Figure
3—we will still have local reversed and down currents in our
up or flow pipe close to the sides, as shown in the main flow-
pipe at *a*.   This is a factor to retard circulation not generally
considered and still of too much importance to be entirely
overlooked.

In a cube or short cylinder, or in a kettle on the fire, this
circulation is shown at its best ; and there is at that time no
other, and it is equivalent to the main or primary circulation,
such as goes on within a boiler.   The circulation in a cube or
short tube cooling on the table, as already shown, cannot prop-
erly be called a primary circulation, as it is not caused by an
increase of heat, but by a loss of heat, and therefore might be
appropriately called a secondary circulation when contrasting
it with a circulation caused by the addition of heat alone ;
but in considering the result and not the cause, and as the
two causes are nearly always present in a warming apparatus,
we must know this local circulation by the name of primary.

It is found in the boiler on the outer sides in the diagram
(Figure 3) at *b*, by the direction of the arrows.

If fire is now made under the boiler a general circulation is
set up, which passes up the middle of the pipe *a* and over into
the pipe *c*, to return to the boiler again.   Some of this water,
however, which starts from the boiler, and which ordinarily is
supposed to shoot right through the pipe *a*, tries to return
by the same pipe.   Presumably, unless the pipe is very
large in diameter for the work it has to perform, no con-
siderable quantity of it returns into the boiler through

the pipe it leaves, but, nevertheless, it starts this rolling
motion at the surface of all ascending water-pipes, and
forms a factor against the velocity and ease of flow,
very similar to the resistance of friction, and this nat-
urally increases the friction factor, as it establishes water-
currents in opposite directions, giving a rolling motion to the
particles and causing eddies against the wet side of the pipe.

This motion, at the surface of the pipe or cylinder, is
sometimes called "molecular" circulation, which very well
expresses the condition, but "local" circulation is probably
the most comprehensive term for the fitter.

If the reader wishes to observe for himself the "local"
circulation which goes on within hot-water pipes, let him take
a small tin can for a boiler and make a simple circulation of
glass tubing from its top, returning again to the side. He may
then fill it with water and put in some very fine charcoal,
when, upon applying heat to its bottom, the action of the
water can be observed with advantage.

This local circulation always affects the general forward
movement of the main current in an apparatus. We are
unable, however, to determine the extra resistance to the flow
in the upward pipes from this cause, but it is considerable,
and is in a direct ratio to the outward surface of the pipe
compared to its volume, being small when compared with the
large diameter pipes, and causing no very practical drawback
to their circulation, but comparatively great in the case of
small pipes, so that a point can be reached by reducing
diameter and increasing length where a local circulation
would go on for a certain distance up the pipes, but

the main circulation through the circuit would not take place, the pipes being warm to the touch for some distance of their length upward, and cold beyond, giving the general impression that the heat of the boiler has been conducted to that height by the iron of the pipe or by the passage of heat from contact of particles not in motion ; and while this may be so to a certain extent, it is more largely caused by local circulation in the lower end of the small pipe.

Local circulation goes on even in horizontal pipes, but in such cases cannot be said to affect the flow—certainly not to an appreciable extent.

The course of local circulation in a horizontal pipe would be from the top to the bottom side, with an upward or return current at the centre when the pipe is giving off heat. At the same time the forward motion would be going on by the force of the main circulation, giving particles of charcoal held in suspension the appearance of a screwing motion along each side of the pipe, the particles on one side of the pipe when looked down upon circling in one direction and those on the other side in a contrary direction.

In the downward pipe there may be said to be no local circulation. None is apparent, though some particles will be found to fall more rapidly than others ; as in such case the main current and the local currents, if any, are in the same general direction. It is easy to understand how the water directly in contact with the surface of the pipe might fall a little faster than in the middle of such a pipe, it being a little colder, but this is not always observed to be so, as, in cases where the pipe observed is part of a main circuit, the water

will be hurried along by the main current in the centre of the pipe faster than it will move against the sides, on account of friction. In the down pipes, however, both currents tend in the same direction, and the tendency of the surface current is to lessen friction or resistance to the main flow and need not be considered.

We will, therefore, for convenience, in these articles, call all currents not working or moving in the direction of the main current, local currents, and the currents induced within the boiler by the heat of the fire a primary current, while the circulation through the main flow-pipes and back again through the main return-pipes will be known as the main current, or the main circuit ; the circulations through all branches, coils, or radiators being known as branch circuits or branch currents.

CHAPTER II.

Consideration of the Question of Motion in the Pipes of a Hot-
Water Apparatus as seen from Different Standpoints,
though having the same Ultimate Bearing — Mr.
Tredgold's Views—Mr. Hood's Views—Fixing
the Cause of Motion in the Minds of Students.

I DOUBT whether it is worth considering the philosophy
of the question of the cause of circulation in hot-water
apparatus very closely.   It is sufficient to say that hot water
will ascend and cold water descend.   This holds good, how-
ever, only in water at temperatures above 40° Fah., and there-
fore holds good for all warming apparatus ; but, as a matter of
fact, water colder than 40° Fah. will also ascend in a mass
slightly warmer than itself, as may be seen in the brine-tank of
a refrigerating or ice-making apparatus, where the intensely
cold brine leaves the ammonia-pipes and flows upward instead
of down, as might naturally be supposed by any one who has
not carefully considered the matter.

T. Bramah, C. E., in an appendix to the "Principles of
Warming and Ventilation," by Thomas Tredgold, C. E., pub-
lished in 1836 in London, says : " The circulation of hot water
when employed for the purpose of carrying and distributing

heat through pipes or other vessels is produced by the unequal
density of the fluid, arising from the difference of temperature
in the ascending and descending columns of water connected
with the heating reservoir and its velocity is governed by the
height of the said columns." And to demonstrate more clearly
the mechanical action of the moving force by which he consid-
ered the circulation is maintained, he inserts the accompanying
diagram and reference previously employed by Mr. Tredgold in

FIGURE 4.

a letter to the Secretary of the Horticultural Society, and
which was recorded in the transactions of that institution at
the time. The passage reads as follows:

"If the vessel (Figure 4) A B and pipes be filled with water
and heat applied to the vessel A, the effect of heat will expand
the water in the vessel A and the surface will rise to a higher
level *a d*, the former general level surface being *b b*. The .

density of the fluid in the vessel A will also decrease in con-
sequence of its expansion, but as soon as the column *c d*, above
the centre of the pipe, is of greater weight than the column *f e*,
above that centre, motion will commence along the upper pipe
from A to B and the change this motion produces in the
equilibrium of the fluid will cause a corresponding motion in
the lower pipe from B to A ; and in short pipes the motion
will be obviously continued till the temperature be nearly the
same in both vessels, or if the water be made to boil in A it
may be boiling hot in B, because ebullition in A will assist the
motion."

Mr. Thos. Hood, in his "Treatise on Warming Buildings,"
takes exception to this, and says : "Now it is certain that this
theory will not account for the circulation of the water under
all circumstances and in every variety of form of the apparatus,
and as the cause of motion must be the same in all cases, any
explanation which will not apply universally must necessarily
be erroneous."

To prove that Mr. Tredgold was wrong in his assumption,
Mr. Hood constructed the diagram, Figure 5, and said ·

"Suppose the apparatus to be filled with cold water and the
two stop-cocks to be closed ; then, on applying heat to the
vessel A, the water it contains will expand in bulk and part of
it will flow (run away) through the small waste-pipe *x*, which
is so placed as to prevent the water from rising higher in the
vessel A than the top of the vessel B." He then asserts that the
water which remained in the vessel A after it had been heated
and expanded and a portion of it had passed away through
the overflow-pipe *x*, as before stated, will be lighter than it

was before warming or running off, but that its height
remained the same, and then asks the reader to suppose the
two cocks to be opened simultaneously and to assume (as
assumed by himself) that the hot water in the boiler A will
immediately flow through the upper cross-pipe to B, and that
the water in B will correspondingly flow toward A through the
lower pipe, and evidently wanting the reader to agree with him
that this flow takes place without the increased head (actual or

FIGURE 5.

potential) in the hot leg, arguing that we must find another
explanation for the cause of motion, as the reason given by
Tredgold " is insufficient to account for the effect in the sim-
plest form of apparatus."

Mr. Tredgold's manner of explaining how the increased
height of the warm leg caused the flow is evidently not cor-
rect, but his meaning is apparent, and shows that he consid-
ered that there was just as much, or more, preponderance of

pressure through the upper cross-pipe to B as there was through the lower pipe to A, and that he looked on heat as the cause of motion.

Mr. Hood goes on to explain that if heat be applied to the boiler A, Figure 5, an increase of the volume takes place, and that it becomes lighter, the heated particles rising through the colder ones, which latter sink by their greater specific gravity, when they in turn become heated like the others (which, of course, is so far correct), and that then, when the water in A becomes lighter than that which is in the opposite vessel (B), the water in the lower horizontal pipe is pressed by the greater weight and moves toward A. A little reflection and consideration, however, will show that the pressure through the lower pipe toward A is no greater after the water in A is warmed than it was before, and if the top pipe is removed this becomes very apparent, as no water can pass from A to B, or *vice versa*, without going through the lower pipe ; and any one conversant with hydraulics knows this, as there are just as many particles in one vessel as the other, and every particle weighs the same whether it is expanded by heat or not. Mr. Hood, on the other hand, in his treatise, is endeavoring to prove that the motion of the water is caused solely by a force of gravitation in the cold pipe instead of by the force of · heat imparted to the water in the warm pipe, and uses some apparently forcible arguments to sustain his theory.

From the practical side of this subject it may appear unnecessary to argue this question, and it would be were it not that it will be a means of fixing the cause of motion in the water in the minds of some who have not considered it, and may, pre-

sumably, throw some light on the question of difference between the Tredgold theorists and those who follow Mr. Hood, and show that there is really no practical difference between the two men, the fact being simply that they view the question from different standpoints, and that Mr. Hood mistook the effect for the cause, as he by that means more readily explained some of the problems that at first appear to be unexplainable by Mr. Tredgold's views as he interpreted them.

If we return to Mr. Hood's diagram, Figure 5, and follow what takes place to the point of getting ready to open the "two cocks simultaneously," we will find that some water has run from the pipe x, and that both cold and hot pipes stand at the same level, though not in hydrostatic equilibrium, as some of the hot column has been drawn away through the pipe x.

Mr. Hood then asks us to open the two cocks together. We do so, and the water circulates or moves we know from experience. But Mr. Hood must assume for himself, and asks us to assume also, that it circulates without a rise of head in the hot pipe.

This, of course, we cannot agree with if we stop one moment and consider that the hydrostatic equilibrium must first be established the moment the cocks are opened, and that we cannot consider the question of a thermo-dynamic circulation to commence until some of the cold and heavy column (B) runs into A through the bottom pipe to establish the balance that was destroyed by running some of the water out at the pipe x, and it is at the commencement of this first movement Mr. Hood assumes the circulation commences. The first movement of the water commences then, but it is only a hydraulic movement, or

circulation, which ends the moment the columns are in hydro-static equilibrium, and it is at this time the thermo-dynamic current commences that afterwards goes on to keep up the motion of the water in the pipes.

In the experimental apparatus, that is not receiving heat, we are apt to consider gravitation only as the cause of motion, but we must look further and consider that heat is being

FIGURE 6.

added to the up-leg of the syphon in as great or even greater quantity than the cold one is giving it off.

Surely we cannot assume that the water in B had anything to do with lifting and discharging some of the water of A through x while the lower pipe was closed, and when the said lower pipe is opened, the upper one being closed, the pressure and current through the lower pipe goes only so far as to establish the balance again ; the warm column going up because

of its lessened weight—not as high as before, as some of it was run to waste—but relatively as much above the top of the cold column as it was before, and it is then the circulation starts and goes on, by the water in the higher level flowing toward the lower one.

Let the reader now make a diagram or a model for himself like Figure 6, and plug or cork the pipe *x* and open the lower cock alone (as in Figure 6) and see what takes place. Why,

he will find that the water in A, being lighter than in B (for a given measure of it), will rise again higher than the water in B until they balance in weight. Let him then open the upper cock, closing the bottom one (as shown in Figure 7), and this head flows through the upper pipe into B, though certainly not pushed there by the weight in B, as *the lower cock is closed*, but by the excess of head in A, above a passage through which it may run off either into B or into an outside vessel, as I will endeavor to show by the diagrams, Figures 8 and 9.

Heat is applied to the boiler A, Figure 8 ; the lower cross-pipe being closed. Some of the power of the heat goes to warm the water, and some of the heat is converted into motion, and raises a quantity of the water in the boiler A from the normal common level water-line C to the level D, or

FIGURE 8.

line of equilibrium. It is in raising this water the *work* is done which causes motion, and it is the fall of this water again to its normal level which maintains the circulation. •

If we let this water run over into B, as we may do by opening the cock in the upper pipe, an equal weight of cold

water from the bottom of B will run into A if the lower pipe is open; but if it is not open, this water, which has run through the upper pipe, will stay above the normal level C, in the chamber B, and it is the fall of this water to the normal level, and not any power below it, that maintains circulation. This may be made plainer by Figure 9. Water flows at a constant level from a reservoir R to the chamber B, thence through the bottom pipe to the chamber or boiler A, where it

FIGURE 9.

is warmed, expanded, and lifted until it flows through *a* at a much higher level than the surface of the reservoir. The question now is, was it the weight in B or the heat applied to A that caused the motion and elevation of water.

If we take an apparatus like Figure 8, but with the cocks removed from the cross-pipes, and apply heat to the bottom

at A, the water will rise in the latter until it runs over into B, and as long as heat is maintained the water will flow, and the water elevated might be just as well run into another vessel as into B, and it would so run until a quantity equal to the increment by expansion runs off.

Of course, when the pipes are open, to allow the water to move around the circuit, this rise is very small, and in an apparently closed apparatus it is said it cannot exist, and this is adduced to try to prove Mr. Tredgold's assumption entirely erroneous ; but a little thought will dispel this, as all apparatus must have an expansion-chamber, and it matters little whether it is on A or B, for when it is on the latter, and A is a closed cylinder on top, with the cock in the bottom pipe closed, the excess by expansion simply flows through the upper pipe and rises in B to flow through the lower pipe when the latter is opened.

If we make Figure 10 we have the simplest form of a water-circulating apparatus. A slight rise actually takes place at d, even with the largest pipe at a, the rise in the diagram being purposely exaggerated. If there is a small pipe at a the water at d will stand higher than when the pipe is large, and the head (d) will increase until it overcomes the friction in the small pipe (a), and this head is the *friction head*, the equivalent of the resistance to the flow of the water.

Perhaps, in the consideration of circulation for our purpose, it is just as well to suppose the cold leg to be pushing the water up within the warm leg of the apparatus. It matters little from the practical side which way we consider it, as with an apparatus, when it is completed, we are only to consider the difference of

power between the rising column and the lowering column
for equal perpendicular heights; and whether this power is
the elevation of water in one pipe, due to expansion, or a down-

FIGURE 10

ward force in the other, it matters little to the fitter, as long as
the result is obtained.   Any force that will tend to destroy the
equilibrium among the atoms of a body of water will result in

motion ; though it is usual to attribute the flow to the force of gravity alone. Certainly, if the force of gravitation did not exist, there could be no circulation or return of the current, but, on the other hand, if work was not done by heat in lifting the water, gravitation alone could not produce motion. The addition or the loss of heat destroys the equilibrium and gravitation always tends to restore it.

Fig. 11

We may liken the whole matter to a chain over a pulley, as shown in Figure 11. If we add weight at one side at *a*, it comes down at that side and goes up at the other as shown by the arrow. If we lift it at *b* it still goes on in the same direction whether we pull down at *a* or not, and if we lift and pull

together it simply goes the faster in the same direction.   The lifting power is figurative of the force of expansion from the boiler (heat), and the pull or weighing down is likened to the force of gravity when it becomes possible to assert itself by the loss of heat from the water, or relatively by the addition of heat to the opposite leg of the apparatus.

CHAPTER III.

To Find the Flow of Water in the Pipes of an Apparatus— Simple Formula Expressing the Law which Governs a Body Falling by Terrestrial Gravitation—Diagram Showing the Curve of the Coefficients of the Expansion of Water— Diagram Showing the Velocity of Flow of Water in Feet per Second when the Height from which it Falls is Known—The use of the Diagrams in Estimating Flow through an Apparatus.

WE will next consider how to calculate or find the rapidity of motion in the mass of water, or its velocity through the pipes of an apparatus. Let us take a tube, say twelve feet long, as shown in Figure 12, and fill it with water at 40° Fah.— and what would ordinarily be called cold water—until it just reaches the 10-foot level at *a* ; or, in other words, we have a column of water just ten feet high at mean temperature within the tube. If we now apply heat to the bottom of the tube and expand the water until it boils, or until the whole mass of water is warmed to 212° Fah., we will find by measurement that the column that was just ten feet high when it had a temperature of 40° Fah. is now 10′ + $4\frac{8}{10}$″ high, or at *b* in the tube, having

increased just .04 of its length (Dalton) by being warmed
from 40° to 212° Fah.

If we now take two such tubes arranged side by side as in
Figure 13, and connect them at the bottom with a cross-tube
and closed cock, arranging an overflow-pipe in B at the

FIG·12

10-foot level c and filling it (B) with water until it is on the
point of flowing out, while at the same time we fill the pipe A
with water to the 10′4$\frac{8}{10}$″ level (b), we will find on suddenly
opening the cock the water will fall from b to a, overflowing
at c, and that if we carefully measure its velocity at the start

we will find it to be just 5.06 feet per second of time, or 303 feet per minute—exactly the velocity a piece of lead would obtain as it reached a if it fell from b to a, a distance of $4\frac{8}{10}$ inches.

If we now run water in at the pipe d (Figure 13) so as to

FIG·13

maintain a head of water in A equal to the height $a\ b$, the water will flow through the pipe A to the cross-pipe, through that pipe to B, and overflow at c, with a lineal velocity of a little over five feet per second, assuming the pipes are of equal diameter throughout, friction not considered. In other

words, this will be the greatest theoretical velocity possible
in the pipes of an apparatus for a *ten*-foot column, under
the greatest ranges of temperature and density due to the
pressure of our atmosphere.

Now, if our column is twenty (*20*) feet high the expan-
sion of the water will be just double for the same range of
temperature, and the fall will be $9\frac{6}{10}$ inches, but the velocity
is not doubled by any means, and it will be found to be only
7.15 feet per second, as I will endeavor to show.

The fall of water in pipes follows the same law as the fall
of a weight through a vacuum.   Where a weight falls through
the air it meets some resistance, and when water falls in a
pipe it meets resistance by friction, etc., but we will not con-
sider it here.

The simplest formula to express the law which governs the
velocity of a body falling by terrestrial gravitation is

$$V = \sqrt{H} \times 8,$$

in which H = the height fallen from or the distance fallen
through in feet, and V = the velocity in feet per second.

If we therefore apply this rule to a body falling $9\frac{6}{10}$ inches
—in other words, .8 of a foot—we will find the velocity to be
7.15 feet per second, or 429 feet per minute, and the same is
true of the water falling from the same height.

It will be noticed, therefore, that although the distance
through which the water had to fall was *doubled* the velocity
was not increased *one-half*, for the simple reason that the
velocity increases only as the square root of the height from
which the water falls.

If we go on, therefore, and see what the velocity will be for a 100-foot column (which is ten times the height of the first column), the ranges of temperature remaining the same (40° to 212°) and the distance fallen from four feet, we will find by applying the rule it will be *square root* 4 = 2 × 8 = 16 feet per second, or 960 feet per minute, which is very little over three times the speed it would attain when falling from only one-tenth of the height.

 ˙ The velocity last mentioned, however, will never be attained in the pipes of an ordinary heating apparatus, as there cannot be in ordinary practice anything like 170° Fah. between the temperatures of the flow and return pipes, even should there be a building 100 feet high warmed with hot water, and it is therefore simply instanced here to fix in the mind of the fitter that the increase of velocity of flow is small compared to the increase of height of the apparatus, and that comparatively shallow or low apparatus, with an apparently small difference between the temperatures of the water in flow and return pipes, will be found to have a velocity of flow sur- prisingly good, if the pipes are only sufficient in diameter to avoid retarding its flow and are properly placed and fitted.

The diagram Figure 14 I have constructed to show the expansion of water according to Dalton—from *mean tempera- ture* to 212° of the scale of Fahrenheit's thermometer ; in other words, to show the expansion of water from the temper- ature at which its bulk is smallest and its density greatest to its greatest bulk and least density, under the pressure of our atmosphere at sea-level, and which covers all the ranges of temperature and bulk ever likely to take place in an open or

FIGURE 14.

low-pressure circulation. It will be noticed the base line is laid off into divisions of 10° Fah. (excepting the first, which is 12°)

FIGURE 15.

from 40° to 212°, and that the perpendicular line of figures, which represent inches, is the expansion or increase of length

of a *ten-foot column* of water when warmed from 40° Fah., and
that the ordinates of the curve show the coefficients of the
expansion of water irrespective of volume.

The diagram Figure 15 has been constructed to show the
velocity of the flow of water in feet per second when the
height from which it falls is known.   The lower, or base, and
horizontal lines are divided into *feet* from o′ to 8′, as probably
covering the greatest range of velocities found in ordinary
apparatus, while the vertical lines represent in inches the
expansion that will be found to take place in a column of
water.   It is intended that these two diagrams (Figures 14
and 15) be used together.

For instance, let us assume we have an apparatus ten feet
high, such as we might find where only one floor of a building
was warmed.   Let us assume now that the water goes up in a
flow-pipe at a temperature of 182° Fah. and returns at 162° Fah.
What, then, should be the greatest possible velocity of the
water through the rising flow-pipe ?   Let us return to diagram
Figure 14 and see what the column in inches reads for a tem-
perature of 182°.   We will find it to be $3\frac{40}{100}$ inches.   Now see
what it is for a column of 162°, and we find it $2\frac{60}{100}$, the differ-
ence being $\frac{8}{10}$ of an inch.   If we now turn to diagram Figure
15, and approximate .8 of an inch on the vertical scale of
inches, we will find that a horizontal line drawn with our pencil
so as to start at $\frac{8}{10}$ of an inch will cross the curve line just
where the two-foot velocity line crosses it, showing that for a
fall of a little over ¾ of an inch we have a velocity of flow in
our pipe of two feet per second.   Let us take another example
of the same, the better to understand the use of the diagrams.

Suppose we have an apparatus fifteen feet high, as shown in Figure 16. We have now to find the measure of the difference of weight or power that keeps up the circulation in this apparatus. Heretofore we have spoken of the height from

FIG · 16

which the water falls, but it may appear to the beginner that the water cannot fall in an apparatus of this kind, as it is practically closed, and that there is, therefore, something to be explained, that the theory of a falling body may harmonize

with the water rushing through the pipes of such an appa-
ratus.

Really, there is a hydrostatic head or its equivalent. It
may be likened to the increased weight of the cold leg of the

Fig·17

syphon or the lessened weight of the warm leg. In the case
of an apparatus as in Figure 16 one may readily think he sees
where the head comes in play iu producing circulation, as the
distance *a c* readily appears to be due to the expansion of the

column $c\,d$, but in Figure 17 it is not apparent at all. Never-theless, to consider the question of velocity in pipes, we are bound either to consider the fall of the water in the hot col-umn from a to c (Figure 16), or the fall of the cold column from c to e (Figure 17), which latter is the measure between the columns $a\,b$ and $c\,d$ for equal weights. It, therefore, matters nothing to us practically whether we consider the height $a\,c$, (Figure 16), or the height $c\,e$ (Figure 17), as the measure of the flow, as the result will be practically the same, as any one conversant with the laws of hydraulics knows.

Our diagram, Figure 14, was made on the increase of height of a column of water due to expansion and not on the decrease due to contraction ; therefore we will speak of the head which produces circulation the same as we would of the total head from a reservoir that produces the discharge through apertures or pipes and on which the velocity of efflux or movement depends.

We will return to our example, Figure 16, to familiarize ourselves with the use of the diagrams. The height $c\,b$ is fifteen feet and the expansion of the water is that due to the rise of temperature between $152°$ and $202°$ Fah. For a 10-foot column, as per diagram, we find it to be $4\frac{36}{100}'' - 2\frac{11}{100}'' = 2\frac{25}{100}''$, which is the rise for a 10-foot column at $202°$ Fah. over one $152°$ Fah. But as our present column (Figure 16) is fifteen feet, we have

$$\frac{2.25'' \times 15'}{10'} = 3\frac{37}{100}''$$

as the increase for the 15-foot column.

If we now turn to diagram Figure 15, and approximate
$3\frac{31}{100}$ on the inch column at the left, we will find whereat a
pencil line run horizontally will cross the curve.   From this
point if we drop a vertical line we will find it bisects the base
line at $4\frac{1}{4}$—as near as we can approximate—giving us the
greatest possible theoretical velocity in this case as $4\frac{1}{4}$ feet
per second.

The velocities already spoken of are the theoretical ones,
no allowance being made for friction, and they can very nearly
be obtained through a short, smooth, taper nipple or nozzle
when measured at its point of smallest diameter.

CHAPTER IV.

Easy Entry of Water into Pipes, etc.—Proper Shaped Points of Entry or Vena-Contracta—Table of Quantities of Water in U. S. Gallons that will pass through a Short Pipe Two Diameters Long after being Led to It through a Vena-Contracta or Easy Point of Entry.

ACCORDING to all accepted authorities on hydraulics, the efflux through a circular aperture in a thin plate is only .615 of the theoretical flow, on account of the convergence of the current at a short distance outside the plate. We, however, have nothing to do with such conditions, unless it should be to roughly calculate the time a vessel would take to become empty through a plug-hole, and which would be out of place here.

When an aperture is through a considerable thickness or through a short parallel tube projecting outwards, whose length is not less than twice its diameter, the discharge has been found to be greater than when it is through a plate, and although a contraction of the water takes place it is less than in the former case, reducing the water passed to a little over .8 of the total theoretical quantity due to the head and aperture. This loss is due to the entry of the water into the pipe,

there being a reduction or contraction of the water by conver-
gence of its particles which reduces the area of the stream for
a short distance within the pipe, and as the velocity at this
reduced area is the theoretical one, it stands to reason the
amount of water passed is proportional only to the area of the
contraction compared to the area of the pipe.

The loss, therefore, due to the entry into the common form
of pipe must be taken as two-tenths of the whole quantity that
would be ordinarily supposed to pass, and must be considered
separately from the loss due to friction in a long pipe, and
must be added thereto and also to the loss for bends, elbows,
etc., when the latter is known, as will be explained later.

When a pipe enters or passes in through the side of a
reservoir or boiler for a short distance the loss caused to the
flow of water by entry is even greater than with a pipe flush
with the inside of the tank or boiler, and this loss has been
found by experiment to be over .3 of the whole, decreasing
the flow of the water one-eighth over a pipe that is flush, and
for this reason pipes should never be carried through the side
of a boiler or through a junction or fitting so as to make a
projection ; unless the obstruction to the flow is no objection or
that there is some object of greater importance to be obtained.

When the water leaves the side or top of a boiler through
a tapered circular nozzle, the loss by entry is less than when
the pipe is parallel at the commencement. When this nozzle
or truncated cone has a length of half its greatest (or base)
diameter, and its smallest diameter .784 of its base, the flow of
water will be augmented as it passes the smaller end, until it
approaches to within less than .05 of the theoretical flow ; and

if the curve of the side of the cone is 1.22 of the diameter of
the pipe, as shown in Figure 18, the loss will be reduced to
about .025 of the theoretical, or a quantity almost too small to
take into consideration in ordinary calculations.

If the smallest diameter of the cone, therefore, forms the
area of the flow-pipe the loss of flow by entry is reduced to a
minimum, and Figure 18 gives probably the best practical pro-
portions for points of entry into pipes or departure from boilers

FIGURE 18.

or large fittings, and is the proper form and shape for boiler
outlets ; and it also could be used to advantage whenever it
became necessary to use enlargements or contractions of a
pipe, as abruptness in the contractions affect the flow detri-
mentally by increasing friction, and for that reason, even
with the best form of contracted vein, a coefficient of .05
should be allowed for entry in close calculations, even with
the best form of vein considered.

Figure 19 shows the *vena-contracta* carried to the extreme. It makes a trumpet-shaped point of entry, which looks well and symmetrical, but withal little, if any, more water will pass into it under the same pressure than will into a vein similar to the one shown in Figure 18, and this fact should be enough to impress on us the advantage derived by having the ends of all wrought-iron pipe, or in fact any pipe for hot-water apparatus, reamed to a thin edge with a triangular or conical

FIGURE 19.

reamer whose length is just twice its base, as shown in Figure 19½. In thick pipes, or ones of small diameter that are relatively thick, enough can be taken from them in this way to almost give the best form of *vena-contracta*, and it will be of immense advantage for elbows and all fittings, not excepting couplings.

The accompanying Table No. I. gives the greatest theoretical quantity of water in U. S. gallons that will pass through a short tube whose length is about two diameters (as shown in

TABLE No I.—Table of total theoretical flow of water through short pipes under ranges of difference of pressure in heating apparatus.

HEAD OF WATER IN INCHES.

U. S. GALLONS PER MINUTE.

D²	Diameter of Pipe in Inches.	¼	½	1	2	3	4	5	6	7	8	9	10	11	12
1	1	2.0	4.06	5.8	8.8	10.0	11.57	12.95	14.17	15.32	16.37	17.37	18.3	19.15	20.
1.5625	1¼	4.5	6.33	9.04	12.76	15.6	17.05	20.2	22.0	23.89	25.55	27.09	28.54	29.87	31.25
2.25	1½	6.5	9.10	13.0	18.4	22.5	26.03	29.13	31.88	34.85	36.83	39.08	41.17	43.10	45.
4	2	11.6	16.24	23.2	32.72	40.	46.28	51.80	56.68	61.28	65.48	69.48	72.12	76.6	80.
6.25	2½	18.12	25.37	36.35	51.12	62.5	72.31	80.93	88.56	95.75	102.31	108.46	114.37	119.69	125.10
9	3	26.1	36.54	52.2	73.62	90.00	104.13	116.55	127.53	137.88	147.33	156.33	162.27	172.35	180.00
16	4	46.4	64.96	92.8	130.88	160.00	185.12	207.20	226.72	245.12	261.92	277.92	292.84	306.40	360.00
25	5	72.5	101.5	145.	203.5	250.0	289.2	323.75	354.2	384.0	409.2	434.2	451.5	478.7	500.
36	6	104.4	146.16	208.8	294.48	360.0	416.52	466.20	510.12	551.52	589.32	625.32	649.08	689.40	720.0
49	7	142.1	199.00	284.2	400.82	490.0	566.93	634.55	694.33	750.68	802.13	851.13	896.7	938.35	980.0
64	8	185.6	259.84	371.2	523.52	640.0	740.48	828.80	906.88	980.48	1047.68	1111.68	1171.2	1295.6	1280.0
81	9	234.9	328.86	469.8	662.58	810.	977.17	1048.92	1147.77	1230.9	1325.17	1406.97	1482.3	1551.15	1620.0
100	10	290.0	406.00	580.00	818.	1000.	1157.	1295.	1417.0	1532.	1637.	1737.	1830.	1915.	2000.
121	11	335.9	456.26	651.8	990.6	1213.0	1435.7	1566.9	1715.1	1854.3	1981.4	2102.4	2214.3	2314.7	2420.0
144	12	497.8	590.00	835.70	1177.92	1440.	1666.08	1864.80	2030.48	2206.08	2357.28	2501.28	2635.2	2757.60	2880.
	Velocity in feet per second....	1.16	1.64	2.32	3.32	4.01	4.68	5.18	5.67	6.13	6.55	6.95	7.32	7.66	8.03

Figure 18), provided the water is led to it through a contracted vein (termed *vena-contracta*) as there shown.

The table is calculated by the simple formula,

$$G = \frac{V \times d^2}{.4}$$

in which G is the quantity in U. S. gallons, d^2 the square of

FIGURE 19½.

the diameter of the pipe in inches, and .4 the part of a minute required for the passage of one U. S. gallon, with a velocity of one foot per second through a 1-inch diameter round pipe.*

---

* For British gallons the division .5 is to be used instead of .4, both of which are close enough for our purpose.

CHAPTER V.

Passage of Water through Pipes—Common Parallel-Shaped
Point of Entry to Pipes—Table of Quantities of
Water in U. S. Gallons that will Pass through
a Common Nipple Two Diameters Long.

FIGURE 20 shows the common parallel-shaped point of
entry found in ordinary practice. The water, in entering
such a pipe, contracts to about .9 of the diameter at *d*, a short
distance within the pipe. This lessens the quantity of water that

FIGURE 20.

would pass the pipe under a proper shaped point of entry to
.81 of the theoretical quantity, for the reason before explained;
as the velocity at its greatest contraction is that due to the

pressure only. This leaves it, then, that the velocity in the pipe beyond the contraction depends on the number of gallons that pass the contraction, and as this is but .81 of the whole, both the velocity beyond the contraction and the quantity will be correspondingly reduced to a little over .8 of the theoretical, or what can be obtained by Table No. I., when the proper shaped point of entry is used. It is commonly taken as .8, however, and on this basis the Table No. II. has been calculated.

Table No. II. gives the head of water required for entry into the various sized parallel pipes with square ends from one to twelve inches inclusive for the different quantities of water in U. S. gallons given in the body of the table, for pressures varying from ¼ to 12 inches of water-head. In other words, it gives the quantity of water that will pass through a short nipple, under the given pressures, with square ends, and does not include the head required for friction of longer pipes. The use of these tables will become obvious as we proceed.

In reality the commercial pipe standards are somewhat larger than the actual diameter, but this is not taken into consideration in the tables, as the ends of pipes are seldom carefully reamed ; the general practice being to cut them with a wheel-cutter, which gives them some contraction. So, for this reason, the nominal size of the pipe is taken as d^2, therefore the tables are for nominal dimensions of fairly clean standard pipe and not for actual sizes, which are a little larger in all cases, except for 2½ and 8 inch pipe, which happen to be a little under the nominal size ; if they are made of standard thickness.

TABLE No. II.—Heads of water required for entry into various sized parallel pipes with square edges for number of U. S. gallons given in body of table.

HEAD OF WATER REQUIRED IN INCHES.

Diameter of pipe in inches.	U. S. GALLONS PER MINUTE.													
	½	¾	1	2	3	4	5	6	7	8	9	10	11	12
1	2.3	3.22	4.6	6.54	8.0	9.25	10.36	11.33	12.25	13.1	13.89	14.72	15.32	16.00
1¼	3.6	5.04	7.2	10.2	12.5	13.6	16.0	17.6	19.11	20.4	21.66	.....	23.89	25.00
1½	5.1	7.14	10.2	14.72	18.00	20.8	23.3	25.50	27.88	30.6	31.26	33.00	34.58	36.00
2	9.2	12.88	18.4	26.17	32.00	37.00	41.44	45.34	41.00	52.6	55.58	57.70	61.28	64.00
2½	14.5	20.30	29.0	40.9	50.0	57.84	64.80	70.84	76.6	82.00	86.76	91.50	95.75	100.00
3	20.8	29.19	41.7	58.94	72.00	83.2	93.24	102.53	110.3	118.7	125.06	129.80	137.88	144.00
4	37.1	51.94	74.2	104.8	128.	146.5	165.76	181.36	196.1	200.00	222.30	234.27	265.12	288.00
5	58.0	81.20	116.	162.8	200.0	231.36	258.96	283.2	307.2	347.8	347.36	366.00	382.96	400.00
6	88.0	123.20	176.0	235.6	288.0	331.21	373.96	408.6	441.2	471.45	500.25	519.2	551.52	576.00
7	113.6	159.21	227.3	320.6	399.0	453.5	507.60	555.44	600.5	641.70	681.9	717.36	750.64	784.00
8	148.6	206.00	207.2	418.8	512.0	592.0	663.00	795.5	784.4	838.16	880.36	936.96	980.48	1024.00
9	187.9	263.00	375.8	530.0	648.0	781.76	839.2	918.24	985.8	1060.0	1125.6	1185.84	1240.92	1396.00
10	232.0	324.80	464.	654.4	800.0	925.6	1036.0	1133.6	1225.6	1309.6	1389.6	1464.0	1532.	1600.
11	263.9	365.0	521.4	702.48	970.4	1136.5	1253.5	1372.0	1483.4	1585.12	1681.9	1774.4	1851.76	1938.7
12	334.2	467.95	668.5	948.4	1152.	1332.8	1401.84	1644.	1764.8	1885.7	2000.8	2106.1	2266.0	2304.0

This table is found by taking $\frac{7}{10}$ of the theoretical quantity of water, as given in Table I., and is correct enough for ordinary purposes.

When the end therefore, of a pipe as it leaves a boiler is square and parallel and no regard paid to a proper form of point of easy entry, then eight-tenths only of the Table No. I. is to be taken as the number of U. S. gallons that will pass through a short, fairly smooth nipple, the power to move the remainder being consumed in entry ; in other words, instead of getting ten gallons through a short inch pipe or nipple in a minute of time, with a 3-inch head of water as per Table No. I., only eight gallons would be found to pass, as given in Table No. II., and so on through the whole table ; the remainder that might be expected to flow under such head being consumed in the effort of getting the particles of water into the pipe, over-coming the eddies and giving them direction.

If we divide the heads in Table No. II. into that which is consumed by entry and into that which remains to move the water, it will give us about three-tenths of the total head for entry and seven-tenths for the movement of the water. These amounts remain constants for the quantities of water given and for the size of pipes given, no matter how much greater the head at our disposal may be. To make this plainer we may say that so long as only thirty-two gallons of water enters a 3-inch pipe in a minute, regardless of what the total head may be capable of producing, three-tenths about of the 3-inch head in the table (No. II.) is the amount that is consumed by entry.

CHAPTER VI.

*The Loss to the Flow by Friction in Long Pipes—Table of
Friction Loss in Inches for 10-Foot Lengths of Pipe
for Various Diameters—How to Find Loss
of Head for Other Lengths, Etc.* •

IN long pipes the friction of the water against the insides of
the pipes as it passes must be considered. The insides of
the pipes are then often called the "rubbing" sides, or sur-
faces. In short smooth pipes, under small head or pressures,
the loss by friction is not very great when compared to the
whole, but in long pipes, passing large quantities of water, it is
considerable, as it increases in a ratio (about) directly as the
increase of length of the pipes and as the square of the
velocity of the water through the pipes.

The loss to the flow by friction in pipes of four inches and
upwards, under pressures and velocities such as are used in
cast-iron water-mains, is well established and known to
hydraulic engineers ; many eminent mathematicians having
considered the subject and formulated rules which some of our
more recent investigators have verified or corrected, and which,
in the hands of some of our hydraulic engineers, give results
surprisingly accurate.

For small tubes, however, under very small heads of water, and such as can be found in heating apparatus, there is no authentic data. Prony's formulæ is considered by Thomas Box as probably the most correct for small pressures and small diameter pipes. For my practice I depend much on the tables of G. A. Ellis, C. E., of Boston.

He has constructed a table for friction in small diameter pipes of various sizes from existing tables, reduced to pounds pressures for U. S. gallons and 100 feet length of pipes. With his kind permission I have reduced and interpolated such parts of his table (No. 5 in his book) as, in my judgment, would be likely to be of use to a hot-water engineer, to pressures represented by *inches of water-head* instead of pounds, and for a length of 10 feet, instead of 100 feet as in his table.

This table is No. III., and shows the approximate friction loss in inches of water-head as consumed in the straight pipes of an apparatus for each ten feet of their length for the different number of U. S. gallons of water given in the first column.

For instance, should the difference of temperature between the flow and return pipe of any part of an apparatus appear to warrant a flow of 10 U. S. gallons of water per minute in a 2-inch pipe, .324 inch of the head will be consumed in each ten feet of the pipe in overcoming resistance to the water, and it will be lost as power. If the pipe is twenty feet long, twice as much of the total head—or .648 of an inch—will be consumed by friction, as in the case just cited ; but if five feet of pipe is used, half only of the .324 inch of water-head will be consumed, or .162 of an inch.

The loss of head by friction in very short pipes compared

TABLE No. III.—Friction loss in inches of water-head for each 10 feet length of different size clean iron pipes; discharging given quantities of water per minute.

FRICTION LOSS IN INCHES OF WATER-HEAD FOR EACH TEN FEET OF LENGTH.

Size of Pipe—Inside Diameter.

U. S Gallons Passed Per Minute.	¾".	1".	1¼".	1½".	2".	2½".	3".	4".	6".	8".	10".	12".	14".	16".	18".	20".
1	.4	.1	.033	.019	.003											
2	1.6	.4	.13	.052	.012											
3	3.6	.9	.297	.117	.028											
4	6.4	1.6	.528	.208	.05											
5	8.91	2.26	.837	.324	.075	.01										
10	35.1	8.53	2.835	1.269	.280	.02	.01									
15	85.6	18.84	6.426	2.610	.550	.10	.04									
20		33.21	10.99	4.482	1.144	.17	.001	.01								
25			17.28	7.074	1.773	.400	.160	.04								
30			24.7	10.128	2.457	.567	.27	.061								
40				17.61	4.32	.185	.41	.09								
50				27.	6.558	1.275	.60	.16								
75					14.364	2.187	.998	.243	.009							
100						4.86	1.998	.510	.035							
135						8.64	3.537	.801								
150						13.203	5.873	1.336								
200						18.0	7.695	1.867	.135							
250							13.554	3.294	.200	.189		.027				
300								5.101	.270	.243	.081	.036				
500								7.182	.450	.675	.108	.108	.045			
750									.702	.999	.243	.210	.090	.078		
1000									.999	1.437	.486	.351	.210	.331	.054	
2000									2.592	2.538	.864	1.383	.674	.618	.097	
3000									5.067		3.321	2.997	1.390	.730	.4000	

to the loss of head by entry is small, but as the pipes become longer the friction loss increases about as the length of the pipe, whereas the loss by entry remains the same, so that a point is soon reached where the loss by friction is greater than the loss by entry. This point may be roughly placed at between 50 and 60 diameters of the straight tube.

Let it be borne in mind, therefore, that in a short tube the loss of head by entry may be a large percentage of the whole loss, but that in a long tube it may be comparatively small ; the loss by friction alone becoming great enough to use up the greater part of the whole head at our disposal.

With our subject, however, the loss by friction of straight pipes will be generally comparatively small, with small velocities and large diameters, as an inspection of the table No. III. will show, but it also shows how rapidly it increases as we attempt to use small diameter pipes and try to get a given quantity of water through them by an increase of pressure.

Our table, therefore, may be likened to a table of resistances, and it can be used to determine approximately the comparative size of flow-pipes for an apparatus in which the resistance is to be nearly alike. For instance, it will be noticed that when one gallon of water passes through 10 feet of 1-inch pipe in a minute the resistance is about $\frac{1}{10}$ of an inch of water-head, and that nearly 2 gallons will pass through the same length of $1\frac{1}{4}$-inch pipe with the same resistance, 3 gallons through one $1\frac{1}{2}$-inch pipe, 5 gallons through a 2-inch, 30 gallons through a 4-inch, 500 gallons through a 10-inch, and so on through the table ; all giving a resistance of only $\frac{1}{10}$ of an inch of water or thereabout.

It stands to reason, therefore, that if the 10-inch pipe will pass 500 gallons with so small a loss of head that 100 *two*-inch pipes may flow into it, each passing 5 gallons, and the resistance in all will be alike ; or they may all take supply from it as they would in the flow-pipe of an apparatus.   Of course, if the pipes are all doubled in length, the resistance is doubled also, but what I wish to call attention to in the table is, that lines of equal resistance may be traced approximately through it for pipes of about the same length, though for different diameters, and that hereafter in proportioning the size of pipes for apparatus this fact may be made use of.

CHAPTER VII.

*Loss of Head or Pressure by the Friction and Resistance of
Elbows—The Division of the Total Resistance into its Ele-
mentary Parts—Great Loss by Short Radius Common
Elbows — Saving by Long Radius Elbows —
Saving by Smooth Elbows—Resistance of
Return-Bends — Resistance Caused by
Couplings — Resistance Caused by
Globe, Angle and Gate Valves.*

THE loss of head in an elbow or bend should be divided
into three parts when we intend to make a study of the
·subject : (1) That due to change of direction of the water alone ;
(2) that due to friction alone, the same as in any pipe ; and
(3) that due to eddies caused by enlargements or contractions
of the currents, such as exist when common screwed elbows
are used that have pipes within them with square ends forming
sharp shoulders against the passage of the current.

The *first* applies to all bends whose radius is less than five
times the diameter of the pipe ; but when the radius is five
times or greater, with smooth bends the loss of head for
change of direction becomes so small that it may not be con-
sidered, as it practically becomes nothing.

The *second* (friction against the sides) applies to all bends, and, in fact, to all pipes, etc., without regard to shape, and it must always be considered as equal to the head consumed by the same length of straight pipe of the same diameter and character.

The *third* applies only to cases where the diameter of the bend or elbow is larger than the diameter of the pipe and has shoulders and threads, and it is greatest with square-ended pipes and least with pipes whose point of entry is easy, with the edges cut to a knife-edge and the angle of the side about as shown by Figure 23, and it does not exist at all in smooth bends of equal diameter throughout.

The *second* and *third* quantities above mentioned also apply to straight-screwed couplings or sockets and tees, and in them has about the same value as in elbows ; but couplings being straight of course there can be no loss for change of direction.

The loss of head for change of direction alone in elbows differs with the angle. Weisbach's formula is the one most used, but it is difficult of application by practical men, and was presumably founded on the loss of head in fairly smooth bends in large water-pipe. If we had special fittings for hot-water work, somewhat like the Durham Company's special fittings for wrought-iron soil and waste pipes, in which the square ends of the pipes are screwed against shoulders in the fittings, or nearly so, and with the diameter of the elbow or tee no greater than the pipe, then we could, with considerable accuracy, determine the loss of head by a bend or elbow, as we would have little more than change of direction and friction to consider ;

but with our present common elbows and tees, reasonable approximations only can be formed.

The late Robert Briggs was of the opinion that a common elbow (90 degrees), with a radius of about three-fourths the diameter of the pipe, would use as much of the head for change of direction as a pipe of the same nominal diameter thirty-eight diameters in length would use in friction while passing the same quantities of water or other fluid.

Deductions from the tables of Mr. Thomas Box also seem to confirm this, for what he calls "quick bends," or ones whose radii are about 1½ diameters of the pipe (or double the radii assumed by Mr. Briggs), give a resistance of about ¼ only (for change of direction) of what Mr. Briggs finds, and as this very nearly represents the ratio in which the resistance should decrease as the radii increased, we may reasonably assume that our common elbow will not use more head for change of direction than would be used by friction in 38 diameters long of the same pipe, and that this is the maximum. When the bend has a change of direction of 45 degrees, or only one-half of 90, then the loss per change of direction is only half.

It might be well to mention here, that, although the loss for change of direction in two smooth 45-degree bends only equals the loss in one 90-degree elbow, the total loss in two ordinary 45-degree elbows is much greater than in the one of 90 degrees, on account of the extra nipple, double the number of the enlargements and contractions of the currents and the extra number of square ends of the pipes, and that a much greater loss does ensue from the nippling of two 45-degree elbows together than will follow with one common elbow of 90 degrees.

The *second* division of the loss of head by elbows relates to friction only, and in that case the length of the bend through its centre line is taken and treated as so much straight pipe only.

The third division of the head lost by elbows is, as before stated, on account of the enlargement of the current when it enters the elbow and its subsequent contraction again to enter the pipe as it flows along, making a new point of entry.

There appears to be no question but that we should consider the action of the water in an enlarged bend nearly the same as when it leaves the boiler, and that a fresh point of entry, with its attendant loss, occurs each time. With favorable points of entry this third division of the head that is lost or consumed may be very much reduced, but with square ends there is as much of the head lost each time as is equivalent to $\frac{3}{10}$ of the heads given in Table II., and this with very low pressures, such as is to be found in hot-water apparatus, is too considerable to be neglected.

On the subject of entry, Mr. Briggs considered that as much head was used at entry as was used by 58 diameters of the pipe, and about the same deduction may be drawn from a study of Mr. Box's tables for small diameter pipes.

From all this, therefore, if we are led to take the extreme view of all the conditions, we are then bound to consider that a short common elbow uses as much head as 38 diameters of the pipe for change of direction alone, and that for entry, with ordinarily fitted square-ended pipes, we must add 58 diameters more, and it points to the fact that the total loss of head from all causes in a common elbow must be about equal to the loss from friction in 100 diameters long of the same

pipe ; at which rate a 2-inch elbow will consume as much head as 200 inches, or 16⅔ feet, of 2-inch pipe passing equal quantities of water.

This, of course, is the extreme view of it, and the rule may not hold true with large diameter pipes, as relatively they are not as thick as small ones at the ends, nor are the enlarge- ments of the elbows relatively as great, though, presumably, we should apply it to all pipes smaller than four inches with common elbows.

With such diameter pipes and elbows as we ordinarily have to deal with in a heating apparatus, however, if we accept this as correct, we will be probably on the safe side and may have some little to spare when the radii of our elbows are no less than the three-quarters the diameter of the pipe (say a com- mon elbow).

As the radius increases, however, the resistance decreases, so that in an elbow of 5 diameters radius, but otherwise a common screwed elbow, we have only the resistance to the entry of the water into the pipe, plus the loss by friction, to consider, which reduces the head consumed to be equal that lost by a straight pipe 62 diameters long.

If, on the other hand, we have a short common elbow, we will have (1) a resistance equal to 38 diameters of the pipe for change of direction, and (2) if we take the trouble to ream the pipe ends carefully the resistance to entry may be reduced very much below the value of 58 diameters given to it by Mr. Briggs, so much so that in thick pipes it may become practically nothing, and probably reduce the *total* resistance to less consid- erable than a straight pipe 50 diameters long will give ; as a

perfect shaped point of entry would reduce it to 38 diameters —plus something for friction, which even in a common elbow is less than four diameters of pipe will cause. Should the elbow be a long bend, however, as shown in Figure 21, then the first factor (for change of direction) is reduced to practically nothing, and the second is done away with altogether, so that friction alone remains and the resistance then is 7.8, or the length

LEAST RADIUS
THAT WILL CON-
-SUME NO HEAD
FOR CHANGE OF
DIRECTION

FIGURE 21.

of the bend in diameters of the pipe, which reduces it to the same value as so much straight pipe.

To make this more comprehensive, I introduce several diagrams of elbows and pipe, giving each part its value in *diameters*, and by diameters I mean the amount of head that would be consumed by a straight pipe one diameter long.

Let Figure 22 be a common elbow with a radius of three-quarters the diameter of the pipe, with square-ended pipes entering it as shown.   Then we will have 38 diameters for change of direction (C D) + 58 diameters for entry (E) + 4 diameters for friction = 100 diameters, as the value of an elbow joining pipes as in Figure 22.

FIGURE 22.

Let Figure 23 be a common elbow, with a radius of three-quarters of the diameter of the pipe—same as in Figure 22—but with the ends of pipes entering it carefully reamed to an easy entry with a reamer, as shown ; then we will have for a change of direction (C D) 38 diameters + nothing (or nominally nothing) for entry (E), + 4 diameters for friction = 42 diameters.   If the pipe is not thick enough to ream until

it gives the proper depth of an easy entry, why then, we must use our judgment and add something to the 42 diameters, and as the roughness of some uncovered threads in the fittings will always play some part in adding to the resistance, we may, perhaps, be justified in calling the value of Figure 23, as a whole, 50 diameters.

FIGURE 23.

Let us now consider Figure 24. It is a fairly long diameter elbow, the radius being 1½ diameters of the pipe, and into it we screw a pipe the same as that shown in Figure 22, by the dotted lines at the edges. Incidentally it is explained elsewhere that to double the radius of a bend is the means also of lessening the head required for change of direction to about one-quarter what it would be for the shorter radius—

in other words, the head required decreases somewhat faster than the inverse of the square of the radius—therefore, for change of direction in Figure 24 we have, say, $\frac{3.8}{4}$ — $9\frac{1}{2}$ diameters, plus *no* diameter for entry, plus 5 diameters for friction (the elbow being longer than before) — $14\frac{1}{2}$ diameters, to which if we add 8 diameters (as we did in Figure 23, for the

FIGURE 24.

same reasons as there given), will bring the value up to $22\frac{1}{2}$ diameters. If we go further and lengthen the radius of elbow to 5 diameters, then C D will become nothing; E will be, say, 8, as before, and F 7.8 — 14.8.

If we make one more diagram (Figure 25) with the elbow and pipe the same diameter throughout, the radius of the

elbow being 9½ diameters, then we have C D — 9½ + E
(— o.) + F (— 5.0) — total, 14.8 ; and if this elbow is further
drawn out, so as to equal 5 diameters radius, then we have
C D — o. + E — o. + F — 7.8 total.

These are approximations that I have reason to believe are
not far wrong, and, though perhaps not absolutely correct,

FIGURE 25.

gives the practical man or mechanic *some definite idea of what
the resistance of an elbow really amounts to*, and shows how
greatly it can be lessened and made almost nothing by proper
radii of elbows and easy points of entry.

With a return-bend, the loss for change of direction is just
double what it would be for a 90-degree elbow.   The loss for
entry will be no greater, but the same for similar fittings and

ends, while the loss for friction will be about doubled, as the bend is about twice as long as an elbow.

The shortest elbow or bend must have a radius of one-half its diameter, and if the back of it is round, the loss of head for such an elbow is about sixteen times as great as it would be in a bend of four diameters, and eight times as great as in one of one diameter. So that the advantage to be obtained by lengthening the radii of common fittings for hot-water work ever so little is obvious.

Therefore, if we consider the total loss of a common elbow as equal to that caused by 100 diameters of a pipe—being made up of 38 for change of direction, 58 for entry, and the remainder for friction—the resistance of a common close return bend will be equal to about 76 diameters for change of direction, 58 for entry into a square-ended pipe, and, say, 8 for friction $=$ 142 diameters.

If the radius of the bend is doubled, the 76 for change of direction becomes about 19. If an easy entry is made the 58 drops very rapidly, say to 8 again, and friction is increased slightly on account of the increase of length, giving the value, say, of 40 ; a most decided gain.

In box-coils for hot-water work it is probable that return bends of greater radii than one diameter cannot be used, but by care their resistance value may be reduced to equal that of 50 diameters of the same pipe. So that in an inch box-coil four feet long the length of pipe and the bend can be made to have equal values, whereas, by neglect, the resistance in the bend may be increased to three times as much as the resistance of the pipe.

It might be well to remark here that a common screwed coupling connecting two square-ended pipes of small diameters together has a resistance equal to about 60 diameters of the pipe it connects, and that by carefully reaming the edges of the pipe as shown in Figure 23 this can be reduced to practically nothing, or without doubt to a resistance of less than ten diameters.

All other fittings and valves cause resistance to the flow of the water. The resistance of a common globe-valve is probably little short of that caused by three common elbows, and in my judgment a common angle-valve will use as much head as two elbows. Straightway or gate valves, therefore, should be used in preference to globe or angle valves, but even they cause considerable resistance on account of the shoulders of disks and seats, etc. The butter-fly valves, therefore, are the ones that cause less resistance, and as absolute tightness is not required as a general thing, they should be used in flow and return pipes in preference to any others. I do not wish to create the impression, however, that ordinary gate or angle valves are not suitable for radiators, for with reasonable diameter inlets and outlets they are, and I cite the above simply for comparison and to show what may be gained by attention to details.

CHAPTER VIII.

Flow of water through mains of an apparatus.—(1.) To find the
total head when the quantity of water to be passed and the size
and length of pipe is given—(2.) To find the quantity of
water that will pass in U. S. gallons when we know the
total head at our disposal and the length and the diameter
of our pipe—(3.) To find the diameter a pipe should
be for a given discharge, under equal heads, with
another pipe, whose length, diameter, and dis-
charge are known — (4.) To find the dis-
charge by pipes of different diameter, the
head and length being the same.

TO find the total head when the quantity of water to be
passed and the size and length of pipe is given :

From the foregoing tables and what has been said about
friction and resistance in pipes and fittings it is not a very
difficult matter to determine the amount of head required for
any particular set of mains, when the quantity of water passing
and the size and length of the pipes are known, as we have
simply to refer to the tables.

Say we have a line of straight and level 4-inch pipe, 100
feet long (no provision made for easy entry), passing 50 gal-

lons of water per minute, from the side of a tank or boiler,
what will be the total head required? By Table III. the head
for *friction* of 4-inch pipe passing 50 gallons of water is .243
of an inch for 10 feet of length, and for 100 feet it is
.243 × 10 = 2.43 inches. Then by Table II. it will be found
that half an inch of water-head will be required to move 51.94
gallons of water through a 4-inch pipe without considering the
head for friction, which gives us a total of 2.43 inches for
friction, *plus* .5 of an inch for velocity, = 2.93 as the total head
necessary to move 50 gallons of water through a 4-inch pipe
100 feet long in a minute. In other and fewer words, the head
for friction is directly as the length of the pipe in 10-foot
lengths (according to the tables here given), and the head
for velocity is a constant, irrespective of length.

If we now put one common elbow into this pipe, such as
shown in Figure 22, we will proceed as in the example given
above, but instead of considering the length of the pipe as 100
feet, we will consider it 100 feet + 100 diameters for elbow;
which will be 400 inches, or 33.3 feet, making the resistance
equal to what it would be in feet 133.3 of straight pipe. Then
we will have $\frac{133.3'}{10'} \times .243'' + .5'' = 3.74''$ total head re-
quired.

If we had five elbows in a run of 100 feet of pipe, then our
problem would be, 100' of 4" pipe + 500 diameters (or 166.5)
= 266.5'. Then, $\frac{266.5'}{10'} \times .243'' + .5'' = 6.97$ as the total head
required for passing 50 U. S. gallons per minute. Of course,
when the elbows are better than the common, as explained

under "Loss of Head by Elbows or Bends," then fewer diameters must be considered and added as the value of the elbows.

By the above simple means we can always determine the amount of head necessary to produce a certain result in pipes that have been already run or set up. In other words, should we go into a building that had been already piped, or should we have the plans of a job before us, with the lengths and sizes marked, and wished to know if the diameters of the pipes were ample or not for a given velocity and quantity, we would proceed as above and determine the total head required as per plan; when it would be manifest whether the pipes were greater or less than they should be, knowing the greatest head at our disposal which can be obtained by the aid of the diagrams Figures 14 and 15, pages 42 and 43.

(2.) To find the quantity of water that will pass in U. S. gallons when we know the total head at our disposal and the length and the diameter of our pipe.

This is one of the most important points to a designer of hot-water apparatus. Where the total head at our disposal is known we are at a loss to know how much of the head is required to overcome the friction and how much is left to produce motion in the water. This does not admit of a direct solution, but we can take advantage of the fact that the discharge by any pipe or series of pipes and fittings is proportional to the square root of their heads (and that *conversely* the head is proportional to the square of the discharge), and therefore all we have to do is to assume a discharge for our pipe, and after having found the head necessary for the

assumed discharge (as in 1, pages 76 and 77) apply the above rule thus :

$$\text{Assumed discharge} \times \text{by square root of required head} \div \text{by square root of assumed head.}$$

Thus, say we want to find the number of U. S. gallons that will pass through a 4-inch pipe 100 feet long under *one* inch of total head ; we will commence by assuming, say, 50 gallons, and already by (1) we have found that 50 gallons required a total head of 2.95 inches of water, which we will take now as our assumed head : therefore we have quantity looked for =

$$\frac{50 \text{ gallons} \times \sqrt{1''}}{\sqrt{2.93}}$$

which is equaled by

$$\frac{50 \times 1}{1.70} = 29.4 \text{ U. S. gallons}$$

as the quantity that will pass under one inch of total head through a 4-inch pipe 100 feet long.*

Having now found the quantity of water that will pass through 100 feet of 4-inch pipe under a *one-inch* head, it is important, also, that we should be able to establish the diameter of a pipe of the same length and under the same head that will discharge some other desirable or fixed quantity of water.

First we found the total head for an assumed quantity, the *length* and *diameter* being known (1). Then we found the

---

* Those who do not wish to work out the square roots of numbers can find tables in Trautwine's or Haswell's Pocket-Books that give the desired information.

actual quantity that would pass through the same pipe under the smaller head of one inch (2), and now we want to establish a new diameter—the length remaining the same—that will pass, say, 50 gallons, as at first assumed (1), but to pass it with only *one inch of head* (2).

This can be done by taking advantage of the fact *that the diameters of pipes vary directly as the fifth root of the square of their discharges,* head and length remaining the same ; in other words, the diameters of pipes are proportional to the $\sqrt[5]{\text{discharge.}}$ *

Thus our third problem is :

(3.) To find the diameter a pipe should be for a given discharge, under equal heads, with another pipe whose length, diameter, and discharge are known.

In our last problem (2) we found that 29.4 U. S. gallons would pass through 100 feet of 4-inch straight pipe under a total head of one inch.   Let us now see how large a pipe of the same length it will take to pass 50 U. S. gallons under one inch total head.

The sum, according to the rule given, resolves itself into a simple proportion, thus :

| The fifth root of the square of 29.4 gallons | : | a diameter of 4 inches | : : | the fifth root of the square of 50 gallons | : | × inches |

— the new diameter in inches.

---

* As it is a difficult thing to extract the fifth root of a number, and as practical men rarely wish to go into abstract calculations, I will refer them to Trautwine's Engineering Pocket-Book, where they will find tables of *fifth roots and fifth powers* that will obviate tedious calculations and, presumably, avoid clerical errors.

Or the following simple formula :

$$\frac{50.0 \stackrel{\text{2.\sqrt[5]{\text{gallons.}} \quad \text{inches.}}}{\times 4}}{\underset{29.4}{\text{\sqrt[5]{\text{gallons.}}}}} = 4.9 \text{ inches,}$$

the new diameter.

It probably is not plain to many very practical men how this answer is obtained, so we will endeavor to go over it in a simpler manner still.

When the discharges from pipes are in the ratios of 1, 2, 3, 4, 5, 6, etc., the diameters will be in the ratio of 1., 1.32, 1.55, 1.74,+ 1.90+, 2.05—, etc.

These ratios of the diameters may be picked out of Trautwine's tables of Fifth Roots and Fifth Powers by squaring the discharges and substituting the answers thus found for the "Power" in the tables; opposite to which is the Number or Root that is the ratio of the diameter.

In our case, then, we have 29.4 and 50 gallons respectively that we must first square and then find the fifth root of the respective squares.   To get the fifth root of the square of either of these numbers will take us far beyond the limit of the tables of reference cited heretofore, but we may (without much error) use some common divisor, such as 10, and reduce the discharges to 3 and 5 respectively and then proceed as above.

Thus, 3 squared $=$ 9, the fifth root of which is 1.55.

Then, $5^2 = 25$, the fifth root of which is 1.9.

Then, $1.55 : 4 : : 1.9 : \times^{\prime}$

$$1.9$$

$$1.55)7.60(4.9 \text{ inches.}$$
$$6.20$$

$$1.400$$
$$1.395$$

$$5$$

Thus the diameter sought is very nearly five inches, and as there is no 4.9-inch merchantable pipe the nearest practical size larger (5-inch) should be used.

(4.) To find the discharge by pipes of different diameter, the head and length being the same.

This is necessary for the engineer when he has found the capacity of one set of pipes and wishes to know the capacity of another set, either larger or smaller in diameter but with the same head and length.

The rule for this is, that the discharges from pipes of equal lengths and heads, is in the ratio of the 2.5 power of the diameter or the converse of the foregoing (3). The symbol "2.5 power" means the square root of the fifth power of a number as here written.

For the reason given before to practical men, a table of the 2.5 powers of numbers can be used much more readily than to attempt to find the root and raise it to its fifth power, therefore I refer the reader to Trautwine's tables again in this matter, and, by a study of the same, it will show that with the diameters in the ratio 1, 2, 3, 4, 5, 6, etc., the ratio of discharge will be 1., 5.65, 15.59, 32., 55.9. 88.18, and so on.

Let us, then, proceed to find the discharge by 100 feet of 6-inch pipe under a 1-inch head; the discharge by a 4-inch pipe of the same length and head being 29.4 gallons. This is simple proportion again, so long as we have the ratio the discharge bears to the diameter, and this can be taken from the tables of the "Square Root of Fifth Powers" before mentioned, or the above ratios may be used as far as they go. Thus:

$$\frac{2.5 \text{ power}}{\text{of known}} : \frac{\text{known}}{\text{discharge}} :: \frac{2.5 \text{ power}}{\text{of required}} : (\times) \text{ discharge} =$$

(in this case) 4″ : 29.4 gallons :: 0″ : (×). Then substituting the ratio for the diameters we have :

Ratio. Gallons. Ratio.

32 : 29.4 :: 80 : ×
     80.0
   _____

32)2350.(73.45 + gallons
   224
   ____
   110
    96
   ____
   140
   122
   ____
   180
   150
   ____
    30

or nearly 73½ U. S. gallons that will pass through a 6-inch pipe 100 feet long under one inch of head.

CHAPTER IX.[*]

*How to Compute Radiating Surfaces—Experiments of Tredgold
and Hood on Warming Surfaces — Mr. Barrus's Experi-
ments with Steam Radiators and Their Probable
Bearing on Hot-Water Surfaces—Cooling Effect
on Window Glass — Value of Average
Vertical Radiator Surface.*

BEFORE we can proceed to construct and settle the proper
sizes for the mains and other pipes of a hot-water appa-
ratus, we have first to determine the size of the radiators or
coils that we must use, and the quantity and the heat of the
water that we must pass through them.

To keep a room warm by artificial means we must add as
much heat to its walls and the air enclosed within them,
through the medium of our radiators or coils, as is given off
from the same room by the glass of its windows, its walls, the
air admitted and extracted for ventilation, as well as the cool-
ing done by accidental causes, such as leaky windows, doors,
etc. In well-built houses the latter (or accidental) factors
become small. In poorly-built ones they are often large, and
in frame or wooden houses they are, as a general thing, greater
than in brick houses.

---

*Before applying the rules in the foregoing chapter to the question of deter-
mining the size of flow pipes, etc., for ordinary conditions of practice, it is neces-
sary that the reader should become acquainted with the subject of the loss of
heat from radiators, so as to determine the amount of water to be passed
through them in an hour or any other given time; hence the introduction of
chapters IX and X at this part of the book.

To find the amount of radiator surface necessary to coun-
teract the effect of windows and walls, it is necessary for us to
have a good conception of the amount of heat lost through
the windows and walls.   It is also necessary to know how much
heat will pass from the water inside our pipes to the air of the
room for given surface of the pipe—say one square foot.

Heat from a room or building is lost by radiation, conduc-
tion, and convection.   From a philosophical point of view, it
would be a nice thing for us to know how the sum total of the
heat lost is divided between these three methods of transmis-
sion, but for our purpose it is only necessary to know what the
total amount is and how to find it—at least approximately.

At low temperatures, or such as we are likely to have to
deal with in hot water and air questions, the heat given off by
radiation is less than that given off by convection and other
causes.   Above 400° Fah. the heat given off by radiation
alone becomes greater, but of this we have nothing to do here,
though when speaking on the matter of boilers hereafter it may
be well to say something about it as bearing on their design.

Mr. Thomas Tredgold, C. E., in his work on "Warming
and Ventilation," the third edition of which appeared in 1836,
(after his death,) while speaking of the laws of cooling, says :
"If the surface giving off heat be different at different times,"
(having different temperatures only, he undoubtedly means,)
"the heat given off in a given portion of time will be directly
as the excess of temperature of the surface of the body giving
off the heat in gaseous media, or in any fluid that is kept in
motion."

This would be according to Sir Isaac Newton's theory of

the law of cooling, and though later investigators (Petit, Dulong, and others) have demonstrated that this is not absolutely true for even low temperatures, and that at very high temperatures it is erroneous, while we have, however, Dalton and Leslie as authority that for differences of temperature between *mean temperature* (40° Fah.) and 212° Fah., that it is correct enough for any ordinary purpose.

If we accept this, the quantity of heat given off will be directly as the surface and the difference of temperature between it and the media it is giving heat to.   This, however, holds true only of surfaces of a like description against which the air can come in contact and rub freely at all points, such as flat windows, flat walls, and flat or vertical radiators ; and by flat is meant surfaces that the air can come freely in contact with either as it rises or falls—one whose vertical plane is straight.

We are not far wrong, presumably, when we contrast for comparison the flat surface of a sheet-iron heater with the glass of a window, while taking the difference of temperature into consideration, and it was this I did when I adopted the empirical rule given on page 27 of " Steam-Heating for Buildings," which reads : " Divide the difference in temperature between that at which the room is to be kept and the coldest outside atmosphere by the difference between the temperature of the steam-pipes and that at which you wish to keep the room, and the product will be the square feet or fraction thereof of plate or pipe surface that is the equivalent of each square foot of glass or its equivalent in transmitting power."

According to this rule, if we desire to keep a room at 70°

Fah. when it is zero outside, with the temperature of the radiating surface 212° Fah., we have :

$$\frac{\text{Difference between temperature of room and outside temperature,}\ 70°\ \text{Fah.}}{\text{Difference between steam-pipes and air of room,}\ 142°\ \text{Fah.}} = .493\ \text{sq. ft.,}$$

or, say, one-half a square foot of plate surface.

Now, use has confirmed this rule as sufficiently near for practical purposes, with ordinary good radiators, either in vertical or horizontal coil form, when the length of the vertical pipe or loop is not greater than 30 inches, and with horizontal coils of 1-inch pipe not higher than eight in number.

This, of course, is only an approximate rule for use in direct radiation alone, and, with a liberal addition of from one-quarter to one-half to provide for air admitted accidentally, has always proved sufficient in low-pressure steam-heating.

Of course, the value of the walls, in addition to windows, as cooling surface must not be overlooked, and though we have only spoken here of glass, each 7 to 12 square feet of wall surface, according to its nature, will have a cooling power equal to a square foot of glass, and must be considered the same.

The above is the first and simplest way of finding direct radiating surface for rooms. The example taken, however, was for radiator surface at a temperature of 212°. This is too high a temperature for low pressure for hot-water practice, and the writer, in his own practice, in designing for hot-water

apparatus, prefers to make his figures on the basis that the
water in the coils or heaters of the apparatus has a tempera-
ture of 140° Fah., and that the outside temperature is 30°, or
just below freezing point; then, as the temperature outside
goes down, to increase the temperature of the water in the
radiators or coils by keeping a stronger fire in the boiler.
This gives us :

(1) Temperature of air of room, 70° Fah. — temperature
outside, 30° Fah. = 40° Fah.

(2) Temperature of coils or heating surface, 140° Fah. —
temperature of air of room, 70° Fah. = 70° Fah.

(3) 40° + 70° = .571 as the part of a square foot of heat-
ing surface at 140° Fah. that will counteract the cooling done
by one square foot of glass or its equivalent, under average
circumstances, when the outside air is 30° Fah.

Of course, to make this a scientific equation, the relative
velocities of air-currents would have to be taken into consid-
eration, which would bring wind velocities into the question ;
that would so complicate matters—and that unnecessarily—
that no attempt will be made to do so, as, with a hot-water
apparatus under increased wind velocities, we have the same
means of increasing the efficiency of our surface as we do
under a lowering of temperature—namely, the increase of
temperature of our water within the limits of our initial coil
temperature (say 140° Fah.), and our maximum 212° Fah. or
the steam-making point under our atmosphere ; which gives
us a reasonable range of temperatures that is sufficient to carry
us down to a temperature of about 10° below zero outside.

The following columns show approximately the increase of

temperature of the surface to the decrease in outside temperatures, increased wind velocities not considered :

Temperature of surface.	Temperature outside.	Ratio of heating surface in square feet to a square foot of glass.
140° Fah.	30° Fah.	.571
157° Fah.	20° Fah.	.57
175° Fah.	10° Fah.	.57
192° Fah.	0° Fah.	.57
210° Fah.	10° below.	.57

This gives us the same ratio of hot-water surface as we would have of steam surface figured for the same conditions, and there is no good reason why we should use more surface for hot water than we should for steam, the surfaces having the same temperature. In "Steam-Heating for Buildings" the ratio is .49, because it was assumed the temperature outside was zero Fah. and the temperature of the pipe 212° Fah.; but here the calculations are based on the assumption that the air outside is 10° below zero, so that for low temperatures in the coils the surface may prove a little more efficient.

To this ratio of .57 of a square foot of pipe or plate surface to one of glass, or its equivalent of wall surface, from one-quarter to one-half more should be provided for warming air accidentally admitted and for loss of heat by sources other than the walls and windows, and the addition must depend on the character of the building and the judgment and experience of the designer.

Roughly, then, for hot water, a building will require a ratio of plate or pipe surface of from .70 to .85 to one of glass at the temperatures given in the first column in the table to maintain them at 70° Fah. by direct radiation when the air outside is of the temperatures given in the second column.

Mr. Thomas Tredgold, early in the present century, considered the question of loss of heat from heated surfaces in a very thorough manner, and, later, he was followed by Mr. Charles Hood on the same subject, both having the same object in view—namely, to find the value of radiating surfaces for warming buildings.

Mr. Tredgold found that 2.19 pounds of water cooled from 180° to 150° Fah. in a vertical tin cylinder in 46 minutes, the exposed sides of which were 79 square inches, when the temperature of the room was maintained at 55½° Fah. during the trial. This gave a mean difference between the air of the room and the surface of the cylinder of 109.5° Fah.

From this we have 2.19 pounds of water cooled 30° Fah. by $\frac{79}{144}$ of a square foot of surface in 46 minutes of time, which is equivalent to 65.7 heat-units for the time, or 85.7 heat-units for an hour of time, and 156.21 heat-units as what would be given off by one entire square foot of the same surface (tin cylinder) in an hour of time. This total heat, for a square foot of surface, for an hour of time, then, divided by the *mean* difference of temperature (109.5° Fah.) between the air and the surface of the cylinder equals 1.42 heat-units; the amount given off per square foot of surface per degree difference of temperature.

His *second* experiment was with a glass cylinder that held 2.125 pounds of water and had a surface of 71 square inches. It cooled from 180° to 150° Fah. in 31½ minutes in a temperature of 56½° Fah., which, by the same method of reasoning as we used before, gives 2.248 heat-units per hour per square foot of surface per degree (Fah.) difference.

His *third* experiment was with a sheet-iron cylinder—the surface being that of new sheet-iron unpainted—whose surface was 76.7 square inches, holding 2.14 pounds of water and cooled from 180° to 150° Fah. in 29 minutes, the temperature of the air of the room being 57° Fah. By the same reasoning and method of calculation used in the foregoing examples we can find that the sheet-iron gave off 2.35 heat-units per hour per square foot of surface per degree difference of temperature.

These cylinders were as nearly alike as they could be obtained in form and size and one cover fitted all. They were suspended by cotton threads, so little or no heat could be lost by conduction or contact, and the sides and bottoms were exposed to the action of the air, etc. The top was covered by about one inch in thickness of alternate folds of cotton and flannel, so that the loss of heat by this direction was very small.

A few days later when the experiments were repeated the iron cylinder had become rusted. This, Mr. Tredgold says, increased its efficiency in the proportion of 156 and 180; the rusted cylinder having the latter value when as a new one it' had the former. The experiments with the tin are of no value to us except to show that bright surfaces have a less value than

dull or slightly roughened ones.   Experiments with brass, etc., by other experimenters confirm this. The relative values of glass and iron, however, are of some value to us as showing how nearly they agree ; the iron being the better of the two, even when new and bright, and increasing in value as it becomes rusty.

It would be well to remark here that, probably, when surfaces become dusty, which they will in practical heating, they may deteriorate somewhat, and that it would be well to assume that what they may increase in efficiency by rusting will be fully offset by accumulations of dust, etc.

The form of Mr. Tredgold's cylinders—short, vertical ones—are, presumably, the best that can be devised for giving off heat. The same cylinders in a horizontal position would probably be found to be a little less efficient, and if they were to be increased in height, say two or three times, though used in a vertical position, it is only reasonable to suppose they would do less duty, for the very simple reason that the air in contact with the upper parts would have been warmed somewhat by the lower part as it passes upward, and, therefore, is not capable of extracting as much heat.   The same holds good of horizontal cylinders or pipes when placed one above the other ; each successive one, counting from the bottom upward. does less work than the one next below it.

According to the above relative values, therefore, of glass and iron, the empirical rule given above for finding heating surfaces by the window area, etc., is not without some scientific pretence, as the loss of heat through the glass of a window

can rarely, if at all, be greater than through the iron of the heaters for equal difference in temperatures or for proportional differences.*

* I do not draw the same deductions from Mr. Tredgold's experiments that he does himself, and, therefore, did not give his figures here, but substituted my own in the manner just shown; the summary of the matter being that the heat lost through glass would be 2.248 H. U., when that lost through iron would be 2.35 H. U.

CHAPTER X.

Experiments on Heating Surfaces to Determine the Units of Heat Given Off by a Square Foot of Surface.

TO go further with this subject, I will refer to experiments of Mr. Hood made more recently than Mr. Tredgold's, as he was not satisfied with the latter's deductions, and made experiments for himself. In his work on "Warming and Ventilation" he tells us that "to ascertain the velocity of cooling for a surface of cast iron, a pipe 30 inches long and 2½ inches internal diameter and three inches diameter externally was used. The ends of the pipe were closed by corks, which entered the pipe 1½ inches at each end, and the bulb of the thermometer was inserted into the water about three inches from one end. * * * The exposed surface of the pipe (including the surface exposed by the thickness of the metal at the ends) was 287.177 square inches. The quantity of water contained in it was 132.534 cubic inches, and the equivalent to be added to this for the specific heat of the pipe was 39.341 cubic inches, making the estimated quantity of water 171.875 cubic inches." The temperature of the room in which the observations were conducted was 67° Fah.

This pipe was presumably used on its side in the horizontal position (though this is not stated), and represented no doubt a section of an ordinary 3-inch cast-iron heating-pipe used at that time for green-house heating, etc.

He informs us the rates of cooling were tried with different states of the surface : *First*, when in the usual state of cast-iron pipes covered with protoxide of iron (fine rust) ; *second*, black varnished ; and *third*, with the varnish removed and two coats of white-lead paint substituted. He observed that the rusty surface cooled from 152° to 150° Fah., or 2 degrees, in 2.5 minutes, and that it cooled from 152° to 140° Fah., or 12 degrees, in 15 minutes. This is at the rate of the whole quantity of water or its equivalent cooling one degree in 1.25 minutes.

He took observations every *two* degrees fall of the thermometer, which give slightly varying results as to the rate of cooling. This variation may be due to errors in reading the scales or in errors in the thermometers, and a close study of the table of his experiments go to confirm the belief that for all practical purposes of house-warming the rate of cooling is very nearly directly as the difference of temperature between pipe or plate surface and the surrounding air.

With the black surface of the pipe black-varnished he found that to cool from 152° to 150° Fah. (2 degrees) it took 2.266 minutes, and that to cool from 152° to 140° Fah. (12 degrees) it took 14.533 minutes ; or, in other words, cooled an average of one degree in 1.21 minutes, his readings showing a slight increase of cooling as the difference between surface and air became less. If we take the average of six experiments

(1.23 minutes), progressing by two degrees, and correct the time observed on cooling the first two degrees by it, we have 2.42 minutes, instead of 2.266 minutes. This shows that the black-varnished surface is slightly more efficient than the rusty one—a little over three per cent.*

With the pipe with two coats of white-lead paint, the efficiency was less than with either of the others, but not as great as usually considered.

The cylinder cooled from 152° to 150° Fah. (2 degrees) in (observed time) 2.316 minutes, and it cooled to 140° Fah., or 12 degrees, in 15.366 minutes ; or, in other words, it cooled one degree in 1.28 minutes average.

Mr. Hood's summary of the matter is that 100 feet of varnished pipe, 103¼ feet of plain pipe, and 105¾ feet of white-painted pipe have the same values as heating surface. He does not, however, give as the values of these surfaces in *heat-units* per square foot per degree difference no more than Mr. Tredgold does, and as this will be very important to us hereafter when we desire to ascertain the quantity of water that must pass through a heater at a given time, to maintain some constant temperature, we will have to calculate it for ourselves by the same method of reasoning, etc., as we did in the case of the latter's experiments.

The surface of the experimental piece of pipe is given as 287.177 square inches, which is two square feet, lacking less than one square inch, and therefore we will call it two square

---

* In comparing these statements with Mr. Hood's table, note that the time here is given in minutes and decimals of a minute, while in the table it is given in minutes and seconds.

feet. The quantity of water actually contained in it was 132.534 cubic inches, and the equivalent in cubic inches of water that was to be added for the specific heat of the iron of the pipe, 39.341 cubic inches ; making the estimated value of the water and its envelope equal to 171.875 inches of water.

The water was cooled from 152° to 140° Fah. in each experiment, and therefore had a *mean* temperature of 146° Fah. The weight of a cubic inch of water at this temperature is 248 grains ; therefore we have

$$\frac{171.875 \text{ cub. in.} \times 248 \text{ grs.}}{7,000 \text{ grs. (1 lb.)}} = 6.089 \text{ lbs. of water.}$$

This water was cooled 12 degrees in the various times, which gives us $6.089 \times 12 = 73.068$ heat-units as the total heat given off in each case from two square feet of heating surface, or 36.534 heat-units per square foot.

The air of the room was 67° Fah. ; consequently the difference of temperature—or, in other words, the excess of temperature of the surface over the air—was 89 degrees.

The time for cooling the rusty cylinder was 15 minutes, or one quarter of an hour ; therefore we have :

$$\frac{36.534. \times 4}{89° \text{ Fah.}} = 1.642 \text{ heat-units}$$

per square foot per hour per degree difference. For the varnished surface it is 1.589 heat-units, and for the white-painted surface 1.552 heat-units.

To ascertain the effect of glass windows to cool the air of a room, Mr. Hood made experiments with a glass vessel as nearly as possible of the same thickness as ordinary window-glass. The temperature of the room was 65° Fah., and the surface of the vessel was 34.296 square inches, and it contained 9.794 cubic inches of water, including the equivalent for the specific heat of glass. ·He does not tell us the form of the vessel, which would be very important to know, but, presumably, it was rectangular, or at least had perpendicular sides, and, being small, represented an average effect in cooling, so that the deductions obtained are, presumably, fully equal to average conditions.

The average rate of cooling from 150° to 110° Fah. was found to be 1.176 degrees when the *mean* excess of temperature of surface was 65ᵛ Fah. above the temperature of the air, and the time 34 minutes.

The total quantity of water, or its equivalent, is found to weigh .3482 pound at a temperature of 130° (its mean temperature). This cooled 40° Fah. ― 13.93 heat-units for 34.296 square inches, or 58.48 heat-units for a square foot for 34 minutes, or 103.2 heat-units for an hour; divided by the mean difference in temperature $= \dfrac{103.2}{65°} = 1.59$ heat-units per square foot per hour per degree difference of temperature.

Mr. Hood's deductions from his experiment is to the effect, that each square foot of window-glass will cool in a minute of time 1.279 cubic feet of air as many degrees as the inside air is warmer than the external in a comparatively still atmos-

phere, but that when windows are exposed to the action of winds further experiments are necessary.

It is evident the cooling of air through glass, etc., depends on both the velocity of the air inside and outside taken together.

Nearly all the heat that is lost by air of rooms to cooler air through glass is lost by convection. The air inside the glass falls by loss of heat and increase of weight and follows the laws of a falling body. The velocity of air outside is due to wind-pressure and the angle at which it strikes the glass. Quadrupling the velocity of the outer air, however, does not quadruple the loss of heat through the glass, for the reason that the air inside will not fall in the same ratio, but in a ratio about as the square root of the increase of outside velocity, so that the loss of heat through glass cannot be accurately established for a given difference of temperature and a certain velocity of the wind outside ; an approximation, however, can be made to the loss of heat for other velocities and temperatures. Unfortunately, we have no very accurate data on the cooling effect of windows for the guidance of heating engineers, though on the warming effect of radiator surfaces there is not such a scarcity of information.

As this book is on warming by hot water, I would like to be able to give some data on the values of hot-water surfaces used in common practice in this country. Presumably, on account of the difficulty of measuring the loss of heat from hot-water coils, etc., maintained at some nearly constant temperature as in actual use, few attempts have been made and none made public except some of the writer's, and these were with indirect coils,

that do not properly represent the value of direct radiation. I hope before going to press, however, to be able to give some data on this question in an appendix, and for the present will give an experiment with a common box-coil that approaches more nearly the condition of a radiator set for direct radiation than anything I know of.

While making experiment on indirect coils I boxed one at the sides and ends and left the top and bottom open, so the air ascends vertically. Presumably, slightly better results would be obtained if the heater was open at the sides as well as top and bottom, but of this there is some doubt.

The coil was of *one*-inch pipe, 6 pipes wide, 10 pipes high, and 36 inches long between bends ; the total surface of pipes, bends, and headers being 74 square feet. A difference of about 110 degrees was maintained between the air of the room and surface of the pipes during the time of trial. By measuring the increase of temperature of the air and its quantity, etc., after passing the coil, the amount of heat found corresponded to 1.343 heat-units per square foot of surface per hour given off for each *one* degree Fah. the air was warmer than the coil. The coil-box was then closed in at the top until the outlet for air was 12x16 inches without apparently diminishing the flow of air, the better to use the anemometer, and the result obtained was practically the same. This agrees quite nearly with the results of Mr. Hood as given for the 3-inch horizontal pipe ; though, on account of there being ten pipes, one above the other, in the box-coil, it would appear that it should do less work. It may be that the currents of air were accelerated sufficient by the boxing to account for the

similarity.   Or it may be an error existed in the use of the anemometer and that it recorded more air than actually passed, which is possible by taking the centre of the current; the rubbing sides of the box and pipe causing a slower velocity there than was measured where the anemometer could be used. It is not safe, however, to give a box-coil ten pipes high, used for direct radiation, a higher value than 1.343, and, presumably, 1.25 heat-units is high enough.

Mr. George H. Barrus, of Boston, in experiments with a Walworth vertical wrought-iron pipe radiator for steam, found that under average conditions of use, with eight pounds of steam, in an atmosphere of about 51° Fah., that the units of heat given off per actual square foot of surface was 394.4. If we assume the surface of the iron to be 235° Fah. (the temperature of the steam) we have 235° — 51° = 184° difference. Then

$$\frac{394.4}{184°} = 2.143 \text{ H. U.}$$

This is somewhat less than Mr. Tredgold's experiments give for a short vertical cylinder, but it is what would be expected, as the pipes used were thirty inches long, and in a cluster two inches wide, screwed into a base.

He also experimented with a Nason radiator of ordinary height, two pipes wide by 24 pipes long. The total number of heat-units per square foot of surface given off was 347.6; the pressure of the steam was eight pounds, and the temperature of the air of the room 64° Fah. Assuming the temperature of the pipe to surface to be 235° Fah., the difference then

between air and heating surface is 170° Fah., which gives us $\dfrac{347.6 \text{ H. U.}}{170°} = 2.045$ heat-units per hour per square foot per degree difference.

Mr. Barrus' method of measuring the heat was to receive the water of condensation carefully and to ascertain its weight, then compute the heat according to the latent heat of steam. The nearness of the results thus obtained by vertical radiators of different makes, and at different times in different buildings, by the same methods, adds value to the data and establishes the fact, when taken with other investigations, that a tube of a vertical radiator will give off heat equal to about two heat-units per square foot per hour per degree difference.

An experiment made by the writer in 1884 on a 2x7 Bundy steam-radiator, for his own information, and before the Bundy patterns were altered to have an actual surface equal to their commercial rating, gave the following results: Actual surface, 38 square feet; water condensed for one hour was 12.843 pounds, when the pressure of steam was maintained between 1 and 1½ pounds; temperature of air of room at floor commencement of experiment 52°; at 5 feet high on side wall 58°; temperature of air of room at floor at end of experiment 57½°; and at 5 feet high 64°. The temperature of the air as it was found at the floor was, presumably, the temperature at which it first came in contact with the heater, but, as in the other cases, the temperature of the room only was noted— without informing us further—we will in this case take the mean of the temperature given, which is 57.9° Fah., and, presumably, near enough for our purpose, which is not to compare

rivai heaters, but to establish the condensation or cooling
for ordinary conditions of use.

Taking the temperature of the steam (one pound), therefore,
at 215° Fah., and the latent heat of its vaporization at 962
heat-units per pound, we will have : difference of temperature
between steam (or pipe). 157.1° Fah., and total heat of 12.843
pounds of steam, 12355 heat-units, or 325.1 heat-units pei
actual square foot of surface, equaling 2.07 heat-units per
square foot of surface per hour per degree of difference
between steam and air.

It is possible that should these radiators be transposed as
to the buildings they were tested in, the results would slightly
differ, as the effect of the passage of heat by radiation alone
from or to the radiator cannot be estimated, as it will depend
on the surrounding walls, etc. For instance, one experiment
being made in a cellar and another on an upper floor of a
building, it is reasonable to assume it will affect the results,
and the queston of humidity may also come in as a factor for
or against a radiator. Draughts of air, also, will materially
alter results, and the effect of an open hatchway, machinery in
motion, or down draughts from windows, etc., will all tend to
throw some uncertainty into the matter, so that unless
positions, etc., are transposed and the water of condensation
measured in the same manner and similar apparatus, it would be
difficult to determine positively which of the above radiators
gives the highest result per actual square foot of surface. Such
remarkable uniformity, however, by different makers appears to
establish beyond a doubt that 2° Fah. per square foot of surface
per degree difference of temperature between surface and air

may be taken as the basis of loss of heat from vertical radiators whether they are for hot water or steam.

This, of course, is the maximum, and it is for radiators of plain, smooth surface, say not over three feet in height, that are not covered up with screens or slabs, but used in the most practical manner and not too close to the walls. It should be borne in mind, also, that these radiators were only two pipes wide and represented more than the average, and that radiators of three or four pipes wide should not be expected to give quite as good results.

It is very probable, taking all the styles and kinds of radiators and coils known to the writer, that the minimum condensation or cooling may be placed at 1.25 heat units and the maximum at 2 heat units. Between these points it must be left to the judgment and experience of the fitter to select when the character of the radiator or coil is known.

*How to Find the Amount of Water that Should Pass Through a
Radiator to do a Certain Duty—How to Determine the Size of
Inlet and Outlet to Hot-Water Radiators—A Reasonable Loss
of Temperature to the Water while Passing Through a
Radiator—The Quantity of Water that Should Pass
Through a Radiator for a Loss of Temperature of* 10
*degrees—The Diameter and Resistance of Radiator
Connections — The Diameters of Pipes for
a Loss of* 20 *degrees Fah.—The Diameters of
Pipes for a Loss of* 30 *to* 34 *degrees Fah.*

THE object of the last article was to fix in the mind of the
reader the average quantity of heat given off per square
foot of ordinary heating surface when placed within a room
and used as a direct radiator, and to give him a knowledge
of the experiments and *data* on which it is based.

A summary of the matter, therefore, points to the fact that
the best vertical tube radiators will do duty a little in excess of
two heat units per square foot of surface per hour for each de-
gree the radiator is warmer than the air, and that the poorest
form of coil or radiator, as ordinarily made, if exposed to the
free action of the air, will not go under 1.25 heat units. This,

remember, is for direct radiation only, with natural currents of air, or such movements of the air as are produced by the heat of the radiator.

Knowing, then, the heat given off by a radiator for a unit of surface, our next step is to determine the total amount of water that should pass through in a given time to do a certain duty, and from this determine the size of inlet and outlet equal to that duty.

Let us assume we have a radiator of 100 square feet in a room with the air at 70° Fah., and that the water enters at 210° and flows out of it at 200° Fah. This is equal to a loss of 10 degrees, making the mean temperature of the water in the radiator

$$\left(\frac{210 + 200}{2}\right) = 205°.$$

We have then the difference between the water (205° Fah.), and the air of the room (70° Fah.), or 135 degrees, which, multiplied by 2 heat units and by 100 square feet, gives us 27,000 units of heat that is given off by the radiator in an hour, or the equivalent of 27,000 pounds of water cooled one degree.

It is not our object, however, to pass the water so rapidly that it will cool but *one* degree between the inlet and outlet, as we would therefore have to pass 3,375 gallons of water through the radiator in an hour, which would call for radiator connections so enormously above practicable sizes—with heads of water to be obtained in ordinary hot-water practice—that we must content ourselves with a difference or loss of temperature between inlet and outlet of, say, 10 degrees. Therefore, we

divide 3,375 gallons by 10 and find that instead of passing 3,375 gallons with a loss of one degree we pass 337.5 gallons with a loss of ten degrees.

This is for an hour of time, and consequently 5.625 gallons will be the amount to pass in a minute, and if we turn to Table II., page 113, we will find that a common one-inch nipple under one inch of water head is not sufficient to pass it, as its capacity is but 4.6 U. S. gallons per minute, and that in practice we would have to take the 1¼-inch nipple, whose capacity is 7.2 U. S. gallons.

In ordinary apparatus, however, the connections to radiators are always longer than nipples, and we have also to take into consideration not only the increased length of connections but the effect of elbows or other fittings and valves on the flow of the water.

From a rising line to a radiator and back again to a return riser, or the ordinary connection through a floor from a main underneath, it is certainly not safe to place the average length of the two connections when taken together at less than ten feet, and to this should be added from four to six elbow turns and one valve.   We have, therefore, to find, not the size nipple that will pass 5.625 gallons of water, but the size pipes of ordinary lengths with their turns and valve for an average condition of practice.

This brings us to a point where the rules given in Chapter VIII. will be of service to us.   In the above case we have (1) determined the quantity of water that must be passed through the radiator to be 5.625 U. S. gallons per minute; (2) the diameter of the pipe we are at liberty to assume as being 1¼

inches, and (3) the length is fixed at ten feet, with six common elbows, square-ended pipes and angle-valve.

According to Chapter VII., we must, for friction, add to the length of the pipe, in determining its resistance, 100 diameters for each common elbow, and for an angle-valve something like 200 diameters, so that the ten feet of 1¼-inch pipe becomes 10 feet + 800. diameters (83.3 feet) = 93.3 feet ; or, in other words, the resistance of the connections to the flow of the water—though only ten feet long—is equal to the resistance of 93.3 of straight pipe.

By Table III. we find the friction for ten feet of 1¼-inch pipe passing five gallons of water—or the nearest to our quantity—to be .837 inches of head, and by interpolation we may establish the friction head for 5.625 gallons to be about 1. inch, and consequently it will be 1. × 9.33 = 9.33 inches for our connections as a whole. This, remember, is only the head to overcome friction, and to it must be added the velocity head as found by Table I., and which will be seen to be under ½ of an inch though above ¼ of an inch, and which it is as well to take as the former, so the error will be in favor of the diameter of the pipe. This will make the total head, therefore, 9.83 inches.

This head is considerably more than we are likely to obtain in ordinary practice in low-pressure apparatus. It is about equal to the head obtained in an apparatus when the water is cooled from 212° to 162° Fah., whose height would be forty feet, and, therefore, in designing for the *maximum-sized flow-pipe*, we should consider an apparatus whose height would not exceed 15 feet, and if we require that the water of

the apparatus shall not cool more than 20 degrees, or say from 210° to 190° Fah., the total effective head at our disposal will be but $1\frac{4}{10}$ inches, as will be seen by diagram, Figure 14.

For this head, therefore, ($1\frac{4}{10}$ inches,) we have to find a new diameter. With a head of 9.83 inches, a $1\frac{1}{4}$ pipe was ample, but with a head of $1\frac{4}{10}$ a greater diameter is necessary. The rule for this is: When *quantity and length* are to remain constant the diameters will vary *inversely* as the fifth root of the heads. The above heads, therefore, are in the ratio of 1 and 7, and tne inverse ratio of their fifth roots are 1.48 and 1, · so that the $1\frac{1}{4}$-inch pipe must be enlarged to

$$\frac{1.25' \times 1.48}{1} = 1.85 \text{ inches}$$

as the new diameter.

We have no pipe of this diameter, and, therefore, we have either to use a 2-inch pipe—the size larger—or a $1\frac{1}{2}$-inch pipe, the next size smaller—and be content with a greater difference in cooling. If we decide to use a $1\frac{1}{2}$-inch pipe it becomes us to find how much greater the difference in cooling will be, and this can only be determined by the rule : That when *head* and *length* of pipes are constant the *quantity* of water they will pass will be in the direct ratio of the 2.5 powers (square root of the fifth power) of their diameters, and that the loss in temperature will be inversely as the increase in quantity.

The diameters of a 1.5-inch pipe and a 1.85-inch pipe are to each other as 1 and 1.233.

The square root of the fifth power of 1 therefore = 1, and of 1.23= 1.74.   Then we have

$$\frac{5.625 \text{ gallons} \times 1.74}{1} = 9.7875 \text{ gallons.}$$

From which we get

$$\frac{20 \text{ degrees} \times 9.7875 \text{ gallons}}{5.625} = 3.48 \text{ degrees}$$

as the difference in temperature between inlet and outlet if we use 1½-inch pipe.

Throughout these papers, for practical reasons, nearly all small differences or errors of calculation are in the favor of the diameter of the pipe.   The reason should be obvious, but fearing it would not be understood by all, I will say I wish to err on the side of safety, if at all, and therefore as practical men may not assume new conditions, but accept the size and condition above given as a maximum, and therefore a stand-ard for all conditions, I will say that from my own practice I am of the opinion a 1½ pipe will do a little better than 17.4 degrees. In other words, I have noted that an ordinary 1½-inch connection if well reamed at the ends, and with not more than six elbows in the two connections, will pass water at such a rate under the cooling done by 100 square feet of surface, that the difference of temperature will be little, if any greater than 15 degrees ; which, no doubt, is partly accounted for by

the fact of the commercial pipe being larger than its nominal diameter.

In ordinary practice radiators should be tapped for the maximum duty by the maker, and therefore if the steam-fitter uses smaller diameter pipes, he does it at his own risk.

Fortunately, in hot-water heating, a small diameter of supply pipe does not entirely destroy the value of a heater. The heater or radiator, however, depreciates in value as the quantity of water passing through it decreases. This is why two heaters of the same size in rooms of equal dimensions frequently give results extremely different. The pipe to the poor heater is either smaller in diameter than the other or very long (though of the same diameter) and the water perhaps travels only one-quarter as fast, and the result is that one radiator circulates so rapidly that the loss of heat is only 20 degrees, while the loss in the other may be forty degrees or more, corresponding to a difference of at least 30° between the average temperatures of the two radiators.

Should we settle the diameter for the inlet and outlet of a 100 square-foot radiator, therefore, at 1½ inches, we shall be obliged, by the rule that the quantity varies as the square root of the fifth power of the diameter, other things remaining the same, to use a 1¼-inch pipe for a radiator of 63 square feet, a 1-inch pipe for one of 36 square feet, and a ¾-inch pipe for one of 18 square feet.

There are, however, many commercial sizes of radiators between those mentioned, while in the matter of the diameter of pipes we are confined to the standard sizes of commercial pipe and have none between those mentioned ; we are there-

fore compelled, if we are to keep up the standard, or rather not go below the standard of a 1½-inch pipe for a 100-pipe radiator, to use

¾-inch pipe for 18 square feet or under.
1   "   "   36   "   "   down to 19 square feet.
1¼ "   "   63   "   "   "   37   "
1½. "   " 100   "   "   "   64   "

These diameters for radiators of the sizes given in the second column will circulate the water with a loss of about fifteen degrees while passing through radiators, when set one story above the boiler, with average length of connections.

Of course, when a radiator of forty square feet has a 1¼-pipe, or one of sixty-eight or seventy square feet has a connection of 1½ inches (as it would have under the above schedule of sizes of pipe, etc.), the results would be somewhat better than 30 degrees—in other words the amount of cooling would be less.

If, however, we are not satisfied with so great a difference as fifteen degrees, and require that the difference shall be only about 20 degrees, then we may take the size of a 1.85-inch pipe as our standard for 100 square feet of surface, and we will have sizes as follows, for inlet and outlet of radiator :

1   inch pipe for 22 square feet or under.
1¼   "   "   37   "   "   down to 23 square feet.
1½   "   "   59   "   "   "   38 "   "
2   "   " 121   "   "   "   60 "   "

CHAPTER XII.

Table of the Diameter of Short Pipes or Connections for a Loss
of Temperature of 20 and 30 degrees while the Water
is Passing Through the Radiator—The Greater
Resistance and Necessary Increase of
Diameter Caused by Greater Lengths.

UNDER the foregoing schedule of sizes—owing to the fact
that we have no intermediate commercial sizes of pipe
—we would be compelled to use a 2-inch pipe for a sixty square
foot radiator. This, of course, would be unnecessary and would
result in two radiators (a fifty-nine square foot and a sixty
square foot) of almost the same size, giving very different re-
sults. Therefore, for this schedule and the one that precedes
it for a difference of thirty degrees, it is better that we should
interpolate and form averages in each case—thus: For dif-
ferences of thirty degress let the sizes be*:

<div align="center">

TABLE IV.

¾-inch pipe, 24 square feet or under.
1   "   " 25 to 40 square feet.
1¼ "   " 71 to 70 "   "
1½ "   " 71 to 100 "   "

</div>

---

* NOTE.—When actual diameters of pipes are referred to, a loss of 34
degrees is to be considered, but in cases where the commercial size is
substituted for the actual, a loss of about 15 degrees may be considered.
The diagrams, which follow later, in relation to this subject are all for
actual diameters of pipe, and are therefore marked for a loss of 20 degrees
and 34 degrees respectively, as calculated.

For differences of twenty degrees:

1   inch pipe, 30 square feet and under.
1¼   "   "   31 to 50 square feet.
1½   "   "   51 to 85   "   "
2   "   "   86 to 125 "   "

These diameters, it must be remembered, are for ordinary lengths of connections with three common elbows in each connection and one valve in one of the connections—usually the inlet.

Taken together the connections have a resistance equal to about 93.3 feet of straight pipe, or at least of pipes with long easy bends and no elbows. It may be that 100 feet of straight pipe will give a resistance no greater than has been allowed for these connections, for reasons before explained, and therefore each additional fifty feet, without elbows, that the radiator is removed horizontally from the place of supply, will add to the resistance an amount equal to that allowed for one connection and correspondingly decrease the quantity of water that will pass through the radiator.

The resistance already considered is for a set of average connections, say from the head of a boiler or from ample mains, the total resistance head being between $1\frac{4}{10}$ and 2 inches for the greater and lesser diameter pipes respectively.

We must, for practical reasons, in such a complex matter as the flow of water through small pipes with many turns, etc., confine ourselves to some general method of reasoning. It is for this reason, therefore, I have so calculated it that the resistance of a pair of ordinary connections is shown to be about

equal to the resistance of each additional fifty feet, without extra bends, the radiator is away from the main or boiler and of the same diameter connections.*

Therefore, when we double the length of the connection, we double the resistance, and under the rule, that when quantity and diameter are constant the head is directly and simply as the length, we will have lengths in the ratio of 1, 2, 3 and 4 ; and head in the same ratio—1, 2, 3 and 4.

The total head at our disposal is always fixed by the height of the radiator above the boiler ; or, more properly speaking, by the relative densities of the two columns of water.   Therefore, when we increase the length—without the height—we are either compelled to do with a smaller quantity of water or use a larger diameter of pipe.

We will assume the diameter of the connection to be unchanged, however, for the present, at least, or until such time as we find we cannot get sufficient water through it for our purpose, when as it is in our power to change it, we may do so after proving it is not ample for our purpose, or rather, when we have found how great a loss we will sustain if we retain it.

For the present, therefore, as we are only to consider the effect on the quantity of water passed, and therefore on the value of the radiator when we double or otherwise increase the length of the radiator pipe, we must consider the diameter as *constant*, which in our case means that it is the size of the short radiator connection as before established.   (Table IV.)

---

* The resistance of coupling is not considered.   If the ends of the pipes are carefully reamed, however, this will be very small.

By the rule, that when *head* and *diameter* are constant, the discharge or quantity passed will vary *inversely* as the square root of the length, we have : for lengths in the ratio of 1., 2., 3., 4., etc., the quantities of water passed will be in the ratio of 2., 1.73, 1.41, and 1., etc.

In our case we are at liberty to assume any quantity passed through the pipe. Say it is 10 gallons that passes through the ordinary connection, whose length is 1. with a resistance equal to 100 feet of straight pipe. If we, however, add 50 feet to the length of each of the two connections they become 2., and the quantity then will decrease in the same ratio that 1. is less than 1.41. Thus,

$$\frac{10 \times 1}{1.41} = 7.09,$$

or, say, $7\frac{1}{10}$ gallons will pass through when the length is doubled, instead of the 10 gallons as at first ; or in that ratio for any other quantity of gallons.

If we make the line 100 feet long (200 feet in the circuit) then it is equivalent to three times the length of the ordinary connection, and the sum is

$$\frac{10 \times 1}{1.73} = 5.78 \text{ gallons;}$$

and if we add 50 feet more, or four times the resistance to the length of the line (100 feet to the circuit), it makes

$$\frac{10 \times 1}{2} = 5 \text{ gallons,}$$

or just half the quantity that will go through the short connections.

This points to the fact that we can run connections (flow and return) 150 feet (300 foot circuit), giving them four times the resistance (if we are careful and ream the ends in the couplings) before we reduce the quantity of water passed to half what it would be with short connections, and consequently increase the cooling of the water to double; so that the amount of water that will cool 20 degrees with a short connection will cool 40 degrees with connections 150 feet long with bends.

If, however, instead of losing 20 degrees extra by the long connection we are desirous of delivering an equal quantity of water at the greater distance, then we must vary the diameter of the pipe, as before intimated that we could.

In this new case, then, we have *head* and *length* constant and require a new diameter for a stated quantity, knowing what some other diameter will do under the same head and length, as we have just shown.

Our problem now is : that instead of passing five gallons through connections each the equivalent of 200 feet in length (150 feet, plus short connections), or four times the resistance of an ordinary connection, we require a new diameter that will pass ten gallons.

Where *head* and *length* are constant the diameter varies directly as the fifth root of the square of the discharge ; thus for discharges in the ratio of 1, 2, 3, and 4 the diameters will be in the ratio of 1., 1.32, 1.55, and 1.74, etc.   Our discharges are in the ratio of 1. and 2. (five and ten gallons), consequently our diameters will be in the ratio of 1. and 1.32.   Therefore, if our connection for a radiator of 100 square feet is 1½ inches,

the pipes to supply the same quantity of water to it 150 feet off, plus elbows, etc., without increasing the head, will be

$$\frac{1.5' \times 1.32}{1} = 1.98 \text{ inches.}$$

According to this, therefore, if our radiator openings are of the size shown in the first column at the inlet and outlet, they will have to be enlarged to pipes of the diameter shown in the second column if they are 150 feet distant *horizontally* from the mains or boiler, thus :

Short Connections.	Connection 150' long.	Which in practice would probably have to resolve themselves into	Radiator, square feet.
¾	1.	1 ′	
1	1.32	1¼″	
1¼	1.64	1½″	
1½	1.98	2 ′	
2	2.64	2½″	

To get the full benefit of the enlarged diameter circuit, the inlet and outlet of the radiator must be the full size of the pipes which it is found necessary to run to it, and consequently hot-water radiators should have ample inlets and outlets that can be bushed to a smaller diameter, if the circuit is short and it does not require a pipe as great as the inlet. All the benefits of the large diameter pipe, however, are not lost should the inlet to the radiator be a size smaller than the circuit, and no one must fall into the error of using a pipe as small as the inlet for that reason. In fact it is a reason for using·a larger pipe, so as to get the water to the contracted point with the least resistance.

CHAPTER XIII.

*The Decrease in Diameter of Pipes as the Building Grows
Higher—Tables V. and VI. of the Diameters of Flow
and Return Pipes for Various Conditions
of Length and Height.*

W E have now to consider the effect on the sizes or diameters
of pipes as the building grows higher. The foregoing
was all on the supposition that the head at our disposal was
that equivalent to one story of a house. Let us assume, how-
ever, we have another story or 15 feet more in height, so that
part of our pipes run horizontally and part of them the height of
two stories or about twenty feet. This will double the head
under which we have been working so far, so that now our head
will be about $2\frac{8}{10}$ inches, or double what it was before. For our
present purpose it matters not what it was in the first case, and
it may be called the head for one story here, being doubled
for the second story, being trebled for the third story, and so
on as the apparatus grows higher in the building.

The rule for this is : That when gallons (or quantity) is to
remain *constant,* and the length is constant, the diameter will

vary inversely as the fifth root of the head.   Thus for heads in
the ratio of 1, 2, 3, and 4, the diameters will be as 1.32, 1.25,
1.15, and 1., so that in the case of a connection 150 feet long,
if it runs two stories high instead of one, we have, taking the
case of the two-inch pipe, again

$$\frac{2'' \times 1}{1.15} = 1.74'',$$

or a 1¾-inch pipe, if we had such a size.

In the case of the third story it would be 1.6, and of the
fourth, 1.5 inches.   In other words, if it is necessary to run
pipes of the diameters in the first column given below
to radiators 150 feet away on the first floor, the sizes given in
the remaining columns are for each successive story ; the pipes
remaining the same length.

1	2	3	4	Stories in Height.
¾″	¾″	¾″	¾″	NOTE.—As no pipe smaller than ¾
1	.87	.8	.757	inch should be used in an apparatus,
1¼	1.1	1.0	.947	the ¾ diameter is given throughout.
1½	1.3	1.2	1.1	
2	1.75	1.6	1.5	
2½	2.17	2.0	1.89	

It must be remembered that the first column in this table
corresponds to the last column in the preceding table, and
that, therefore, the first column here is not the radiator connec-
tion, but the nearest commercial diameter for 150 feet horizontal.
This table, therefore, forms the reduction for rising lines that
are not branched (separate rising lines), without reference to
length.   In other words, if we were to run from the head of a

boiler, or from properly designed mains, straight upwards to separate radiators, this table shows the comparative size of pipe for each story averaging ten feet of rise.

The fitter must use his own judgment in selecting commercial sizes of pipe to correspond with tables. For instance, in the case of a first-story radiator with a 1¼-inch pipe to it, he should use a 1¼-inch also to the second story, as there is no 1.1-inch pipe, but in the case of the third and fourth stories his results will be more uniform if he uses an inch pipe in both cases, and so on ; bearing in mind that it is better to overrun in the size than be under when circumstances will permit the former.

The following tables are summaries of the sizes of pipes for different radiators under different conditions of temperature, distance, and height, according to the rules, etc., just given.

The third column is for the radiator connections and is given in commercial sizes. The remaining columns are the actual sizes of the diameters in inches, taking the first column as the basis of calculation.

It must be understood that many, if not all of the rules here given for the flow of water, etc., are not absolutely correct, but that they give close approximations to the truth, and that for practical purposes we may accept them. By applying these rules to new conditions we may extend the following tables (No. V. and VI.) indefinitely. The tables V. and VI., as far as they go, however, are just suited to hot-water apparatus that have many mains or rather circuits starting from the head of a boiler and running to the different sections of a house ; usually from *four* to *six* such lines being used for private

houses, though in some large buildings in Canada twenty or more such circuits are not unusual, where the practice is to connect two or more boilers with a large header—both top and bottom—taking the flow-pipe from the upper one and entering the lower one with the return pipes.

Elsewhere in this work will be found an illustration of this kind of fitting for a private house with seven circuits, and also an example of two boilers, connected with headers, from which twenty circuits are carried to different parts of a large building. The Tables V. and VI., therefore, are for this class of work and give the diameters of circuits for different conditions covering all that is in the small tables that are not numbered.

TABLE No. V.

Size of Flow and Return Pipe for a Difference of 30 Degrees for Length and Conditions Given.

Actual Size of Radiator in Square Feet for Size of Pipe Connection in 3d Column.	Size of Radiator. Average Range Interpolated to Suit Practice.	Size of Connection, First Story (commercial).	Size of Connection, 150 Feet, First Floor (actual).	Size of Connection, Second Story, 150 Feet (actual).	Size of Connection, Third Story, 150 feet.	Size of Connection, Fourth Story, 150 Feet.	Size of Riser, if Run to Second Floor, less than 50 feet.	Size of Riser, if Run to Third Floor, less than 50 Feet.	Size of Riser, if Run to Third Floor, less than 90 Feet.
18.	24 sq. feet or under.	¾"	1	.87	.8	.757	.75	....	.....
36.	24 to 40 square feet.	1	1.32	1.15	1.05	1.0	.87	.80	.757
63.	40 to 70 " "	1¼	1.64	1.426	1.31	1.25	1.1	1.0	.947
100.	70 to 100 " "	1½	1.98	1.72	1.584	1.5	1.3	1.2	1.1
198.	100 to 198 " "	2	2.64	2.3	2.1	2.0	1.74	1.6	1.5

TABLE No. VI.

Size of Flow and Return Pipe for a Difference of 20 Degrees for Length and Conditions Given.

Actual Size Radiator in Square Feet for Pipe Connections in Third Column.	Size of Radiator. Average Range Interpolated to Suit Practice.	Size of Connection, First Story (commercial).	Size of Connections, 150' dist., First Floor (actual).	Size Connection, Second Story, 150 Feet.	Size Connection, Third Story, 150 Feet.	Size Connection, Fourth Story, 150 Feet.	Size for Riser, if Run to Second Floor, under 90 Feet.	Size of Riser, if Run to Third Floor, under 90 Feet.	Size of Riser, if Run to Fourth Floor, under 90 Feet.
22.	30 square ft. or under	1″	1.32	1.15	1.05	1.0	.87	.8	.75
37.	30 to 45 square feet.	1¼	1.64	1.426	1.31	1.25	1.1	1.0	.947
59.	45 to 75 " "	1½	1.98	1.72	1.58	1.5	1.3	1.2	1.1
121.	75 to 130 " "	2	2.64	2.3	2.1	2.0	1.74	1.6	1.5
203.	130 to 225 " "	2½	3.3	2.64	2.43	2.5	2.17	2.0	1.89
1	2	3	4	5	6	7	8	9	10

In using the tables judgment must be exercised in selecting a commercial size of pipe, as the sizes given are not, as will be noticed, "commercial" except in the third column.

For instance, the size given for 75 square feet of surface on a second story (difference ten degrees), 150 feet away, is 1.72. If there are many more elbows than six in the whole circuit, it is better to make it two inches than 1½ inches, for reasons that are obvious, although with the latter size pipe it would not be a failure, as by the table for thirty degrees difference, it will be noticed, a pipe 1.42-inch diameter will do for 70 square feet. What would follow if the smaller size is

used would be a greater difference of temperature of the water, which, of course, would not be desirable in good work. If, on the other hand, the radiator was 45 or 50 square feet, then the 1½-inch pipe would be ample, provided there are not too many elbows introduced into it.

The first columns of the tables show the actual square feet of radiator surface suitable to the diameters. The second columns give the safe ranges for variation of sizes above or below the actual size. By comparing the actual size of radiator, therefore, and the range of sizes, any one of intelligence should be able to judge as to whether it would be safe or not to use diameters smaller than those given in the remaining columns.

The table for a difference of 30 degrees also forms a·guide to determining minimum diameters for average duty of 20 degrees. In other words, if a diameter is selected for a certain size heater smaller than that given in the 20-degree table and it proves as small as the diameter given in the 30-degree table for a heater of about the same size, it should be rejected as causing too slow a circulation. For instance, suppose the radiator to be 45 square feet, then under the 20-degree table it will call for 1.72 inches diameter, while under the 30-degree table a diameter of 1.42 inches is required. It is reasonable to suppose this heater would give satisfactory results (about 20 degrees difference) with a 1½-inch pipe, as 63 square feet would only call for 1.42 inches diameter by the 30-degree table.

CHAPTER XIV.

*Diagrams Giving the Diameter of Flow and Return Pipes in
Inches When the Radiator Surface and Length of Pipe
Circuits are Known — Exercise Illustrating the
Use of the Diagrams—Skeleton Diagram
of the Pipes of a Building.*

THE rules relating to the flow of water in pipes are very
confusing to any one who has not the time to thoroughly
consider and familiarize himself with them. For this reason,
although I have tried to make myself understood, some read-
ers may be still unable to find any practical good in the rules
and examples I have given. I have, therefore, constructed
four diagrams, Figures 26, 27, 28, and 29, based on the ordi-
nary rules of hydraulics, which give the diameters of pipes for
hot-water apparatus up to 1,600 square feet of surface, or what
I consider sufficient for private dwellings.

Diagrams, Figures 26 and 27, show the diameters of rising
lines for the different stories of a house, on the supposition
that the stories are an average of 15 feet in height. Figure
26 is worked out for a loss of 15 degrees in the temperature
of the water between flow and return-pipe, and Figure 27 for
a loss of 34 degrees.

The horizontal lines show the number of square feet of

FIGURE 26.

a DIAMETER of RISERS in INCHES

FOR A LOSS OF 34 DEGREES FAHRENHEIT

FIGURE 27.

DIAMETER of PIPE IN INCHES

SQUARE FEET of HEATING-SURFACE

SQUARE FEET of HEATING SURFACE

DIAMETER for 100 feet in LENGTH of CIRCUIT

DIAMETER for 100 Feet in LENGTH of CIRCUIT

FOR A LOSS OF 20 DEGREES FAHRENHEIT

FIGURE 28.

FIGURE 29.

FIGURE 30.

surface the pipe is to supply water for, and the vertical lines
indicate diameter of pipe in inches ; while the ordinates of the
curved lines, where they bisect the horizontal lines, indicate
the required diameters by the vertical lines.

The curved line *a* indicates the diameters for the first
stories, *b* for the second, *c* for the third, and so on; or they
stand for heights, about 10, 20 and 30 feet, etc., when the stories
are greater or less.

The diagrams, Figures 28 and 29, show the diameters of
the main lines for lengths varying from 100 to 1,000 feet.
These lengths are the lengths of the circuits, so that 1,000 feet
means 500 feet through the flow-pipe, and as many more back-
wards through the return-pipe to the boiler.

The horizontal lines show square feet of heating surface
up to 1,600, and the vertical lines the diameters of pipes, while
the ordinates of the curved lines indicate the diameter for the
surface opposite to them, or the surfaces for the diameters
above them.

To illustrate the use of the diagrams in finding the diame-
ters of the pipes of the different parts of an apparatus, we
should construct a skeleton diagram of the pipes of a house
or building in the manner so well known to heating engineers
and shown in Figure 30.

The distance from the datum, or the level at which the re-
turns enter the boiler, to the top of the radiators on the first
floor is assumed to be ten feet, and each succeeding floor of
the building is assumed to be ten feet higher than the one be-
low it.   The length of the horizontal pipes are marked in feet,
and to those who are not accustomed to these diagrams, I will

explain that all diagonal pipes, as well as the ones shown, in the horizontal position, are to be considered as horizontal ; the diagonal pipes as shown being horizontal branches at right angles to the mains.   The vertical pipes in the diagram are rising lines, and the diagonal branches are radiator connections.

The numerals 1, 2, 3, etc. (Fig. 30), shown at the branches of the risers indicate the floor the radiator is on.   The figures shown at the opposite side followed by the sign for square feet thus □, indicate the size of the radiator in square feet.   The rising lines are further numbered from the left to the right, as No. 1, No. 2, No. 3, etc., for convenient reference.

To use the diagrams the engineer constructs a diagram suitable to the building, for which he is designing an apparatus, and it will be found of advantage to trace it over the ground plans of the building, letting the rising lines then run in a diagonal direction as the branches can be shown in their proper position on the plan.

To find the diameters the designer will commence with the head of the rising line furthest from his boiler in any direction, and note the radiating surface and the floor number. In the case of our diagram we take riser No. 5, as it is the end of the line or circuit on the right of the boiler.   We note it calls for 75 square feet of surface on the third floor, and as we are going to determine sizes for a loss of 20 degrees, we turn to Figure No. 26, and find that 75 square feet of surface on the third floor calls for a pipe a little larger than 1¼ inches, as will be seen by noticing that the line *c* for the third floor crosses the horizontal line opposite 75 square feet at a point a

little beyond 1¼ inches. As it is nearer 1¼ inches than it is to 1½ inches, and as 1¼ inches "commercial" is a little larger than 1¼ inches actual, and as it is also necessary to take the averages into consideration as shown in the second column of Table VI., the 1¼-inch pipe is ample; its use probably causing a loss of 24 degrees in that particular heater.

We then come to the second floor on the same rising line and find a heater of 75 square feet also. As the pipes to this point must be ample for taking care of all above it as well as the immediate radiator, we have to add the 75 square feet on the third floor to the 75 square feet on the second floor and proceed to pick out the diameter for 150 square feet on the curved line b, Figure 26, which will be found to be 1.85 inches —a size we have none of. We are now forced to use either a 2-inch pipe or a 1½-inch pipe. The 2-inch pipe will give us more water than we actually require, and the 1½-inch pipe will not give us sufficient water. By looking over to diagram 27, we notice the curved line b crosses the 150 square foot horizontal line, very close to the 1½-inch diameter line. If we use the latter we reduce the quantity of water we require (if we desire equal results in all radiators) until the radiators from this point upwards receive water equal to a loss of about 34 degrees. It is also likely to follow that the radiator on the third floor will do better than the one on the second floor, as · the pipe from second to third floors is of a size suitable to the 10 degree loss. Therefore if anything like equality in resistance is required, and consequently equal work from equal heaters, the 2-inch pipe must be used and a bushing slipped into it of the actual size required (1.85 inch).

Coming to the first story we have to provide a pipe for 100 □ + 75 □ + 75 □ = 250 square feet. * The size is found on the curved line *a* opposite 250, Figure 26, and is somewhat greater than a 2½-inch pipe. A 2½-inch commercial pipe, however, will be ample in this case if there are not too many elbows in it, and its length is not too great.

In the present instance there are six common elbows between the first floor and the main. The branches are ten feet, and with the pipe that goes through the floor the circuit may be taken as 25 feet of 2½-inch straight pipe, plus 600 diameters or 125 feet for 6 elbows = 150 feet of circuit so far as resistance is concerned. The diameter of 2½ inches already found was for 100 feet of circuit, and we have now to determine whether it should be increased or not. The actual increase for the extra resistance would bring it to a diameter about 2¾ inches for a head of 1.4 inches (first story head). The probability, however, as it is the lower end of a rising line, is that the additional head augmented within the risers by the extra stories is not all absorbed by friction within themselves, and that enough remains to exert its influence on the velocity of the water through the riser connections, and that we are safe in not increasing its diameter, unless there are more elbows than the number shown.

We have now to determine the size of the main pipes to the point where riser No. 4 leaves them. The length of our risers were not taken into consideration, as the resistance between floors and through the radiator connections may be taken as the resistance of 100 feet of straight, smooth pipe for reasons given before. With the horizontal mains, however, we must

take length into consideration as in the riser connections. In this case the length from the lower end of the riser connection No. 5 to the point where No. 4 joins it being but 40 feet, the circuit will be 80 feet long. In determining its diameter, however, we must take into consideration the length of the remaining horizontal pipe beyond it—the riser connection—the diameter of which we have just determined.

That pipe having a friction resistance equal to 150 feet in length has now an additional resistance of 80 feet added to it, so that the diameter must be determined for a 230-foot circuit, which, according to our diagram, Figure 28, brings its diameter up to 3 inches.

This suggests the question as to whether it would be better to carry the 3-inch main to the bottom of the vertical part of the riser, as that part—the 10-foot length—was already a little smaller than actually required on account of their being no 2¾-inch pipe. The answer to this would be to let the 3-inch pipe and bends extend to the points *p p*, and thus use 3 × 2½-inch elbows. This puts the bends in the large pipe, and beyond this point 2½ inches are all that would be called for.

The rising line No. 4 is for average size radiators, and they are of the same size throughout (48 square feet) and four stories high. The upper one on the fourth story will require a 1-inch pipe, as seen by the curved line *d*, diagram, Fig. 26. The pipe to the third story will be 1½ inches, as seen by the line *C*, and the pipe for the second story is much nearer the 2-inch line (*b*) than it is to the 1½-inch line, while the line *a* for the first floor and 192 square feet is nearer the 2½-inch line than any other.

.   On the rising line No. 5 we have 250 square feet of sur- ·
face, while on No. 4 we have 192 square feet.   These amounts
taken together form part of the data by which to find the dia-
meter of the 25-foot lengths between risers 3 and 4.   If the
line stopped here, and did not run to riser No. 5, a 2½-inch
pipe would answer, as will be seen by diagram, Figure 28, if
the resistance of turns or elbows did not bring its valve higher,
as it is under a 100-foot circuit in length.   The extra resistance
caused by the lengths of the 3-inch pipe, etc., beyond it, how-
ever complicates the problem, as this resistance must be taken
into consideration.   The resistance caused by the length of the
rising lines was not considered in determining the size of the
3-inch main, as their vertical position augments the head or
causes an acceleration of power within themselves, which un-
doubtedly more than offsets the resistance their length would
cause if they were horizontal or nearly so.   With the horizon-
tal mains, however, the power to move the water within them
comes entirely from the boiler and their own difference of level
above it, and therefore the power of the boiler, or rather the
power of the head caused by the relative weights of water
within and without the boiler, measuring from the level of the
return-pipe, where it enters the boiler, to the top of the radi-
ators on the first floor, is all we can with safety depend on for
the velocity through our mains in this class of apparatus or
with any branched circuits, especially to different levels;
though, when providing for single circuits the total head due
to the successive floors can be safely taken, especially if the
small number of radiators supplied from it are on the same
level.

In determining the size for the main, therefore, between the third and fourth rising lines, the resistance of all the pipe beyond it must not be overlooked. It is a difficult matter to determine exactly what this amounts to. We have shown that a 2½-inch pipe would be ample if the extra riser did not exist. We can also show by our diagram that a 4-inch pipe would be ample if the total surface on risers 4 and 5 were all at No. 5, and therefore if we use a 4-inch pipe between risers 3 and 4, we know it must be a little more than ample.

This leads us to the adoption of an empirical rule, sufficiently accurate within the limits of the lengths and diameters that we have to deal with, which consists in considering the total length of the line of pipe or circuit beyond the point for which the diameter is to be determined as well as all the surface that is beyond it.

By Figure 26 we again determine the diameter for riser No. 2 as shown. This rising line increases the total amount of surface on the right of the boiler to 567 square feet, not including the surface of the mains and riser. To determine the diameter then for the 10-foot length of main between boiler and riser No. 2 we have to consider the whole length of our main circuit; thus (10′ + 25′ + 40′) × 2 = 150′, and then approximating 567 square feet on diagram, Figure 28, we find it calls for a 4¼-inch pipe.

It may appear to many that further examples would be unnecessary in the use of these diagrams. My apology, however, to those who grasp a matter quickly is, that these papers are for practical men who desire to see a matter in as many of its bearings as possible, and hence I will trouble the

reader to go over the subject with me in selecting diameters for the pipes on the left hand side of the boiler, where the loss is to be about 34 degrees.

These pipes are long and the radiators on them are large, and in riser No. 2 there are a number of extra elbows caused by the pipe going around a light-shaft, elevator passage, bank vault, or any other obstruction to its direct course.

We will commence at the head of riser No. 1 and pick out its diameter for 200 square feet on the second story for a loss of 34 degrees by diagram, Figure 27, and we find it to be about half way between 1½ and 2 inches. We have now to use our judgment as to whether we wi'l use a 1½-inch pipe or a 2-inch pipe. There is a disposition always to use the smallest pipe possible to lessen the cost. At a moment of indecision like this the natural suggestion is, What is the additional loss, greater than 17 degrees, if we use the 1½-inch pipe? The answer to this is readily found by the diagram as well as the answer to the question, What would be the diminution of loss of temperature if the larger size pipe (2-inch) was used?

To find the additional loss in this case, let us follow the curved line *b* (Figure 27) for the second story until it crosses the 1½-inch line. Opposite this point in the column of square feet of heating surfaces we find 137 square feet, indicating that a 1½-inch pipe will supply that number of square feet of heating surface on the second story, or in other words, that it wil' carry the water for 137 square feet to this point, instead of for 200 square feet under the conditions we first required. Our problem now is simply that if 137 square feet cools a given measure of water 34 degrees, what will 2co square feet cool it?

which in this case is

$$\frac{34° + \ 200 \square}{130 \square} = 49.6 \text{ degrees}$$

as the loss of temperature we will get if we use the $1\frac{1}{2}$-inch pipe.

If we desire to know what the loss of temperature will be if we use the 2-inch pipe we will have to run down the line *b* (Figure 27) until it crosses the 2-inch line, where we find 275 square feet ; in other words, then, we have the pipe and quantity of water for a loss of 34 degrees for a radiator of 275 square feet, and knowing how much 275 square feet should cool it we have to find what 200 square feet only will cool it, which will be

$$\frac{34° + 200 \square}{275 \square} = 24.4 \text{ degrees.}$$

Therefore we will consider a loss of 49.6 degrees too great and use the 2-inch pipe, which we are at liberty to bush to $1\frac{3}{4}$ inches if we desire an equal distribution of the flow.

This brings us to the first floor, at which point we must provide for 200 square feet + 200 square feet or 400 square feet. This calls for a pipe a little larger than $2\frac{1}{2}$ inches ($2\frac{6}{10}$ inches, Figure 27). We are obliged to use the $2\frac{1}{2}$ inches, however, and, as before explained, the commercial size being a little larger than the actual, it is ample if we have no considerable length of it.

The diameter as first established is for circuits of 100 feet —50 feet flow and 50 feet return. In this case the riser is 200 feet away from riser No. 2, and consequently the circuit, or rather the combined lengths of the two pipes—flow and return

—is equal to a circuit of 400 feet.   We have, therefore, to pick out the diameter by diagram on the curved line 400 feet opposite 400 square feet, which gives us a 3½-inch pipe.

We have allowed nothing for the two elbows at q.   If we enlarge the pieces r just above the elbows to three inches instead of 2½ inches we will probably reduce their value to a point not worth considering if we use nicely reducing elbows without bushings, and this would be advisable.

This brings us to the riser No. 2.   Though a ¾ pipe is nearly ample we will use a 1-inch for the third story.   The second story calls for a pipe somewhat smaller than 1¼ inches, and the first story for one nearly two inches.   From the point s, however, to the main we must use a much larger pipe on account of the length and the number of the elbows.

The length is $12'+12'+12'+12' = 48'$, or, say, a 100-foot circuit, and assuming the diameter to be 2½ inches, ten elbows will call for 1,000 diameters more, or 3,500 inches, an addition of 208 feet, making a circuit of a little over 300 feet or its equivalent, in the matter of resistance, and for 180 square feet of surface, brings the diameter to nearly 2½ inches, and with the resistance of the tee in the main added, would probably bring it to fully that size.

It would be a safe practice in cases where the distance from s to the first radiator is short, to make it the diameter of the horizontal pipe, as it can be done at so small a cost.

Another good point of practice would be, when starting from the mains or returning to them with a nipple and elbow, to make the nipples and elbows a size larger than the branch and use a reducing elbow.   In such cases the resist-

ance for the tee in the main may be omitted so far as the head for change of direction is concerned.

We have now to find the diameters of the mains between the rising line No. 2 and the boiler. On the first riser there is 400 square feet of surface, and on the second 180 square feet, or a total of 580 square feet. If all the surface was on the first riser we would require the diameter for $(50'+200')$ $\times 2 = 500'$, if there were no elbows; and looking on the diagram we find the diameter to be about 4.2 inches for 580 square feet at this length of circuit. We have some elbows, however —3, not counting the ones at q—and also some resistance from the tees, that will undoubtedly bring the total resistance up to what it would be in 600 feet of straight pipe. This calls for a pipe very nearly 4½ inches, and as 4½ inches is our nearest commercial size we are obliged to use it, and would probably have to use it even if there were no elbows, as a 4-inch pipe would run under the standard of 34 degrees loss.

We, however, carry this pipe only to the second riser of this diameter, and a question comes up here whether we should not increase it somewhat more for the resistance of the long branch with many turns to the second riser? This resistance probably need not be considered when we take the augmented head due to a riser three stories high into consideration, and when we remember that we are already somewhat larger in diameter than the surface actually called for.

CHAPTER XV.

Single-Circuit Mains, and How to Run Them—Table of Standard Dimensions of Wrought-Iron Pipe—Cases Where the Inlet and Outlet of Radiator may Require to be Larger than Ordinary—Resistance Within Radiators and Coils —Resistance of Flat Coils—Resistance of Box Coils—Resistance of Wall Coils.

SINGLE CIRCUITS.

IN running a single circuit from a boiler, the head caused by the total height is to be considered.

Figure 31 shows two single circuits run from the head of a boiler, one vertical and one horizontal. The vertical one is 50 feet high and the horizontal is 50 feet long to first story ; both 100-foot circuits with 100 feet of surface each. For a loss of 34 degrees the vertical pipes, 50 feet high, will require a pipe very little over one inch, while the horizontal circuit requires a pipe 1½ inches, which is about 2¼ times more area than the former.

The resistance for radiator connections — elbows and valves—is not considered. If we add resistance equal to 100 feet to each, for reasons explained earlier in these papers, we

would have to use a 1.71-inch pipe in lieu of the 1½, and 1.15 instead of the 1-inch pipe.

The fitter must now use his judgment as to whether he will take the next larger commercial size or be content with the diameter for 100 feet of length. To assist his judgment I would suggest that he refer to a table of standard dimensions

FIGURE 31.

of wrought-iron pipe which I here introduce to facilitate the matter and make the subject more complete.

The branches of the risers in the diagram, Figure 30, should have the diameters given in Tables V. or VI. (pages 122 and 123), as the case may be. In long single circuits, however, when the diameter of the flow and return pipe is enlarged to compen-

sate for length and extra resistance of bends, the connections into the radiator or coil should be of the same diameter as the pipe. This in some cases may become impracticable if the radiator is a long distance away and consequently the largest diameters possible for inlet and outlet under the circumstances must be employed and elbows avoided, with particular atten-

TABLE No. VII.—*Standard Dimensions of Wrought-Iron Pipe for Steam, Water, etc.*

Nominal Inside Diameter.	Actual Inside Diameter.	Length of Pipe per square foot, Outside Surface.	Internal Area.	Length of Pipe con- taining one cubic foot.
Inches.	Inches.	Feet.	Inches.	Feet.
⅛	0.270	9.44	0.0573	2513.
¼	0.364	7.075	0.1041	1383.3
⅜	0.494	5.657	0.1917	751.5
½	0.623	4.547	0.3048	472.4
¾	0.824	3.637	0.5333	270.
1	1.048	2.903	0.8627	166.9
1¼	1.380	2.301	1.496	96.25
1½	1.511	2.01	2.038	70.65
2	2.067	1.608	3.356	42.91
2½	2.468	1.328	4.784	30.10
3	3.067	1.091	7.388	19.50
3½	3.548	0.955	9.887	14.57
4	4.026	0.849	12.730	11.31
4½	4.508	0.764	15.961	9.02
5	5.045	0.687	19.990	7.20
6	6.065	0.577	28.889	4.98
7	7.023	0.501	38.738	3.72
8	7.982	0.443	50.039	2.88
9	8.937	0.397	62.733	2.29
10	10.019	0.355	78.838	1.82
11	11.000	0.325	95.033	1.51
12	12.000	0.299	113.098	1.27
13	13.25	0.273	137.837	1.04
14	14.25	0.255	159.485	.903
15	15.43	0.239	187.04	.77

tion being paid to reaming the ends of the pipes and nipples and the avoidance of valves or fittings that cause sharp or abrupt shoulders.

There is furthermore a resistance caused by the water passing through the radiator that we have not considered heretofore. It is small in ordinary cast-iron hot-water radiators, whose tubes are connected top and bottom, or even in wrought-iron radiators so constructed.   With coils, however, it becomes very great and cannot be overlooked.

For instance, if an inch pipe is capable of carrying water to the inlet of a 1-inch flat coil (for any reasonable loss of heat), it may probably be entirely inadequate to carry it through the coil and have favorable results.   It would probably carry sufficient water through a radiator satisfactorily well as the large chambers cause so little extra resistance, but in the flat coil there is its own pipe and return bends of the same diameter as the flow-pipe that probably adds several times more resistance than there is caused within the mains or connections.

Take the example of a coil 5 feet long and 10 pipes high. made of 1-inch pipe, as shown in Figure 32.

It has 50 feet of plain pipe and 9 return-bends, and assuming them to be of the very best pattern, it will be no exaggeration to consider each of them to cause as great a resistance as a common elbow, if an ordinary close pattern bend causes resistance equal to 142 diameters (see page 74.)

In this case then we have 9 bends × 100 diameters + 12 inches = 75 feet.   In other words the bends alone add a resistance equal to 75 feet of straight pipe, so that the resistance of the coil is equal to that of 125 feet of 1-inch straight

pipe, and with carelessly reamed ends may reach a resistance equal to 150 feet, and adding to this the resistance of ordinary connections—10 to 15 feet long or thereabouts—with a valve and six elbows, which was shown earlier to be about equal to that of 100 feet of straight pipe, we have a total resistance from the flow main through the coil and back to the return-pipe equal to that of 250 feet of 1-inch pipe when straight.

If we notice where the second and third curved lines—200 and 300 feet respectively, in the diagrams, Figures 28 and 29 —cross the line for 25 square feet of heating surface, we will see that in the case where the loss of temperature is about 34 degrees—Figure 29—they cross close to the one-inch line, while in the case of the 20 degree—diagram, Fig. 28—they cross near the 1¼-inch line. This shows that a coil one inch in diameter with its valves and connections cannot be greater than ten pipes high and five feet long, and circulate with a less loss than 34 degrees, provided it is no higher in the house than the first floor. For every return bend that is omitted 8 to 10 feet of inch pipe can be added in the coil by increasing its length between the return bends and diminishing the number of pipes high.

In considering box coils and their relation to flat coils, in the matter of their sections, the resistance of the valve and connections is to be omitted.

The leaf of a box coil 5 feet long and 10 pipes high will have a resistance equal to between 125 and 150 feet lineal of one-inch plain pipe. This is about 20 square feet of surface to the leaf and would call for about a *one*-inch pipe for a loss of 20 degrees by diagram, Figure 28.

This is probably the greatest length of section of that diameter that should ever be used in a box coil for direct radiation.   For indirect radiation they should be shorter, and this question will be treated of hereafter.

In the construction of flat coils, therefore, the resistance within the coils must be carefully considered, as the diameter of the pipe of the coil must always depend on the length of the circuit and the amount of heating surface it contains.   In treating of radiators we did not consider the resistance within them.   Usually it is small, but this depends on the make and how closely they resemble a coil, and particularly a coil of small diameter.   For instance, the resistance caused by the passage of water through the base of an ordinary vertical radiator and through the aggregate of its pipes may well be taken as no greater than the resistance of a short 3-inch pipe. If this radiator, then, can be supplied by a 1½-inch pipe under a scanty head of 1 or 1½ inches, the extra resistance caused by the radiator will be the same as that caused by the 3-inch pipe.   And under the rule that when *quantity and length are constant the head will vary inversely as the fifth power of the diameter*, we have fifth power of 1 = 1, and fifth power of 3 = 243, so that the extra resistance caused by a properly made radiator is only $\frac{1}{243}$ part what the resistance of the connection would be, and consequently I have omitted it to prevent introducing elements that would unnecessarily complicate the subject.

The resistance of the rising lines are omitted for a like reason in considering the horizontal mains, and their resistance is not added in consideration of the augmented head due to

their elevation, which, as explained before, probably more than compensates for the resistance caused to the flow of the water.

Let us consider the resistance of a $1\frac{1}{4}$-inch diameter coil of the class known as flat coils, Figure 32. Assume it is 4 feet long and 12 pipes high, a common size and form for small rooms. There is 48 feet of $1\frac{1}{4}$-inch pipe and 11 return bends. The return bends will each have a resistance equal to 100 even if they are of the best form of merchantable fitting. So that we have

$$\frac{1100 \times 1\frac{1}{4}''}{12} = 114\frac{7}{12} \text{ ft.} + 48 \text{ ft.} = 162\frac{7}{12} \text{ feet in length,}$$

or, more properly speaking, the equivalent of $162\frac{7}{12}$ feet in length, so far as resistance is concerned.

We have now to determine its heating surface, and as 2.3 feet lineal of $1\frac{1}{4}$-inch pipe is a square foot, according to the manufacturers' rating, we have

$$\frac{48}{2.3} = 21 \text{ square feet,}$$

to which may be added about a square foot for every *three* return bends, so that the coil contains 25 square feet of surface. This calls for the passage of about $1\frac{1}{2}$ gallons of water per minute (see page 107), if the loss of heat from the water is to be 10 degrees, in its passage through the coil. By Table III. (page 61), we find that one gallon requires a head of .033 inches to pass through a $1\frac{1}{4}$-inch pipe *ten* feet long, and under the rule that *the head varies as the square of the quantity passed through a pipe*, we will have for $1\frac{1}{2}$ gallons

a head of .07325 inches. Thus $1^2 = 1$, and $1.5^2 = 2.25$, or $2\frac{1}{4}$ the times the head required for the single gallon.

This is for 10 feet of pipe, and our coil is $162\frac{7}{12}$ feet long, its equivalent, so that the total head for the coil is

$$\frac{.07325 \times 162.6'}{10'} = 1.19 \text{ inches of head,}$$

or the total resistance of the coil, provided it is exactly $1\frac{1}{4}$ inches in diameter.

As a matter of fact it is a little larger, the standard table giving the inside diameter of $1\frac{1}{4}$-inch pipe as 1.38 inches.

FIGURE 32.

A question here arises as to the propriety of considering the extra diameter due to the commercial pipe. It not only applies to coils but to all pipes. After a pipe is in use for some time it corrodes more or less and an incrustation forms on its inside. As this incrustation is about of the same thickness for small and large pipes alike it certainly affects the flow in small pipes more than it does in large ones. If we also consider careless cuttings with wheel-cutters and the neglect to ream the ends, our judgment would be not to allow anything for it,

or rather not to take into consideration the excess of commercial sizes over the nominal diameters.

On the other hand, however, the coating is not as great as might be suspected from the fact that the air is expelled from the water, and as it is desirable to use flat coils in many cases without increasing the total resistance beyond 1½ inches of head, we will consider the increase of diameter that we may the better find how long a connection we can use without getting our total resistance beyond 1.4 inches or 1½ inches, or, say the head for a lower story. Therefore, as "the head varies inversely as the fifth power of the diameters of pipes," we have fifth power of 1.25 = 3.05, and fifth power of 1.38 = 5, from which we get

$$\frac{1.19' \times 3}{5} = .714 \text{ inch}$$

as the head for a 1.38-inch pipe (the commercial 1¼-inch).

This points to the fact that we can just about double the coil's length (without connection) before we reach the 1.4 inches of head, due to the height of the first floor above the boiler; or it shows that we can add about one-third to its surface and use a set of ordinary connections 1¼ inches in diameter, with elbows and valve, and not exceed the 1.4 inches of head.

This shows that a flat coil of 1¼-inch pipe should not exceed 33 square feet of surface, with pipes 4 feet long, if it is to be used on the first floor of a building, and it is well to add here that no flat coil should be supplied with a pipe of a smaller diameter than itself.

As the coils go higher in the house, the lengths may be

increased with the head, or the diameter decreased. I am not in favor of a decrease of diameter for the second floor with this class of coils, but as it may be necessary, the rule, which is the converse of the last given, is, that the diameter will vary inversely as the fifth root of the head for constant lengths and quantities of water. It must also be remembered that the heating surface is decreased in the proportion of the diameter of the pipe, so that the length must be increased to have equal heating surfaces.

Example : For the first story the head was shown to be about 1.4 inches, and for the second story twice as much, or 2.8 inches ; so the heads are in the ratio of one and two, and so on for higher stories, or for elevations of 15 feet each. Then as the fifth root of 1. is 1., and the fifth root of 2. = 1.16, we will have

$$\frac{1.25'' \times 1}{1.16} = 1.08 \text{ inches}$$

as the diameter for the pipe of the coil for the second floor that will pass the same quantity of water as the $1\frac{1}{4}$-inch would on the first floor—other things being the same—and the divisors 1.25 and 1.32 will give the diameters for the third and fourth floors respectively, so that for the third floor the diameter becomes just one inch. The length of the 1-inch pipe or coil will now have to be increased until it has the same heating surface as the $1\frac{1}{4}$-inch coil ; and as 2.3 lineal feet of $1\frac{1}{4}$-inch pipe is equal to a square foot, and three feet of 1-inch has a like surface, our resistance will be increased in the

proportion of the increase of length.   Therefore the head 1.19 inches, as found before, will be

$$\frac{1.19" \times 3}{2.3} = 1.552 \text{ inches of head.}$$

If we made corrections for the commercial size over the nominal, it would lessen the head thus found, but for obvious reasons this had not better be done.   It shows, however, that an inch diameter coil on the second floor will do almost equal work with a 1¼-inch coil on the first floor; the surfaces being the same, and that for the third floor an inch pipe or coil of the same surface will pass more water than a 1¼ on the first floor.

The total head for a third floor being about 4.2 inches, and 1.5 inches or thereabouts being required for resistance in mains, there is 2.7 inches of head remaining to overcome the resistance of an inch coil.   If a coil, therefore, of 25 square feet of surface requires a head of 1.552 inches, 2.7 inches of head will force water through a coil of 43.3 square feet of surface. Thus

$$\frac{25 \times 2.7}{1.552} = 43.5 \text{ square feet.}$$

There is an advantage in using connections to a flat coil of a larger diameter than the coil itself.   There is no object, however, in designing work in this manner, and the rule should be to have a flat or return bend coil and its connections of the same diameter throughout by making the flat coil of the proper diameter at the commencement.

In the improvement of a defective circulation considerable

can be gained by so doing, as in that case the water will be carried to the top pipe of the coil with a reduced resistance and consequently more power or head will remain to overcome the resistance of the coil.

WALL COILS.

Header or wall coils, sometimes known as mitre coils, have a low resistance when compared with flat coils. Figure 33 shows a coil of this arrangement : a is the inlet or connection pipe ; $c\ c$ the headers at the ends ; $b\ b$ the pipes or heating surfaces, and e the outlet connection.

FIGURE 33.

We will assume that the inlet a is an inch pipe and that the pipes $b\ b$ are also *one* inch in diameter and 15 feet long, giving the coil about 20 square feet of surface, not including the headers or elbows, nor will we consider the resistance of the elbows or headers for the present.

We can also assume the resistance in the inlet and outlet pipes to be equal to 100 feet of 1-inch pipe, or, say, about

one inch of head for the quantity of water necessary for a coil of 20 square feet.*

The question now is : What additional resistance is caused by the coil alone to the passage of the water around the circuit ; or, in other words, what is the total head necessary to pass the water through the coil when the head to pass it through the flow and return pipe is one inch ?

A convenient and approximate rule that will perhaps always do in pipe practice, is to say, that when a pipe is branched into any number of pipes greater than itself, though of the same diameter, that the resistance in these pipes for equal lengths with the first pipe, will be in the inverse ratio of the number of branches.

For example, the water flowing through *a* and *e* has a resistance equal to one inch. When it is divided into four branches, *b*, *b*, etc., each pipe has to take care of *one-fourth* of the water ; and under the rule that the friction in pipes increases or diminishes in the proportion of the square of its velocity, it is evident that as but $\frac{1}{4}$ of the water goes through it the resistance will be but $\frac{1}{16}$, and as we have four of them the resistance in them will be $\frac{4}{16}$ths, or $\frac{1}{4}$ inch.

In like manner if six pipes are branched from one, all of the same diameter, the resistance of the whole six would be just one-sixth of the resistance in a single pipe. Thus one-

* NOTE.—It matters not what resistance we assume for the inlet and outlet of the coil, but in cases of this kind it is better to assume a close approximation to the truth, the better to familiarize ourselves with the subject.

sixth of the velocity calls for $\frac{1}{36}$th of the power, and this mul-
tiplied by 6 equals $\frac{6}{36}$ths or one-sixth.

This would be for equal lengths, but in the case of the first
example, Figure 33, we have connections with resistance equal
to between 90 and 100 feet of straight pipe or its equivalent,
while we have the pipes of the coil of only 15 feet in length,
or about $\frac{1}{6}$ of the length of the connection. Then, under the
rule that the resistance in pipes is about directly as the length,
our $\frac{1}{4}$ inch is reduced to a $\frac{1}{6}$ of the $\frac{1}{4}$ or to $\frac{1}{24}$. Thus it is
that though the total resistance in the connections or that part
of the circuit a and e, in Figure 33, is 1 inch, the resistance in
the coil is but $\frac{1}{24}$ of an inch, or rather it would be if there were
no elbows or fittings in the coils; but there is an inch elbow
to each 15 feet of length of coil, which adds as much resist-
ance as 100 diameters of pipe, or about 8 feet more to the
length in the point of resistance, and there is the resistance of
the branch tees at both ends of the coil, which we are unable
to determine with much accuracy but which cannot be greater
than the resistance of the elbows. Allowing them to be the
same as the elbows, then we have 8 feet for elbows and 8 feet
for headers, and as the length of our coil in the first place was
15 feet, we have $15' + 8' + 8' = 31'$ as our length for resistance.

Therefore the elbows, etc., just about double the resistance
of the pipes of the coil, and instead of adding $\frac{1}{24}$ we must add
$\frac{1}{12}$ of an inch as the head necessary to overcome the resistance
of the coil.

Ordinarily, then, the resistance for well-made wall-coils is so
little we need not take them into consideration any more than
we did resistance through radiators unless they are very long.

PROPORTIONING APPARATUS FOR INDIRECT HEATING.

I T has been shown, by the experiments of different investi-
gators earlier in these papers, that a square foot of direct
radiating surface gave off heat to the surrounding air in
amounts varying from 1.25 to about 2.25 heat units per hour
for each degree the radiating surface was warmer than the
air. The variation is due, primarily, tó the form and nature
of the surface, and secondly, to its arrangement for the free
passage of the air.

With direct radiation the movement of the air usually
depends solely on the form of the surface. When the air can
reach all of the surface readily and pass rapidly upwards the

best results are obtained, and each increment of heat imparted to the air causes an increment of upward velocity, though in a less ratio.

With the best ordinary radiators, however, it is not safe to count on imparting to the air more than 2 heat units per square foot per hour per degree of difference of temperature. If, however, the air for indirect radiation is forced over the radiators by the draught of warmed flues or by fans, a square foot of surface will do more work, and in steam coils where the pipes are large enough to keep up a constant pressure the increase of work or heating is nearly proportional to the increased volume of air passed through the coil. With hot water, however, this does not follow, for the simple reason that the water when it is cooled passes but slowly away to make room for more, and that nothing is gained by abstracting heat from it any faster than it can be supplied.

The ability of hot water to supply and maintain the heat depends on its velocity. Its velocity is also somewhat accelerated by the greater abstraction of the heat, but this acceleration of velocity bears such a small ratio to the heat taken away, that with an artificial draught the water in the coil is so much cooled as to be entirely useless for heating unless the pipes are of such a diameter that they will convey more heat, under their most unfavorable conditions, than the maximum quantity of air to be passed can take away.

We must assume some standard loss of temperature, to be occurring while the water passes through the coils, that will satisfy us. For an "open" apparatus, or one in which the maximum heat and pressure depends on the height of the

building, a temperature of about 212° Fah., is the greatest
that can reasonably be expected to be maintained at the boiler.
If we get the water to the coils at 210° Fah. and cool it to
190° Fah. in the coil we should call it good practice, and it is
on this basis that we shall consider the following problems in
indirect work.

There are two reasons for warming by indirect radiation.
The first and most important one is to obtain ventilation as
well as heat, and the second is to avoid having the room en-
cumbered by a direct radiator or coil. The first is the only
one we will consider.

It is understood, of course, that heat is lost in two direc-
tions from a room warmed by indirect radiation. A certain
amount of heat is lost through the glass of the windows and
through outside walls, and this loss is a constant amount irre-
spective of the amount of air passed through the room. The
other is the heat carried out through the vent-flues, and taken
together they form the total heat necessary for a room warmed
by indirect radiation.

The heat lost through the glass and walls is about the same
no matter what mode of heating is used. If the walls of a
room were perfectly air-tight the heat lost through them by
conduction, radiation, etc., will be just equal to the heat given
off by a direct radiator suitable for the same room. An indi-
rect radiator must furnish this heat and also enough heat to
warm, to the mean temperature of the room, the air escaping
through the vent-flues.

Assuming that we have a corner room 14x18 feet on the
floor and 10 feet high, with 4 windows of 25 square feet each,

we will find that we have 220 square feet of outside wall and 100 square feet of glass passing heat from the room. Assuming again that 10 square feet of wall cools the room about as much as one square foot of glass, the cooling effect of the walls and windows will be equal to 122 square feet of glass.

According to Mr. Hood's experiments (page 98) the loss of heat per square foot of glass is equivalent to about 1.28 cubic feet of air cooled from the inside to the outisde temperature per minute, and if we take the room to be 70° Fah. and the outside air zero, we have $1.28 \times 70 \times 122 = 10931.2$ cubic feet of air cooled one degree in a minute or 655,872 cubic feet per hour, which if we divide by 50 gives us the units of heat lost per hour[*]. Thus

$$\frac{655872}{50} = 13117.4 \text{ heat units}$$

that are passing each hour through the walls and windows of this room on a very cold day.

To this must be added the heat required for ventilation.

---

[*] The divisor 50 may be taken as a constant for our purpose when finding the units of heat in air. It is obtained thus: One pound of air at 32° Fah. under the pressure of an atmosphere (29.9 inches of mercury) will occupy a space of 12.38 cubic feet and its specific heat is .2379 when water is unity at the same temperature. In other words, a pound of water will hold 4.2 times as much heat as a pound of air and, therefore, 4.2 pounds of air require only the heat of one pound of water for the same increase of temperature. Thus 12.38 cubic feet × 4.2 — 52. cubic feet of air will absorb as much heat as one pound of water to warm each one degree.

Corrections for humidity are not considered, nor for the increase of volume of air when warmed above 32° Fah. The weight of 52 cubic feet of air at 32° is about the same as that of 60 cubic feet at 100°, but corrections for average humidity will reduce it somewhat, but for all ordinary ranges of conditions that we have to deal with in warming 50 is a good average, as in winter weather we may be taking in air as cold as zero, though the average is presumably not below 36° for a winter in or near New York.

This amount of heat must be taken as the difference of temperature between inside and outside, multiplied by the cubic feet of air admitted in an hour divided by the constant 50.

The room contains a little over 2,500 cubic feet and requires a change of air every 15 minutes, or four times in an hour, which will be 10,000 cubic feet of air per hour warmed to 70° Fah. Thus

$$\frac{10000 \times 70°}{50} = 14000 \text{ heat units.}$$

Thus it will be seen we require a total heat for this room equal to $13117.4 \times 14000 = 27117.4$ heat units per hour.

There are two methods, either of which we may follow, to find the coil surface. One is—we have shown that it requires 14,000 heat units to warm this air (2,500 cubic feet four times an hour) 70 degrees, consequently the heat necessary for the walls and windows (13117.4 heat units) will warm it 61.2 degrees additional, so that the air entering the room must have a temperature for all purposes of 131.2 degrees.

The coil having a mean temperature of 205 degrees, and the initial temperature of the air being zero, the mean difference of temperature between the air and the coil is 139.4 degrees. As each square foot of surface will give off heat equal to two heat units per degree of difference per hour, we have the total heat units divided by 139.4×2. Thus

$$\frac{27117.4}{139.4 \times 2} = 97.26 \text{ sq. ft.}$$

as the necessary surface of the coil.

The units of heat given off by the coil or radiator surface is the variable factor. We have taken it here as 2, which is probably a safe medium for all work. If the coil surface does

better, more water will be cooled. The cooling accelerates the velocity of the water, but as it is only in a ratio of about the square root of the cooling, the water gets rapidly cooled, and soon becomes unable to warm the air. Therefore the coil should be proportioned so as to do its greatest work under the least difference of temperature, and when it is not called upon for its greatest duty the water simply circulates hotter and slower.

I do not wish to convey the idea that it is absolutely necessary to make indirect coils as large as in the example, as by the rough and ready rule often used it figures out about one square foot to about 25 cubic feet of space in the room. With my present knowledge on the subject, however, I would advise those who use this rule to limit themselves to 1 to 30, and to work inside of it when possible, keeping in mind however that the amount of air moved for the purpose of ventilation affects any such arbitrary ratios.

I regret that I have no experiments but my own to offer on the effect of cooling in indirect hot-water coils. They were made some two years ago with the view of determining the value of a square foot of a new form of surface when compared with a box coil, which latter may be taken as a standard, and throws some light on the subject under consideration. The following are extracts from a report made at the time :

"In my experiments with hot-water heating on a 'compound' indirect coil, *six* pipes wide by *two* pipes high by forty and one-half inches (40½") between the bends and headers *versus* an ordinary box coil *six* pipes wide by *ten* pipes high by thirty-six inches (36") between the bends.

" The twelve pipes of the compound coil, exclusive of bends, contained forty feet and six inches (40′ 6″) lineal of 1-inch pipe. The sixty pipes of the box coil, exclusive of bends, contain one hundred and eighty feet (180′) lineal of 1-inch pipe.

" The commercial rating of the compound coil was 48 square feet of heating surface, and the commercial rating of the box coil 74 square feet.

" The analysis of the surface of the box coil is as follows : 180 feet lineal of 1-inch pipe ▬ 62 square feet—

$$\left(\text{thus,} \; \frac{180 \; \text{feet}}{2.9 \; \text{sq. ft.}} = 62\right).$$

The two headers and fifty-four bends made over twelve square feet additional, but I allowed only that amount for them, as some makes of bends on the market are found to be smaller than those used.

" The twelve pipes of the compound coil have each a helical coil of No. 14 square wire wrapped about it—also in the form of a helix—and from which it takes its name of 'compound' coil.

" The coils were set, as shown in Figs. 34 and 35, and connected to a Hitching's hot-water, base-burning boiler ; the vertical distance between the inlet to each coil and the return outlet to the boiler being six feet and nine inches (6′ 9″), and the flow and return pipes in all parts being 1½ inches wrought iron with ordinary cast-iron fittings.

" On the first day's trial the bottom of the coil boxes were removed, and the outlets on top were 12″x16″ or 1⅓ square feet.

"On the second day's trial the bottom of the coil boxes were restored and connected with the outside atmosphere by 12″x12″ tin ducts, and the apertures on top were also made

FRONT ELEVATION

FIGURE 34.

12″x12″, being drawn in from 12″x16″ by suitable inverted hopper-shaped tin ducts. The heights from the tops of the coil to the tops of the outlets were 20 inches, and the whole

apparatus was set up to imitate an apparatus when set within
a basement of from 7′ 6″ to 8′ in the clear, and supplying air
to the first floor registers ; or, in other words, about the poor-
est ordinary condition to be met in practice, as the air to the
upper floors of a house will always move with a greater velocity
—other things being the same.

" The following table gives the results of the observations
of two days' trials.

" The illustration is a side and end view of the apparatus as
used ; A being the box coil, B the compound coil, C the boiler,
D the expansion tank, I I the cold-air inlets, J J the warm-air
outlets, and H H the thermometers.

" The flow pipes to each coil were taken from opposite sides
of the boiler, and the return pipes entered the boiler at oppo-
site sides, so as to have no branched pipes, and in all cases to
have both coils under exactly similar conditions.

" The difference of temperature of the water entering the
coils on the first day (col. 9) is accounted for by the fact that
the temperature of the water was advancing at the time the
observations were taken; the box coil being always noted first.
This, however, does not affect the result as deduced in col. 15,
except to be slightly in favor of the box coil.

" The units of heat were obtained by finding the heat added
to the air.   This method, of course, is subject to error, except
for comparative purposes.   Care was taken, however, with the
use of the anemometer, and probably fully as much air passed
as was recorded.

" It shows in the case of the box coil for the first day, when
used almost as a direct radiator, a loss or passage of 1.343

heat units per hour per square foot, per degree of differ-
ence between air and coil, and it shows a loss to the water of
16.16 degrees ; and on the second day, when used exactly as

SIDE, ELEVATION

FIGURE 35.

an indirect coil, the loss or passage of 2.475 heat units with a
loss of temperature to the water of 20.06 degrees.

TABLE No. VIII.—*Average of the Observations for Each Day.*

No.	Observations	Compound coil, 48 sq. ft. (1st. day)	Box coil, 74 sq. ft. (day)	Compound coil, 48 sq. ft. (2d.)	Box coil, 74 sq. ft. (day.)
3	Observations.	3	3	4	4
4	Temperature of air as it entered coil box. (F.)	85°	85°	78°	78°
5	Temperature of air as it escaped, top of box. (F.)	143.3°	134°	166°	150°
6	Mean temperature of air. (F.)	114°	109.5°	122°	114°
7	Velocity at top through 1x16-inch aperture. Feet per minute. (Ft.)	110.3	86.5		
8	Velocity at top through 12x12-inch aperture. Feet per minute. (Ft.)			151.22	229
9	Temperature of water entering coil. (F.)	195°	191.66°	206.04°	206.04°
10	Temperature of water leaving coil. (F.)	185°	175.5°	194°	186.38°
11	Mean temperature of water in coil. (F.)	190°	183.58°	200.2°	196.39°
12	Vol. of air per minute in cubic feet.	115.336	159.1	157.22	229
13	Vol. of air per hour in cubic feet at 32°.	5,666	7,811.8	7,050	10,956
14	Total heat units in air for an hour.	6,352.46	7,361.1	11,930.8	15,169
15	Units of heat given off per square foot of commercial surface for each degree Fah. difference of temperature between air and coil.	1.741	1.343	3.18	2.475
16	Difference between air entering and leaving coil boxes.	58.3	49	88	72
17	Volume of air per hour passed at top of box in cubic feet.	6,920	9,546	9,073.2	13,740

" Reference to col. 15 will show the units of heat lost per square foot of surface.

" In the case of the compound coil the units of heat given off are greater.   It must be remembered, however, that this secondary surface had an actual surface per nominal square foot considerably in excess of the box coil.   The box coil's actual surface and nominal surface are the same.   The actual surface of the compound coil including that of the wire is much greater than its nominal surface ; hence though a commercial square foot of it will do more work, an actual square foot of it, wire included, does less work."

The compound coil, however, has but about one-third as much pipe per nominal square foot as the box coil has, hence the loss of heat to the water was but 10 degrees when the units of heat given off per square foot were 1.741, and on the second day the loss to the water was but 12.4 degrees when the units of heat were 3.18 per square foot.   This, of course, is on account of the less resistance to the flow of the water in the compound coil, as it had but two pipes per section to the ten pipes in the box coil with their return bends.

PIPE FOR INDIRECT RADIATORS.

We have next to find the diameters of flow and return pipes for indirect radiators.

A total head of one inch is the greatest that we should allow for indirect work in an ordinary cellar or basement. The head for 15 feet we found to be one and four-tenths inches, therefore, the head for 9 feet will be a little under 1-inch.

Taking the example of the indirect radiator already considered for a corner room of 2,500 cubic feet of space with outside wall surface and glass equivalent to a total of 122 square feet of glass in cooling power, and moving 10,000 cubic feet of air for ventilation,* when the external air is zero, we are at liberty to assume a loss of ten degrees to the water as it passes through the coil. Our total loss in heat units being 27117.4 it is plain we will have to pass only one-tenth of that many pounds of water if we cool it ten degrees, hence 2711.74 pounds of water will have to pass through the coil in an hour.

A U. S. gallon of water at 205° Fah. weighs 8 pounds and a very small fraction. The total pounds of water required, therefore, being $\frac{2711.74}{8}$ it is plain we require just 338.97 U. S. gallons of water per hour, or 5.65 gallons per minute.

By Table III. we find 6 gallons will pass through a 2-inch pipe 10 feet long with a loss of .15 inches of head. It is plain from this that a pipe 10 times as long or 100 feet, or a shorter pipe or circuit with elbows and valve sufficient to make a resistance equal to 100 feet, will cause 10 times the resistance, so that the head for 10 feet becomes .15 × 10 = 1.5, or nearly *one* inch, plainly showing us that we require not less than a $2\frac{1}{10}$-inch pipe for this radiator for a loss of 10 degrees and a 2-inch pipe for a loss of 20 degrees.

---

* This room is a fair example of a corner room in a private residence, and probably forms nearly a maximum of wall and window surface to cubic contents. As rooms increase in cubic contents the walls and windows increase in a less ratio. Hence I consider this an ample illustration.

This leaves little for resistance caused by the coil itself or for resistance through boiler, etc.   We have something in our favor by a 2-inch pipe being actually 2.07 in diameter.

On the whole a 2-inch commercial pipe is ample for this radiator doing this work if carefully reamed and easy bends are used with a gate valve instead of an angle or globe.   The coils or radiators, however, should be of a class that offer little resistance and if box coils are used have as many sections in the width as possible, as the more branches the large pipe discharges its water into the less the resistance.   The advantage of large diameters for coils or sections it is not necessary again to refer to.

The following diagram, Figure 36, is for mains for indirect work, on the assumption that it requires a 2-inch pipe for 100 square feet of surface for a 20-degree loss, and as the 2-inch connection above determined was for a heater of but 97.264 square feet this table and diagram allows nothing additional for resistance in coils or in boiler, except the little that is gained by the commercial over the actual size of pipes.

DIAMETER of PIPE in INCHES.

CHAPTER XVII.

Systems of Piping Used in Hot-Water Heating—Simple Circuit Apparatus—Compound Circuits—Branched Circuits—Table of the Ratios of Increase of Diameters for Increase of Surface or Increase of Length or Both, With Examples.

SYSTEMS OF PIPING USED IN HOT-WATER APPARATUS.

THE main pipes and systems of piping used in the warming of buildings by hot-water may be classed under two principal heads, as simple or single circuits and as compound circuits.

A compound circuit is made up of a number of simple circuits branching from a main circuit, whereas the simple or single circuit has no branches, and the water that is sent out through it from the boilers has no alternative but to pass forward and through the coil or radiator at the end of the loop, and return by the way of the return-pipe to the boiler again.

A good example of a simple or single circuit apparatus appeared in Volume 17 of *The Engineering and Building Record* in a description of Mr. Wyld's residence in Toronto, Canada, the boiler and other parts of which are here republished.

Seven circuits are here taken directly from the head of the boiler and returned into manifold headers at the bottom of the

boiler.   In this case, though for the sake of convenience they enter headers, there is no reason why they should not enter the side of the boiler, and in fact it would be a little better if they did, as less obstruction would thus be offered to the return flow of the water. An absolutely simple circuit has no branches, and usually supplies but one radiator or coil. In practice, however, it often becomes necessary to supply two or three radiators from near the end of a loop of a single circuit to avoid running too many pipes in one direction.   The fact, therefore, of two or even three radiators on the same level being supplied from a simple circuit does not make it what is usually called a compound circuit or one in which large mains are run with branches to the rising lines, etc., as is the usual practice in the United States in the large buildings for the Government.

On the other hand, in many buildings in Canada, warmed by hot water, the practice very much in vogue, if not the only one now resorted to, is to run separate circuits of main pipes from the top of the boiler to the principal divisions of the house or to one or two radiators.   This practice seems to have its advantage in the fact that the fitter who has not thoroughly studied the subject is much more likely to secure nearly uniform results in all parts of the house in the way of equable tem-peratures of the water in the radiators or the coils than he would if he were to run a large main and branch from it to the sections or rising lines.

In reality, this separate-circuit system is unnecessary if the work is planned by one who has time and ability to consider

carefully the conditions and requirements of the different lines and branches of a system, or if one is willing to use a main so

·Perspecte View· ·F·Wyld·Esq·
Showing Boiler and Pipes in Residence of Toronto
FIGURE 37.

large that there is no question of its ability to carry water hot enough to the remotest branches and radiators no matter how slow its current may be.

Currents through a branched or compound system will unquestionably take the direction of least resistance and will short-circuit unless planned by an expert, or unless the mains exceed their actual requirements in all parts ; while, as has been said, the separate circuit must circulate to the end, if it circulates at all, and hence the practical man often finds it to his advantage to use it.

In this house, as seen by **Figures 37, 38 and 39,** the separate

PLAN
SHOWING BOILER AND PIPES
IN RESIDENCE OF

F·WYLD·ESQ·
TORONTO

FIGURE 38.

system is carried out almost to the extreme. The circuits are all of 2-inch pipe, except the branches to the radiators, which are smaller. The return-pipes are also 2-inch, as they properly should be, the shrinkage of volume of the water being so inconsiderable between the flow and the return that no attention should be paid to it.

The circuits are numbered from 1 to 7 inclusive, and may be traced on the basement plan to the points where the con-

nections or rising lines run through the floor. Corresponding numbers are also found on the elevation and plan of the boiler so the lines or circuits may be readily followed.

Circuit No. 1 (2-inch diameter) supplies the two box coils in the lower hall, which have a surface of 144 and 110 square feet respectively, making 254 square feet on the circuit which loses about 20 degrees between flow and return. Circuit No. 2 supplies the parlor and pantry on the main floor, and then runs to the bath-room heater on the second floor and thence to the expansion tank; the total surface on this circuit being 182 square feet. No. 3 goes to the two heaters in the drawing-room, one of 108 square feet and the other of 96 square feet or 204 square feet on the 2-inch circuit. No. 4 supplies the two breakfast room coils of 66 square feet each; No. 5, the two dining-room coils of 112 square feet each; No. 6, the indirect coil under main hall, made of 1-inch pipe and containing 84 square feet, and No. 7, the front hall coil, second story, of 200 square feet, and the coil in the front chamber next to it of 108 square feet.

The connections to the coils are fairly ample—1½-inch for large coils, 1¼-inch for medium, and 1-inch for the small one in the pantry.

The circuits are treated very much in the way that plumbers in New York treat the circuits for domestic supply in their best work. The flow and the return pipes are supplied with valves close to the boiler, as plainly shown in the illustrations of the boiler. A line of small "draw-off" pipes are placed in the flow and return pipes on the house side of the stop-valves to allow the water to be drawn from a line or

circuit. This is plainly shown in Figure 37, and also the funnel into which they empty. This funnel is trapped into the sewer in the usual way, and the overflow-pipe of the expansion tank is brought to it to prevent a dry trap.

The letter F, for flow, indicates the outgoing pipes of the circuit and R the return pipes. Arrows also show the direc-

RESIDENCE OF F WYLD ESQ. TORONTO   SECTION   "The Engineering & Building Record".

FIGURE 40.

tion of the flow of the water in both pipes, so that a little study of the diagram will readily show the relations of one pipe to the other.

The pitch and flow of the pipe is always upward until it reaches the heater, so as to free itself of air at the highest point of the coil (the upper header), at which point an air-vent is used. The box coils are screened and have marble tops.

The total radiating surface in square feet, not including the mains, is a little over 1,500, and the boiler has about 51

BASEMENT   PLAN

FIGURE 39A.

KITCHEN

PANTRY

BREAKFAST ROOM

PARLOR OR LIBRARY

DINING ROOM

DRAWING ROOM

HALL

FIRST FLOOR PLAN

FIGURE 39B.

SECOND   FLOOR   PLAN

FIGURE 39C.

square feet of surface of all kinds—that is, fire-box and flue surface—which gives a ratio of boiler surface to radiator surface of 1 to 29.8.

The house was formerly heated by a hot-air furnace in the basement. With this arrangement 32 tons of coal were formerly burned in a winter without sufficient heat. The consumption of coal with the hot-water apparatus is said to be 19 tons, and the owner says the house is comfortably warmed in the coldest weather.

The size of pipes used is less in most of the circuits than that called for by diagram, Figure 29, while some of them come quite up to the proportion required by diagram, Figure 28, so that a careful examination of the temperature of the pipes would probably show that while some of the circuits lost only 20 degrees in passing from flow to return, the most of them lost fully 30 degrees.

The accompanying plans and diagram (Figs. 41, 41A and 41B) show the hot-water heating apparatus in the house of Mr. W. H. Carrick, of Toronto, Canada.

It is selected because it shows the hot-water plant of an average city residence that would ordinarily be warmed by a furnace in a comparatively cold country, and is typical of the system of piping largely followed in Upper and Lower Canada in the warming of buildings by hot-water circulation.

The plant had been one winter in use when the writer examined it, and is now several years old, and it has proved ample for the warming of a fairly well built wooden structure, that has been kept warm with water ranging from 120° to 190° Fah., according to the state and requirements of the weather outside,

and from which deductions may be drawn leading to the formation of data for heating surface for future reference by persons interested in heating problems.

It will be noted that the sizes of windows are shown, the cubic contents of rooms marked, the position of heaters shown, and their sizes marked, the figure attached to each indicating the number of " Bundy" loops, each loop being nominally 3½ square feet of heating surface in the hot-water radiator

For any one who wishes to work out the wall-surface I give the heights (in the clear) of floors; the principal or *first* floor (called in Canada ground floor) 10′ 6″; the *second* floor (called in Canada first floor) 9 feet, and the *third*, or attic, 8 feet.

The sizes of the mains and floor-pipes are marked on the plans, and the boiler is a No. 25 Gurney, old pattern ; the consumption of anthracite coal for a season being seven tons or just about 100 pounds per day in cold weather ; the climate of Toronto differing very little from the cities of Northern New York, Ohio, Michigan, Western Pennsylvania, and the Eastern States.   This, then, may be taken somewhat as a guide to the plant and its maintenance for a $5,000 house on a 20-foot city lot in the new districts of New York or in Brooklyn.

The diagram (Fig. 41) shows the skeleton apparatus, and a reference to the plans will show its relation to the house. The boiler is in the front cellar, pretty well central. There is some advantage in having a hot-water plant balanced in this respect, though when it cannot be carried out larger flow-pipes to the long side will compensate for the increased distance. The radiators marked *A* in the diagram are on the principal floor,

DIAGRAM

Showing Hot Water Pipes in the Residence-

of

W·H·Carrick·Esq·

· Toronto ·

~Note~

A— in first story
B— " second "
C— " third "

Boiler
in
basement

Figure 41.

those marked *B* are on the second floor, and the ones marked *C* are on the top floor.

The circuit No. 1 starts from the boiler 1½ inches in diameter, runs along with the rest of the pipes to near the pantry, where it turns upward and runs through the partition to the top floor, where it comes out and branches to the two radiators and expansion-tank.

Circuit No. 2 starts from the boiler two inches and continues on to the end of pantry, where it has a tee 2x1¼x1¼ ; one branch of which goes along parallel with side of pantry to pantry-door and then goes up through the partition and feeds sewing-room, bath-room, and upstairs hall. The other branch runs straight to the back end of house, and up through the kitchen to the nursery, where it heats the 1x10 radiator near the window. It may seem strange that this break was made in this way, but it was found when split at the point where the first pipe went up that the circulation was very sluggish, and that the nursery radiator did not heat properly, hence the change of running the two pipes parallel to this point.

Circuit No. 3 starts from boiler 1½ inches in diameter, and heats the 6-pipe radiator in the den, and then continues 1¼ on to one radiator in dining-room which has 14 loops.

Circuit No. 4 starts from boiler two inches in diameter, and branches to a 1½-inch pipe to the lower hall, and 1¼ inches to parlor.

Circuit No. 5 breaks at the boiler into two 1¼ pipes, one going to front chamber where it heats the fourteen loops, and the other to the back chamber (second floor), where it heats the eight loops.

The flow and return pipes of a circuit are exactly alike in size and almost identical in the manner of being run. The

FIGURE 41A.

pipes are near the ceiling, with a pitch of about one inch in ten feet.

Each radiator has an angle valve on the inlet end and an air-cock in the top chamber. Although air collects in this

PLANS

SHOWING HOT WATER PIPES

·IN THE RESIDENCE OF·

— W·H·CARRICK·Esq

·TORONTO·CAN:

FIGURE 41B.

chamber a neglect of a week is not sufficient to affect the flow of the water. The dotted lines in the plan indicate pipes

under floor or in partitions, while the dotted lines in the dia-
gram indicate the return flow pipe.   The pipes through the
cellar are covered with a plastic non-conductor.   On the ex-
pansion tank is a glass to show the height of the water, and a
connection with the city water-pipe is made to be used when
required, but the waste is so small a ball-cock was not con-
sidered necessary.

In all these cases the pipes are smaller than I would advise,
still, fairly good results are obtained, and when the advantages
of using pipes of larger diameter, and of reaming their ends
and connecting them with long-radius elbows and other fittings
are once fully appreciated, the results in hot-water circulation
will leave very little more to be desired, as by a careful study
of the laws that underlie the subject an engineer can predict
beforehand with almost positive assurance under what loss of
temperature the water of an apparatus will circulate.

BRANCH CIRCUITS.

All that can be said of a simple circuit applies also to the
branch circuits from a large main.   The one leads directly
from the head of the boiler, the other from the large main ;
and when the latter is of ample size and a proper circulation is
maintained therein, branches from it will give results equally
as good as with those taken directly from the boiler.   In fact,
in long, low buildings better results can be obtained, and at a
less first cost, by carrying a large trunk main through the
centre of the building and branching it properly, than can be
obtained by a number of long simple circuits that are of neces-
sity of a comparatively small diameter, and so give a very much

greater resistance for the amount of water passed than that of a single large main. I may repeat again that single parallel circuits carried from the head of a boiler to the remote divisions of a building will only be used by those who are not skilled in proportioning and branching large mains into proper subdivisions. It is the practical means used, however, for preventing complete failure and securing reasonably equable temperatures, as the hot water from the boilers is so divided at the start that each circuit takes its share, the amount passing in any direction being regulated by the diameter of the pipe, its length and bends, and the height of the end of the circuit above the boiler.

I do not wish to be understood, however, as saying that the simple circuit system is always a panacea for defects of circulation. Unfortunately many simple circuits fail to circulate properly, but in such cases the defect is circumscribed and can be located at once and the alterations necessary for its remedy will not affect adjacent circuits. A common cause of failures in circuits is the insufficient diameter of the pipes. Short circuits generally work well while long ones give trouble. If a long circuit is correctly proportioned and the pipes are fairly well covered from the air the result at the radiator will be as good as with the short circuit or so nearly so that the difference will not be readily discernible. Of course this is on the assumption that the alignment of all pipes is perfect, and that air-pockets or mechanical obstructions do not exist.

If we have constructed an apparatus that circulates satisfactorily in some of its circuits while one or two others fail to do so, then we should see that the defective ones are propor-

tioned by the following figures, taking the conditions of length and turns of a satisfactory circuit as a standard.

For instance, assume that we have a coil or radiator of say 60 square feet on a 1¼-inch pipe and the length of the circuit is 40 feet, 20 feet flow and 20 feet return, and it gives you satisfactory results. Then to get the same results at 80 feet or 120 feet, or any other multiples of the first length, you must increase the diameters in the ratio of 1.15 for the second length, 1.25 for the third, and so on.

When the radiator or coil on a new line is greater or smaller than the line that is taken as a standard, the diameters used for the standard circuit must in the new circuit be increased or diminished in the ratio of 1.32 for a coil of double the size and reduced to .75 for one-half the size ; and the following columns of figures, Table IX., are arranged to show the ratio of increase of diameters for increased amounts of surface and increased lengths of circuits.

To use it we have simply to multiply our original diameters, that we have found and know to be satisfactory, by the corresponding number in the column next to that which contains the number of times the heating surface or length of circuit has been increased and we have the proper diameter to satisfy the new conditions. For instance, to find the proper diameter for a circuit that has three times as much surface as the standard of comparison, you must multiply that of the standard by the number under ratios of diameters that is next to the right of 3 under ratios of surface and you have the new diameter.

If the circuit is to be increased in length, and at the same time has to supply three times as much heating surface as the

standard circuit, then supposing the new circuit is *four* times as long as the standard, its diameter must be further increased by multiplying it by the number under ratios of diameters next to the right of 4 in the column of ratio of lengths.

In the following examples the standard circuit is supposed to be of 1¼-inch pipe.

Example 1.—With three times the surface we have 1¼″ × 1.55 = 1.937″ as the diameter for the new circuit.

TABLE IX.

Ratios for the increase of surface.		Ratios for the increase of lengths.	
Ratio of surface.	Ratio of diameter.	Ratio of lengths.	Ratio of diameter.
.5	.75	..	....
Unity.	1.00	Unity.	1.00
2.	1.32	2.	1.15
3.	1.55	3.	1.25
4.	1.75	4.	1.32
5.	1.90	5.	1.38
6.	2.05	6.	1.44
7.	2.18	7.	1.48
8.	2.30	8.	1.52
9.	2.41	9.	1.55
10.	2.52	10.	1.59

Example 2.—With four times the length, but with no change of surface, we have 1¼″ × 1.32 = 1.65″ as the diameter for the new circuit.

Example 3.—With three times the surface and four times the length and we have 1¼″ × 1.55 × 1.32 = 2.556″ as the diameter of the new circuit.

Should this table be required for numbers beyond 10, say for 50 times the surface or 50 times the length, it is only neces-

sary to separate the given number into two or more factors and to multiply in succession by the corresponding ratios of diameters. Thus, for 50 times the surface, since $50 = 10 \times 5$, $1\frac{1}{4}'' \times 2.52 \times 1.90 = 5.985''$, or say the ratio of the diameter for 20 times the surface is required as $20 = 4 \times 5$ or 10×2, then either 1.75 and 1.90 may be multiplied together for the new ratio, or 2.52×1.32, which in either case gives 3.325 as the ratio for 20 times the surface. If it was for 200 times the surface multiply again by the ratio for 10 (2.52), which gives 8.38 as the ratio for the new diameter. The same rule applies to finding ratios of diameters for increased lengths.

CHAPTER XVIII.

Compound Mains of an Apparatus System in the State, War and Navy Department Building—Eccentric Fittings— Fitting of a Small Residence—Fitting of the Westchester County House.

COMPOUND MAINS.

COMPOUND mains are made up of a number of simple circuits taking flow from a trunk main and returning into a similar main return-pipe, the trunk mains only joining with the boiler.

. The State, War and Navy Department building at Washington, D. C., is a fine example of this class of work, a full description of which appeared in *The Engineering and Building Record*, January 22, 1887, and part of which is here reproduced * (Figures 41, 42, 43, 44, 45 and 46).

The building is 500 feet long from north to south, and 275 feet from east to west, and is shown entire in the block plan— Figure 41. The centre and west wing (War Department), shown by shade lines on the block plan, comprise the new part of the building. The darker shading comprises that part of the building shown in enlarged detail in Figure 42, which has within it a set of boilers and a warming apparatus. Within the entire building there are six such apparatus, one in the north and one in the south wing, and two in each of the east and west wings, the centre being supplied from the west wing.

The cellar of the building is principally given up to the warming and ventilating apparatus. The remaining floors of the building, which consist of basement, first, second, third and fourth floors, are for offices. The warming of the basement and first floor is by direct indirect-radiation. The remaining floors, second to fourth, inclusive, are warmed by indirect radiation.

---

* It was through the courtesy of General Thomas Lincoln Casey, Corps of Engineers, U. S. A., under whose direction the work was done, that access to the drawings and data was obtained.

The plan of the greater part of one of the six plants of this building is shown in Figure 42.

Figure 43 is a vertical longitudinal section of the same, showing one of the boilers, and the trunk mains both flow and

BLOCK   PLAN
FIGURE 41.

SECTION A-B SUB-BASEMENT
FIGURE 44.

return, and Figure 44 is a cross-section (looking south) showing the two boilers of a plant, and the main connections with the trunk mains, both flow and return.

The boilers used in this section are full of tubes. They are 54 inches in diameter, and contain 121 3-inch tubes, and

60-inch boilers used in the other plants of the building have 148 3-inch tubes each. Fourteen-inch cast-iron necks join the boilers with a 20-inch cross drum, both above and below, as shown in Figure 44. These drums are carried full size into the main passageway under the halls of the building. Twenty-inch gate-valves are here used as seen in Figure 42 basement plan. They are the main stop-valves of a single plant. The pipes then branch into a 16-inch and a 14-inch main, as shown, the former running north and the latter south and central. The flow-pipes only are shown in this figure, but the return-pipes are identical with them in size and may be seen in Figure

FIGURE 45.

43 in elevation. The flow-pipes rise very slightly as they go from the boilers. Where they reduce in diameter from a large to a smaller size—as, for instance, from 16 to 14 inches— eccentric fittings are used, so as to have the top of the pipe on the same common alignment, and slightly rising to the ends. This is to prevent air-traps or lodgments of air at any point of the pipes. This can be noticed in Figure 43. The branches from the mains are also taken out on a level with the top of the main through special eccentric branch-*tees*, the object being the same. This can be seen in Figure 44 ; and Figure 45 shows one of this class of fittings in detail. They prevent

the formation of air-pockets where a line reduces in size, which pockets must necessarily follow with common fittings, and in the case of branches that leave the side of a main instead of the top, they distribute the air evenly, more evenly among the branches, and they further admit of keeping the main pipes near the ceilings, so the top sides of all the pipes will be on the same common alignment, an advantage in low basements.

Figure 46 is a diagram showing the sizes of the rising lines. For a large window radiator on the basement and first floors the branch leaves the main three inches in diameter and reduces to two 2-inch branches, one 2-inch branch for the basement and one of the same diameter for the floor above. This is about theoretically correct, when the augmentation of head due to the additional height between the basement floor and the first floor is considered. A 2½ branch from the main at the cellar ceiling runs 2½ inches to the first floor, with a 2-inch branch to the window radiator on that floor; then to supply a large radiator on the fourth story it is only 1¼ inches the remainder of the distance. The connections that supply the indirect coils on the cellar ceiling are mostly two inches, and the average surface of the indirect coils about 200 square feet each. It is well to call attention to the fact that the connections to these coils are short and have few elbows, and that, therefore, with water entering at 200 it will probably leave the coils at a temperature not much below 160 Fah.

It may be said of this work, that the system followed is almost identical with that followed in steam-heating, with the exception of the increased diameters of the pipes, and the

absence of anything like relief-pipes.   Nearly all the Govern-
ment buildings that are warmed with hot-water have modifi-
cations of this simple principle, which consists of nothing
but mains and their branches, which latter are again divided
into smaller ramifications to suit circumstances.

FIGURE 46.

It is well to impress on the fitter, however, that unless the
pipes of an apparatus of this class are properly proportioned,
and ample at every stage of their progress, he will have "dead"
ends or circuits ; or, more properly speaking, sections of the
apparatus will work sluggishly, and the uniform heat of the
radiators cannot be kept up.

The cause of this is, all the water that passes out through a contracted or insufficient main will find easy circulation through the central part of the apparatus, leaving the more distant circuits poorly or almost entirely unsupplied, and the whole apparatus may be compared to a sluggish circulation of the blood on a cold day—the extremities are cold because of the lack of force and volume at the centre.   In man, however, the circulation is mechanical, and may be accelerated by exercise, but in an apparatus that depends entirely on difference of density no amount of firing will help the ends to any considerable extent, as long before the necessary force could be obtained steam would be formed and the apparatus proved a failure in any event.

Large buildings, such as the State, War and Navy Department, cannot be warmed by any other system than compound mains.   It would be wholly impracticable to warm it by single circuits, as there would be hundreds of them running to the boiler room, filling the passages, etc.   The apparatus in the house of Notre Dame, Toronto, Canada (shown in Chap. 31), with all its circuits would not be a circumstance to the bewildering mass of pipes that would be required for this building in a single one of its sections—there being six such sections and plants in all.

As an illustration of an extremely small apparatus of the compound-main class, though sufficient to warm a residence comfortably, the reader is referred to Figures 47 and 48.

Going from large to small work—although the principle is the same—I will describe a small hot-water apparatus, fitted in the most simple manner, in one of the numerous small

brick houses, intended for one family, now being built in New York and vicinity. These houses are now a feature of immense

FIGURE 47.

districts of Brooklyn, N. Y. They rent for from $300 to $450 a year, according to circumstances and location, and

are the homes of many thousands of small business men, pro-
fessional men and clerks who do business in New York and
vicinity, and who thus have accommodations in pretty brick or

FIGURE 48.

brown-stone front houses, all to themselves, who would be
forced to live in apartment-houses in New York at greatly ad-
vanced rents.

The drawback to these houses, however, is their method of heating. They are, almost without exception, warmed (?) with a fire-place heater in the dining-room, with a flue to the parlor and front bedroom. During the cold weather people are either forced to freeze or be suffocated with the nondescript half-furnace, half-stove that warms the dining-room and sends gas, ashes and dust to the upper floors, as not one in twenty of these fire-place heaters are in order during the second winter, and whether they are in order or not the houses cannot be warmed by them in ordinary cold weather. Such, however, is the writer's experience with two different ones, and it seems to be the experience of all his neighbors. No air is admitted from out of doors, so the advantage of fresh air cannot be claimed for them, as they depend on the return of the air down the stairways for a supply to keep up the circulation.

Almost invariably, however, the leakage of gas is from the heater into the air-flues of the house. A 3-inch smoke-pipe is run up within the principal air-flue, and when the air-flue draws better than the chimney and smoke-pipe the inhabitants keep warm on a mixture of warm air and coal-gas, especially when the damper in the pipe is shut, which is the invariable rule at night, to save coal, by those who follow the instructions of the makers. Fortunately, this 3-inch damper has a 1-inch hole in its centre "to carry off the gas," and, therefore, people do not die suddenly from coal-gas poisoning, but of the impairment of health from this cause there is no doubt in the judgment of any intelligent person who has investigated the subject.

To escape this state of affairs the apparatus shown here was put in and is now in use the third winter with a satisfaction that is beyond comparison with the old hot-air method. There is no patent on it and its cost is trifling, which will be given in detail hereafter. The radiators and boiler used are, presumably, patented by the maker, but any hot-water boiler of the many good ones now before the public can be used, and flat coils of 1-inch pipe or any hot-water radiator can be placed in the rooms, any one may set them up at a small outlay ; the principle of piping being old and it is the property of any one who wishes to use it.

In this case a No. 22 Hitchings hot-water base-burning boiler was used and placed in the corner of the dining-room at B, Figure 47. It looks like a base-burning stove and takes up no more room. The object of the position was twofold. It warmed the dining-room and brought the boiler very near the basement door, so ashes, etc., could be quickly removed to the area under stoop, the usual receptacle for it in these houses. The only objection to this position is the length of the stove-pipe necessary to reach the chimney now built. In the summer, however, this is taken away, and in the winter (with all the heat that comes from a fire in a hot-water boiler), a Russia iron pipe five inches in diameter is not very objectionable. In fact, to the man who had to wear his overcoat at breakfast when he depended on his Baltimore heater it is most welcome.

From this little boiler, that has about twelve square feet of fire surface in it, there is carried a 1½-inch flow-pipe to within six inches of the ceiling. Just below the elbow there is taken the flow or supply pipe for the parlor radiator, plainly shown

in the diagram, Figure 48, which diagram is an exact reproduc-
tion of the pipe in the house, and, to a practical man, shows all
there is to be seen.   For the unpractical, however, I will
explain further.   After supplying radiator No. 1, the 1½-inch
main passes into the hall, or just through the partition.   From
there it is carried straight to the rear wall of the house, through
the basement hall and kitchen, reducing to 1¼ inches in size
after the *third* heater is taken off, and thence carried 1¼ inches
to the end or fourth heater.   This main rises all the way to the
last heater, there being about three inches rise in its whole
length.   The return-pipe is an exact reproduction of the flow-
pipe, and is set side by side with it, the only difference being
in where it enters the boiler—at the bottom.   The radiators
are all of the same size with an angle-valve to the inlet end of
each.   They are nominally 35 square feet of surface each, be-
ing single-row Bundy hot-water loops, regular height, 10 long,
taken at 3½ square feet of the loop, making, in all four, 140
square feet of surface, which has proved itself ample to warm
the house when taken in connection with the mains and boiler,
which are not covered.

The upper or bedroom floor requires no heaters.   Sufficient
heat escapes from the parlor floor to keep it warm enough for
bedrooms in the coldest weather, with water at 170° Fah., the
windows on the upper floors can be kept open an inch or two,
and, ordinarily, a temperature of 150° Fah. in the pipes keeps
the house warm and comfortable, and allows for opening the
windows, as above, for a change of air.   The apparatus runs
day and night, and a variation of ten degrees is never
experienced.

The average consumption of hard coal is less than 50 pounds per day ; a ton a month more than doing for all purposes. With the old heater a ton would last not quite twenty days for all purposes.

The houses are in blocks, thirty such houses being in the row this one is in. The end houses would require a more ample apparatus, as they have more windows and a greater outside wall area ; for the centre ones, however, the apparatus described here is ample.

The sizes of windows are marked on the plans, Figure 47 and also the sizes of the rooms.

A difference of about sixteen degrees exists between the temperature of the flow and return pipe at the points where the one flows out of the boiler and the other enters it.

The cost of such an apparatus is as follows :

> The boiler, or one of equal power, can be purchased and delivered for about....................................$50
> 140 square feet of good hot-water radiator will cost about 40 cents per square foot............................ 56
> The cost of mains is about $16......................... 16
> Four days' labor, man and helper, $7.50................ 30
> Smoke-pipe and zinc.................................. 5
> One thermometer on flow-pipe at boiler 3
> Galvanized sheet-iron expansion tank and sundries....... 5
> ___
> $165

This is the actual cost, and does not allow a profit to the contractor. If, however, the consumer takes the builder's risk and contracts for labor, he can keep his cost down to $175 unless things are very badly managed.

Another modification of branched mains is shown in Figures 49, 50 and 51. They are diagrams of the pipes in the West-chester County (N. Y.) alms-house, and show a wonderful ramification of pipes, a separate compound system being run for each floor or common level of the building.

Figure 51 is an isometrical drawing of all the flow-pipes as they are used and their sizes, and a reference to the basement plan (Figure 49) shows plainly their relation to the building. The return-pipes (not shown) are almost identical with the flow-pipes so far as position is concerned, and in size they are equal.

Figures 49 and 50 are plans of rooms of the buildings that have been warmed by this system. They comprise all the rooms of the first, second and attic stories of the main building, and the first and second stories of the hospital building, the asylum wing being as yet heated by the furnaces. The building is a very old one, though of solid masonry, and is in good repair.

Figure 49 shows the basement plan and the position of the pipes and boilers, as well as the male and female dining-rooms, keepers', and other rooms that are warmed in the basement.

It will be noticed that a separate flow and return pipe is used for each floor or common level of the building with the exception of the third, which is warmed by branches of the second-floor system. The basement contains about 450 square feet of surface, not considering the surface of the mains, and for this amount of surface, under the limited height of the basement, eight feet, the main or flow-pipe C starts $2\frac{1}{2}$ inches in diameter from the cross-drum at boilers and is carried up to the level of the second floor (a), within a closet, where an air-chamber

FIGURE 49.

PLANS SHOWING THE METHOD OF HEATING THE WESTCHESTER COUNTY ALMS — HOUSE. BY HOT WATER.

FIGURE 50.

and air-vent is attached, thence down again to the level of the basement ceiling, close under which it runs. At the hall, under the centre of the main building, it reduces to 2 inches, and at the end it is 1¼ inches to the two last coils. Its branches are 1¼ and 1½ inches to the coils—1¼ inches to coils of 50 square feet, and 1½ to larger coils. The return-pipes are similar, but in this case are on or near the floor, so as to get the water back to the boilers, as the heaters are nearly as low as the bottoms of the boilers.

The loop *a*, Figure 51, with air-chamber, was introduced for the purpose of quickening the circulation to the lower floor. It may quicken it in a slight degree. The extra bends and length, however, add resistance, and the difference of temperature between the up and the down leg of the syphon is infinitesimal when the water passes with any reasonable velocity. The up-leg of the loop and the pipe from the boiler is carefully covered, the object being to secure as great a difference of temperature between the legs as possible ; or, in other words, to secure a greater loss of heat in the down-leg, and consequently maintain a greater constant difference of the density of the water in the legs. The motive power, then, for the basement—considering gravitation as the cause of motion —is in the down-leg of this syphon, and the pipes which drop to the coils and heaters and the heaters themselves.

The amount of heating surface on the first or principal floor, main building, is about 1,383 square feet, part Bundy hot-water radiators and part box-coils. A close study of the plan will show the different locations, the coils being marked "Box-Coils," and the radiators "Rad." There is no advantage in

the use of radiators or coils in one position over another, ex-
cepting appearance, the radiators being in the best-finished
rooms, parlors, etc.

About 843 square feet of this surface is in the centre build-
ing, first floor, and 540 square feet in the nursery and hospital.
The pipe to the main part of the building (A) starts three
inches in diameter and runs, as shown, under the basement
ceiling. About the middle of the building, under the hallway,
it reduces to two inches, thence runs to the end of that diame-
ter. To any one particularly interested in the matter, all its
branches can be traced in Figure 51, with their sizes, etc. The
pipe to the nursery and hospital part is 2½ inches (A, right,
Figure 51), and is run as shown and marked, and requires no
more explanation from us, as it may be traced on the drawing
easily.

The pipe B B in the drawing is for the second and third
floors. It is three inches to the main building and 2½ inches
to the centre building, and can also be traced, with the quan-
tity of surface, at each branch.

In a few cases a pipe branches to two radiators, or coils,
but usually a separate riser goes to each heater. The third
floor, however, is always a continuation of the second story
riser, though of a smaller size.

The loss of heat between the flow and the return-pipes of
the basement circuit of this building is certainly not less than
between 40 and 50 degrees, being least, of course, when the
initial temperature of the water is high, there being 450 square
feet of surface of coils on a 2½-inch circuit, the radiating surface
of which is nearly all on the level of the boiler or partly below it.

The 1,383 square feet of surface for the principal or first floor is divided into 843 square feet for the circuit on the left of the boilers, and 540 square feet for the right circuit, the former being a 3-inch compound circuit, and the latter a 2½-inch compound circuit. The result is a loss of temperature of 40 degrees or more between the flow and the return pipes on the left, with slightly better results on the right.

Nearly 2,000 square feet more surface is divided between a 3-inch left circuit and a 2½-inch right circuit for second and third floors. Though there is considerable more surface on these circuits than on the ones for the first floor, of equal diameter, still on account of the increased height of the circuits the results at the radiators are not much inferior to the floor below.

To compensate for this great difference in temperature between the flow and the return-pipes large radiators and coils are used, and there is no lack of warmth in the building, but from the standpoint of a designer it is better to use ample mains and less radiating surface, and secure a less difference between the temperatures of the flow and the return-pipes. It is also cheaper to have larger mains and less heating surface.

CHAPTER XIX.

*Boilers Used for Hot-Water Heating—Brick-Set Boilers—The
Horizontal Tubular Boiler—Placing Tubes in Horizontal
Boilers—Diagrams of Head Sheets for Horizontal
Boilers—Illustrations of Brick-Setting for Hor-
izontal Boilers—Leakage of Air Through
Brick-work of Boilers—How to Prevent
It—Table of Dimensions, Thick-
nesses, Heating Surface, etc.,
of Horizontal Boilers
and Its Use.*

BRICK-SET HORIZONTAL BOILERS.

N EARLY every boiler that will answer for making steam
will also do for warming water.

There are some forms, however, that are not desirable for
making hot-water for warming purposes for the simple reason
that their internal resistance to the passage of the water through
them adds too much to the total resistance of an apparatus.

One of the chief points in the design or selection of a boiler
for water heating is to secure one that will give the minimum
of resistance.

Another point in the choice of a boiler is to secure prop-
erly disposed surfaces. Surfaces that will absorb the greatest
amount of heat possible from the fire, and surfaces that are
easily kept clean or that will remain comparatively clean in

consideration of their angle, the effect of the draught on them, or other predisposing causes.

Anything that quickens the circulation through or within a boiler or over its fire surfaces will increase its capacity per unit of surface. The faster the water rushes over a surface the more units of heat,there are taken away in a given time. Therefore, fairly well disposed surfaces, combined with free and easy water passages from bottom to top through a boiler, when taken together, conduce to give better results than can be obtained by sacrificing one point of excellence to the good of the others.

There are also other points of importance, such as the life of a boiler, the area of the flue passages, the grates, room the boiler requires, its cost—all of which enter into a good boiler.

The horizontal multitubular boiler, that has done so well for steam, also does well for hot-water heating. When made for hot-water work, however, it is usual and profitable to have it entirely filled with tubes, or nearly so, having suitable distances between the tubes for the free and easy passage of the water.

This distance, however, need not be as great as for steam boilers, as there is not the necessity for as great a local circulation in a hot-water boiler as there is in a steam boiler, and in fact it may be said there is no necessity for it, if the water can be made to push forward through the pipes as fast as it is warmed. This rarely happens, however, and therefore, to prevent the formation of steam bubbles on the very hot surfaces a local circulation is necessary to maintain a somewhat equable temperature of the water in the boiler or in divisions of the

of each space between any pair of tubes, and as there will be

temperature of the water in the boiler or in divisions of the

boiler, as it will be found that as a general thing the upper parts will be the warmest, and when the hot water cannot flow away it should return and diffuse with the remainder and cooler parts.

The distance between the tubes of a horizontal boiler, therefore, for hot-water work may be regulated as much by the practical side of the question as by any other—in other words, the distance between tubes is to be sufficient to secure a good boiler

FIGURE 52.

head, or one that will have sufficient metal between the tubes to prevent the cracking of the bridges, and probably ¾ of an inch should be the minimum in this respect.   In a boiler 12 feet long this will give ¾ of a square foot as the horizontal area of each space between any pair of tubes, and as there will be

from 12 to 15 such spaces in an ordinary boiler there will be
from 9 to 10½ square feet of vertical passages at the centre of
the boiler.   As the boiler is a cylinder, however, the water-
ways are lessened in number at the top and bottom, as will be
seen in Figures 52 and 53, but as the outer tubes are always
about 3 inches from the shell, this will not materially add to
the resistance.

FIGURE 53.

There is one point of special note, however, that is often
overlooked, which is, that, in the anxiety to get all the tubes
possible into a boiler, the upper horizontal row is often brought
too close to the shell, and consequently to the discharge nozzle,
causing obstruction to the passage of the water into the flow
pipe, as shown at *A*, Figure 53.

FIGURE 54.

At the bottom the corresponding row of tubes is omitted to make room for the hand-holes, and thus the obstruction that would directly interfere with the free passage of the water into the boiler, is, through accident of circumstances, removed. To prevent an obstruction to the flow, therefore the tubes *A* (Figure 53) should be omitted and a space maintained as in Figure 52 at *A*.

It would be an advantage also to use a bell-mouthed nozzle at the flow, as the water, meeting at this point from all directions, makes considerable resistance before the change of direction is accomplished, unless the nozzles are very large, as shown in the cuts.

Boilers of this class are used for very large plants, and it would be well for those who require them to have their boiler shells made in two pieces, with their longitudinal seams at B B, (Figure 52) and no girth seams except the seams of the ends.

This makes a boiler that has but one seam in the fire-box, and that is the seam of the back head sheet, and when made of mild boiler steel there is no trouble to obtain sheets sufficiently large for a boiler 16 feet long.

A boiler of this class, made this way, for low-pressure hot-water heating will probably never require repairs, except to receive new tubes, until it is entirely worn out by natural use and deterioration.

The setting of these boilers for hot water is always substantially the same, and may be said to differ from the setting of a steam boiler only in the formation and position of the "back-connection arch," which of course must be always higher than for steam, so as to come above the extra tubes that fill the upper third of the boiler.

This arch is often made of cast iron, for the reason that when it is of fire-brick it must be at least two courses of brick on edge thick, or nearly 9 inches. This will bring the top of the arch up into the flue space, when the flue is returned over the top of the boiler, and it is on this account iron is used. The iron arch, however, will not last long with a temperature often of between 800° and 1,000° Fah. below it, and therefore nothing but an arch of fire-brick should be used, as shown in Figure 54.

Figure 54 shows the setting when the flue is returned over the boiler, and Figure 55 shows it when the boiler projects through the front, and the smoke is taken to the chimney in a direct flue.

It is claimed for the return flue that it is the most economical. This may appear to be the case to a small extent in some cases, as nearly one-half the shell—the upper part—is apparently good heating surface.

As a matter of fact, however, this surface is of little or no value (1) because the gases of combustion have passed through the tubes before they reach it ; (2) on account of the accumulation of soot and ashes which lodge there ; and (3) for the reason that the infiltration of air through the upper side of this brick flue, whose surface is so large, materially affects not only the temperature of the gases of combustion and their power to impart heat to the shell, but lessens the power of the chimney, both by the extra volume of air that is admitted to it, that never passes the fire, and by cooling it and increasing the density of the upward column of air. The writer has examined a boiler set this way where the escaping gases were not over 112 degrees the leakage was so great.

Figure 55.

For the reasons given, therefore, especially the two first, I prefer to let the gases escape from the front end of the boiler as a general thing, and Figure 55 shows the setting I usually use. It is also better than a flush front setting, as the rivets of the front head sheet are carried so far forward that the seam cannot be affected by the heat should the brick-work at B about the door fall out, as it frequently does, and often remains so for days and weeks without being renewed or repaired.

The infiltration of air through the brick setting of boilers is always a serious quantity and often impairs their general efficiency more than is usually suspected. For this reason the best hard brick and mortar should be used. Although lime mortar is the fittest, so far as heat is concerned, mortar with considerable cement in it makes a tighter wall. All the joints should be filled with mortar the same as for hydraulic work, and when a full lining of fire-brick is used no deterioration of the cement mortar in the remaining parts of the brick-work is noticeable. Hot asphaltum applied to the outside of the walls or asphaltum paint is a great assistance to prevent the passage of air through a wall. Whitewash with soap and alum also makes a wall comparatively impervious to the passage of air.

I have compiled the following table for the benefit of the fitter. The first five columns are from a pamphlet of Messrs. Bartlett, Hayward & Co., who have used horizontal multi-tubular boilers in all their large work, and the remainder has been calculated from the usual data. The first column gives the diameters of boilers ordinarily used. The second column shows about the number of tubes of the diameters given in the third column that can properly be used in shells of the diameters

TABLE X.

Diameter of Boiler Shells.	Number of Tubes in Boiler.	Diameter of boiler Tubes.	Thickness of Boiler Shells.	Thickness of Boiler Heads.	Square Feet of Heating Surface to one Foot Length of Boiler; Tubes and Shell included.	Square Feet of Heating Surface in Tubes only for one Foot of Length.	Square Feet of Surface to one Foot Length of Shell.	Lineal Feet of Tubes to one Square Foot of Surface.
24-in.	34	2- in.	¼-in.	⅜-in.	22.39	16.11	6.28	2.11
"	28	2¼-in.	"	"	21.38	15.10	"	1.854
"	24	2½-in.	"	"	20.62	14.34	"	1.674
30-in.	58	2- in.	¼-in.	⅜-in.	35.34	27.49	7.85	2.11
"	46	2¼-in.	"	"	32.66	24.81	"	1.854
"	44	2½-in.	"	"	34.35	26.3	"	1.674
36-in.	66	1½-in.	¼-in.	⅜-in.	48.84	39.42	9.42	1.674
"	50	3- in.	"	"	45.83	36.41	"	1.372
42-in.	86	2½-in.	¼-in.	⅜-in.	62.37	51.37	11.00	1.674
"	68	3- in.	"	"	60.52	49.52	"	1.372
"	54	3½-in.	"	"	57.07	46.07	"	1.172
48-in.	94	3- in.	⁵⁄₁₆-in.	⁷⁄₁₆-in.	81.02	68.46	12.56	1.372
"	72	3½-in.	"	"	73.99	61.43	"	1.172
"	58	4- in.	"	"	69.20	56.64	"	1.024
54-in.	118	3- in.	⁵⁄₁₆-in.	⁷⁄₁₆-in.	100.12	85.99	14.13	1.372
"	86	3½-in.	"	"	87.51	73.38	"	1.172
"	72	4- in.	"	"	84.44	70.31	"	1.024
60-in.	148	3- in.	⅜-in.	⁷⁄₁₆-in.	123.49	107.79	15.70	1.372
"	106	3½-in.	"	"	106.19	90.49	"	1.172
"	86	4- in.	"	"	99.68	83.98	"	1.024
66-in.	172	3- in.	⅜-in.	⁹⁄₁₆-in.	142.55	125.27	17.28	1.372
"	136	3½-in.	"	"	133.32	116.04	"	1.172
"	106	4- in	"	"	120.79	103.51	"	1.024
72-in.	216	3- in.	⅜-in.	⅝-in.	176.17	157.32	18.85	1.372
"	172	3½-in.	"	"	165.60	146.75	"	1.172
"	136	4- in.	"	"	154.59	135.74	"	1.024
1	2	3	4	5	6	7	8	9

given in the first column.   The fourth column gives usual thickness of plate for the shells, and the fifth column the thicknesses for the head sheets.   The sixth column, which is calculated from the data given by the National Tube Works Co. for their standard boiler tubes and other data, gives the number of square feet of heating surface in one foot of length of a boiler, shell and tubes considered, but with head sheets omitted.   The seventh column gives the surface for tubes for one foot length of boiler.   The eighth column the surface for one foot length of shell, and the ninth column the length of tube to one foot of internal surface.

The use of the table is obvious to any one wishing to select a boiler of a given capacity.   The sixth column multiplied by the length of a boiler in feet will give a very close approximation to the square feet of surface required in the boiler.   The seventh column gives the tube surface alone in the same manner.   If the shell or half the shell surface is to be omitted, it is found by the eighth column.   If some of the tubes are to be omitted the ninth column furnishes the data.

ı The thicknesses of boiler shells and heads, given in the fourth and fifth columns, may be varied slightly by the designer, but as a general thing the dimensions for thickness should not be made less ; not that they require this thickness for strength, however, but that they may the longer withstand the action of corrosion and wear.

CHAPTER XX.

Various Modern Boilers, etc., Used in Hot-Water Heating.

IN further considering this question of boilers it would be well to classify them under the head of "brick-set" and "portable" boilers, or ones that require no brick-work, except it be a foundation or ash-pit of brick-work.

Coil boilers were early used for hot-water purposes. They are of two distinct classes : The box coil class, Figures 56 and 59, and the spiral coil class, Figure 57.

The spiral coil is the most primitive form of a closed hot-water boiler for heating, and Figure 58 shows the earliest form the writer is acquainted with. Mr. Perkins, of London, Eng., used this form of heater for his high-pressure work, though it was undoubtedly used by others before his time.

It is the safest form for high-pressure apparatus, as the pipe may be of any thickness. It may be used on a simple or branched circuit, but Mr. Perkins usually used it on a simple circuit, the flow-pipe being carried about the room or building to be warmed, forming a continuous pipe and returning to the coil at the bottom. He used an expansion chamber of strong pipe of sufficient capacity to hold the increased bulk of water when the latter was warmed and expanded to its utmost. Tne air was retained in this chamber, so the expanding water

compressed it ; the result being to put the apparatus under very high pressure.

The best-known form of this apparatus at the present day is the " Baker " car-heater ; the only essential difference being a safety-valve on the expansion chamber.   Mr.Joseph Nason, of New York, was the first to make and use this coil heater in the United States to any appreciable extent, and to him also belongs the credit of introducing the box coil heater.

FIGURE 56.

The objection to a spiral heater is the resistance it causes to the flow of the water and its lack of economy of fuel.   If the coil is made sufficiently long and high to have surface enough to absorb a reasonable amount of the heat of the fire its resistance is very great, and it often happens the resistance is so great as to retard the passage of the water until steam is formed, when the water is forced out of the coil at both ends,

performing the operation technically known as "kicking-backwards."

The box coil heater as made by Mr. Nason was a simple box coil of bent pipes joined to headers top and bottom, as in Figure 56. Later the return bend was substituted for bent pipes,

FIGURE 57.

still for very high pressures it is preferable to use bent pipes, thereby doing away with many joints within the furnace. His method of setting was a simple brick furnace over which the coil was placed and enclosed in brick-work, with doors for cleaning, etc.

The "Pascal Iron-Works" of Philadelphia, now the Morris Tasker Co., Limited, early made an improved boiler on this principle in which the sides of the fire-box were formed

FIGURE 58.

by pipes of the coil, the lower tier of pipes also forming every second bar of the grate, an ordinary bar being used between them. This boiler is fully shown in Figure 59. The connec-

tions at the ends of the pipes are box bends, a bridge wall
being formed by two sets of them. In the illustration the boiler
appears at first glance to look like a steam-boiler, the drum
with " try-cocks " and safety-valve adding to the impression.

FIGURE 59.

This drum, however, is the expansion tank, and the system
is an improvement of the Perkins, but designed for lower
pressures and temperatures.   Mr. Perkins made an absolutely

tight apparatus, and the pressures were enormous and danger-
ous, and would be prevented by the fire commissioners and
underwriters now.   His apparatus consisted of a coil of very
thick pipe of small diameter with an expansion chamber of
very strong pipe as shown in Figure 58, in which B was the
heater, *f* the flow-pipe, T the tank, C the coils, and R the return-
pipe.   The tank was of large capacity—one-third or one-
fourth of the apparatus—and the apparatus was made abso-
lutely tight and filled to the hole *h* in the side of the tank near
the bottom, then this hole was plugged, and the water, as
it expanded, was allowed to compress the air in the head of
the chamber (T) giving pressures that it was almost impossible
to estimate.

The boiler, Figure 59, is not intended nor would it with-
stand any such pressures or temperatures as a welded spiral
coil, and therefore they can be made on an ampler scale, the
principle remaining the same ; the tank which is on its side
being supplied with cocks to gauge the height of the water
within it, and a safety-valve being applied to let off the
excessive pressure of the compressed air.

It will be noticed the flow pipe leaves the tank as low as it
enters it, so the air will be disengaged and imprisoned above
the water and not carried into the circulation.   This method
also allowed the flow pipes to be carried above the tank level,
though as a general thing it is not advisable to do so, for
should the air get out of the tank it fills with water and the
apparatus will have to be partly drawn off and filled again to
get it to operate properly.   These boilers were usually used
with the coils or radiators no higher than the flow pipe.

Mr. Garth makes a convenient form of this class of boiler. He forms the sides of the fire-box and grate with the sections of the boiler. Figures 60, 61, 62 and 63 show drawings of the boiler as used in the Westchester County (N. Y.), Alms-house, by the Denny Brothers Co. of New York, being respectively longitudinal section, front and side elevation and ground plan.

They are twin hot-water boilers, and each contains 700 extra

LONGITUDINAL SECTION

FIGURE 60.

feet of heavy 1½-inch pipe. They are separately connected, as shown, by a 6-inch header, with 4-inch connection from each boiler.*

---

* The total heating surface in this building was about 3,860 square feet. not including any of the running pipes. The boiler surface is about 700 square feet; therefore, there was one of boiler to 5½ of radiating surface, not considering mains, of which there were a great many. It is probable the mains would make the ratio of boiler to surface 1 to 7, and in reasonably cold weather one boiler was sufficient, so that 1 to 14 proved sufficient at times.

The drawings show thoroughly what the boiler is, and require very little description. They are, in brief, box coils, with the fire-box or furnace sides formed by flat coils. The heat of the fire, after leaving the furnace, is made to travel about the baffle plates D D to the top, thence down the rear to the flue F. Doors are provided for cleaning at the sides A B,

FRONT ELEVATION

FIGURE 61.

so as to reach all the tubes, and the door C is to remove ashes from the flue F. The dimensions of the walls, etc., on the ground plan are given. The elevations show the positions of the stop-valves and connections, and also the fire and draught doors. Each boiler in this case has a separate chimney.

This class of boilers offer considerable resistance to the flow of the water, however. Each section being a " flat coil "

with many short bends and pipe ends to encounter, a section will offer more resistance, therefore, than a spiral coil of the same length and diameter. As these sections, however, are connected with headers top and bottom, the water that flows into the bottom header has ten or more channels to pass through on its way to the upper header, and, therefore, for equal surface and like diameter it will, as a boiler, present less .

SIDE ELEVATION
FIGURE 62.

resistance than the spiral form. When, on the other hand, however, it has ten times the surface of the spiral boiler of the same diameter pipe, and has to pass ten or nearly ten times as much water then its resistance is greater than the spiral.

This class of boilers should always be made of large diam-eter pipes and as few bends as possible. To double the

diameter of the pipe means to reduce the velocity of the flow
of the water to one-fourth and the resistance to one-sixteenth.

Assume a boiler of this class with 10 sections of 1½-inch
pipe, whose total area of waterway is 22.5 square inches. Now
it will be very probable the resistance in these 10 sections,

PLAN OF BRICKWORK FOR FURNACE.

FIGURE 63.

with their bends, etc., will be greater than in one 4-inch pipe
of the same length, so that the boiler offers more resistance
than the flow-pipes, which of course is not the best practice.
An increase of the pipes to only two inches in diameter, how-
ever, will very materially lessen the resistance of the boiler

compared to the flow-pipes, and is a decided advantage.   It is assumed, of course, that with the increase of diameter the length of each section is proportionally reduced, so that the surface of the boiler remains the same for comparative purposes.

My object in introducing the cuts, Figures 61, 62 and 63, is to give an idea of the usual setting for large boilers of the box-coil class, and the method of connecting the flow and return pipes with the boilers, and to show a pair of interchangeable boilers that may be used separately or together.

FIGURE 64.

The "Blake" boiler shown in Figure 64, and made by Messrs. Blake & Williams, of New York, is another form of wrought iron coil boiler that is set in brick-work.   It has a very much lower resistance to the passage of the water than the box-coil type, as the pipes run from header to header with but a single elbow in each pipe.   In other respects it is much the same.   When used for hot water a separate flow pipe may

be taken from each header for single or simple circuits, and the return treated in like manner.

There are other modifications of coil boilers, but it is hardly necessary to refer to them here, as they have generally

FIGURE 65.

become obsolete. Where it is necessary, however, to make them for high pressure and high temperature the sections should be short or the diameter large, by which means the resistance is lessened without decreasing the surface.

Passing from wrought-iron coil boilers we come to a class of boilers that are made of cast iron but which are in substance cast iron pipe boilers.

The "Mills" boiler (made by the H. B. Smith Co., of Westfield, Mass., and New York), Figures 65 and 66, and the "Clogston" boiler, Figures 67 and 68, used by Ingalls and Kendricken, of Boston, are types of this boiler.

FIGURE 66.

They are used for hot-water or steam, and their resistance is less than in wrought-iron coil boilers on account of the longer diameters of the parts.   Their resistance is increased by the use of small diameter nipples between the sections and the headers, and were it not for this fact their resistance would be practically nothing.   When used for hot-water heating, therefore, the nipples should have as large diameters as possible.   These boilers require brick setting.

A very recent modification of this class of boiler that requires no brick-work is the "Mercer," Figures 69 and 70, and made by the H. B. Smith Co.

In many respects it resembles the "Gold" sectional boiler made by the same company ; its present modification being expressly designed to meet the requirements of the trade for a

FIGURE 67.

horizontal return-flue boiler in sectional form, which it substantially is when put together.

It consists of a number of cast-iron vertical sections, AA, set on a cast-iron base, G, which forms the ash-pit. The front section is arranged to receive the fire-door and double-flue doors to give access to the flues for cleaning. The rear sec-

tion forms the fire-back and connection to lower set of flues as designated by arrows in Figure 70.

The intermediate sections form the sides of the fire-box, and their number determines the capacity of the boiler.

All these sections have planed surfaces at points of contact and are connected to the return headers *HH* at each side of

FIGURE 68.

the bottom leg, and to the supply-header *K* at top with extra heavy lock-nut nipples as shown.

The flues consist of two sets, upper and lower, five in each, with an intervening water space between them, and also between the upper and lower rows.   Figure 71 shows the flue arrangement, it being a half section through first and second section.

The dimensions of these flues are seven by two and a half
inches, and their length is determined by the number of grate
sections of six inches each. The smoke connection, as will be
noticed, is at the rear and is arranged with a damper or slide

FIGURE 69.

V for temporary use during the making of the fire, and this
slide when open also gives access to the rear section and flue
connection for cleaning.

The grates are Reed's shaking pattern, and there are three-fourths of a square foot of grate surface per intermediate section.

There are twelve square feet of effective fire and flue surface per section of boiler, so that the boiler shown has 84 square feet of heating surface.

FIGURE 70.

The proportion of fire to flue surface is 1 to 2½, there being 3.4 square feet in the fire-box and 8.6 in the flues of each section.

The makers rate a 7-section boiler of 84 square feet, to 600 square feet of radiating surface, or as about 1 to 7, which is more ample than usually allowed.

A special feature of the boiler is the facility with which it can be enlarged or diminished, and the sections and ash-pit

FIGURE 71.

being in parts admit of its being placed in buildings already constructed and without sufficient opening for the admission of ordinary shell boilers. The accessibility of the parts of the boiler and flues to the brush for cleaning is apparent.

Asbestos, mineral wool or any other plastic material can be used as a covering; the rib or extension on the sections as shown at *A A* being perforated at intervals for rods or wire.

When used for hot-water, for which it is principally intended, any desired number of circuits may be taken from the supply and return headers by tapping them at intervals.

Its internal resistance is probably somewhat less than the two former boilers, but with the same diameter nipples the resistance of the flow may be said to be the same; therefore it

FIGURE 72.

is desirable to have large diameter nipples in all cases between sections and headers—say not less than 2 inches when used for water heating, and larger if possible.

A cast iron boiler that may be said to be a modification of the spiral coil boiler is the " Florida," Figure 72, made by the Pierce, Butler & Pierce Co., of Syracuse, N. Y. It was their first modification of a hot-water boiler and is substantially the coil as shown by the arrows. In a later modification, which

they now make, with direct vertical connections, less resistance is offered to the passage of water than the first, through which the water had to pass in a serpentine course in its passage from inlet to outlet, while in the latter the passages are straight, the water diffusing through the intervening parts of the rings by local circulation.

Figures 73, 74 and 75 show simple types of boilers that have been largely used for green-house heating. Figure 73 is the "Hitchings" conical boiler, Figure 74 the "Scollay" boiler, and Figure 75 the "Weathered" boiler. The resistance through these boilers is very small and a unit of surface has a very high efficiency. The heating surface being small, however, compared to the grate the gases of combustion as they escape into the chimney are high, therefore they are more suited for green-houses than for residences, excepting the "Scollay" boiler, where, as in the former case, the heated gases can be carried in a horizontal flue under the benches, having the chimney at the opposite end of the house from the boiler, thus utilizing the escaped heat.

I class the Scollay hot-water boiler with the "Hitching's Conical" boiler, and the "Weathered" boiler, where it properly belongs. I should, however, have considered the "Scollay" boiler separately, when referring to the temperature at which the gases of combustion escape into the chimney, as on account of the surface of the crown-plate and the arrangement of the flue passages through it and around it, the heat of the fire is largely intercepted and the gases of combustion pass into the chimney very little hotter that the water in the boiler; so that, instead of its not being quite as well adapted for house-heating as for green-house work, it is admirably adapted for both purposes.

Figure 73 is probably the first of this class of boilers ever made. The elder Mr. Hitchings made it as early as 1844, and the others are simply more recent modifications of it.

Figures 76 and 77 show the simplest types of boilers made. Figure 76 is made by Bartlett, Hayward & Co., and is a single casting without joints. They make but one size, being 19 inches in diameter with a 17-inch grate, and it is rated for 400 feet of 4-inch pipe. Its total inside surface does not exceed 10

FIGURE 73.   FIGURE 77.

square feet, therefore the boiler surface to heating surface must be about 1 to 40. The three simple types mentioned before are about in the same ratio. The gases of combustion escape hot.

Figure 77 is the "Hitchings" base-burning boiler made by Messrs. Hitchings & Co., New York. It is of cast iron,

having a water bottom below the fire and a magazine for coal.
They are in the proportion of about 1 of boiler surface to 20
of radiating surface, and the gases of combustion do not escape
as hot as with the preceding four boilers, so that it is not advis-
able to carry them through a horizontal flue when setting.
The internal resistance to the flow of water in this boiler and
in the one that precedes it is comparatively nothing.

FIGURE 74.   FIGURE 75.

Figure 78 shows the "Dunning" hot-water boiler made
by the New York Central Iron-Works, Geneva, N. Y.   It is
made of wrought iron or boiler steel, and is composed of an
outer and inner shell, with crown sheet, etc., as shown, but it
differs from ordinary upright tubular boilers in having a much
higher furnace and in not having the tubes run from crown
sheet to head, but in returning down the side, as shown, in an
annular ring of tubes, forming a reverberatory draft.   It is

shown here with a magazine, but where desired they are
omitted, in a manner very similar to the door-fired steam
boiler made by the same firm. The internal resistance of
these boilers to the flow of the water is very small.

The ordinary upright wrought-iron boiler with vertical
tubes makes a good hot-water heater.

Figure 79 shows a modification of it used by the writer.

FIGURE 76.

It is shown without a magazine, but when desired it may have
sufficient of the centre tubes omitted and an appropriate
wrought-iron magazine inserted with cast iron muzzle. As
shown the gases of combustion pass upward in the centre tubes
and return by the outer circle of drop tubes to the annular

smoke connection at the bottom, from whence it passes into
the chimney.   If considered desirable the brick-work can be
set three inches or thereabouts from the boiler, and an up-take

FIGURE 78.

formed, so as to make heating surface of the outside of the
shell.   When the porosity of brick-work, and its liability to
leakage of air by cracks, is considered, it is questionable if

anything is to be gained by such a form of setting, and if the
work is poorly done a loss will result ; therefore, the form of
setting shown is the one I approve of with this boiler.

FIGURE 79.

The upper smoke connection is of cast iron made in six
parts that are laid into place about the main flow-pipe. They

FIGURE 80.

FIGURE 81.

can be removed one at a time and part of the tubes cleaned, even where the apparatus is in use.

These boilers have very little internal resistance to the flow of the water, and have a high efficiency per square foot of heating surface. It is claimed, however, that the wrought iron tubes of these boilers eat or corrode away in a much shorter time than the shells, and especially so when soft coal is the fuel. The reason is not plain, but it does appear that the wrought iron tubes of a hot-water boiler eat out faster than the tubes of a boiler used for steam. For this reason recent efforts have been made to produce a suitable cast iron upright boiler that will be a proper substitute for the regular wrought iron upright, especially for house heating.

The "Gurney" hot-water boiler, shown in Figure 81, was the first prominent cast iron boiler of its type put in the market. It was invented by Mr. Edward Gurney, of Toronto, and first used in Canada. It is, now however, made in Boston by the Gurney Hot-Water Heater Company.

The illustrations, Figures 80 and 81, show the boiler in its most recent form. The lower section (No. 1) forms a "water-bottom" beneath the fire. The second section (2) is technically a "water-leg." Section 3 forms the fire-pot, and is arranged on the fire side so that a little more than half the inside surface is covered with fire-brick. Between the fire-brick panels the iron of the fire-pot projects to the fire, so as to make alternately a fire-brick and an iron panel. The advantage claimed for this is that the fire-brick, when so arranged, is practically indestructible. The explanation given is that when a fire-pot is all fire-brick the slag of the fire

clinkers on it and ruins the brick.   On the other hand, when
a fire-pot is all iron the heat of the fire is taken away so rapidly
that combustion is interfered with and slow fires are more likely
to go out, but that with this arrangement enough of the heat of
a strong fire is taken away through the iron panel to prevent

FIGURE 82.   FIGURE 82'

the adhesion of the slag to the brick, and that with slow fires
the brick forms refractory surface enough to prevent the fires
from becoming black at the sides.   As to the correctness of
the theory I do not presume to give an opinion.   I do know,
however, that the brick lasts much longer arranged this way

than when in a continuous ring around the fire, and that they do not clinker.

The fourth section of the boiler is corrugated inside and out to increase the surface. The fifth section forms the crown sheet and above it the tube and flue surface.

A noticeable feature is the system of bolting the sections together. Formerly long bolts ran from top to bottom, but in the improved form short bolts are used, as shown in Figure 81. Several advantages are claimed for the short bolts, an important one of which is the ability to break any single joint

FIGURE 83.

without disturbing the others. In the flue sections all the angles are replaced by curved corners, and the top and bottom surfaces of each section are concaved on the fire side, while the water side is convex, leaving no chance for lodgment of air or steam within the sections. Reference to the illustrations (Figures 80 and 81 with the details above them) show the other peculiarities of the boiler and its general arrangement.

Another of this class of boilers is shown in Figures 82 and 82'. It is called the " Perfect," and is made and sold by the Richardson & Boynton Company of New York.

FIGURE 84.   FIGURE 84¹.

It is square and a section lined with fire-brick forms the fire-box. The next two are water sections and form the furnace. The remaining sections form the crown and flue surfaces. This boiler may be said to be a cast iron box coil, as it fully contains that principle in the arrangement of its water-ways. The water enters the lower hollow section, passes upwards at the front corner into the second section ; thence backwards and upwards again to the third section ; thence front again, and so on, giving a positive circulation of the water in its passage from the inlet to the outlet. The internal resistance of this boiler compared to a wrought-iron box-coil boiler is very small.

The Figure 83 shows two sections of the heating surface above the fire, and the method of joining them at the opposite corners is clearly made apparent.   The broken sections, Figure 82, show the general arrangement and cross section through the V-shaped water tubes.

The next boiler of this class to appear was the " Spence," a Canadian boiler, shown in Figures 84 and 84', and made by the National Hot-Water Heater Company at Boston.

In general appearance and in some points of detail it re-sembles the boiler, Figures 80 and 81, as may be readily seen. A feature of it is the arrangement of its internal circulation. The water that enters the fire-pot section passes to the second section at the back and enters the upright water passage a, where it is made to flow around the septum c in each remaining section before it can get into the second upright water passage b on its way to the flow-pipes at the top. It is a positive circulator, meaning that the water must flow in a certain direction, and is in a measure a cast-iron spiral-coil boiler.   Its internal resistance, compared to coil-boilers,

FIGURE 85.

however, is low, and in any case it is not of sufficient import-
ance to be particularly objectionable, or to materially add to
the resistance of the general circuit.

Figure 85 shows the Mowry hot-water boiler made by the
Page Steam Heating Co., of Norwich, Conn.

It is made up of cast-iron sections with screwed joints, and
contains features that may be traced in the boilers shown in
Figures 80 to 84, with many that are particularly its own.

For instance, the fire box is made up of a number of upright
section or "staves," shown in cross section at the upper right
hand corner at F, which are made into a shoe at the bottom.
The upper ends of these staves or fire-pot sections are made
into a crown section, which in plan is somewhat like the figure
in the upper left-hand corner (Figure 85) and which is com-
posed of V shaped radial arms.   The remaining sections (s)
are very similar to the crown section, with radial V shaped
arms, arranged one above the other in such a manner that the
gases of combustion are deflected from one to the other, so
they do not find a straight passage between the arms of the
wheel.   It is in the V shape of the heating surface of the
wheel sections and in the "staggered" arrangement of the flues
the similarity to the boilers before mentioned can be seen.

The sections are joined together with 8-inch screwed
nipples at the centre as shown, and a manifold header is
arranged top and bottom for the flow and return pipes.

Figure 86 shows the "Auburn" hot-water boiler made by
D. F. Morgan, of Akron, Ohio.

It is made entirely of cast iron and consists of a base,
in which hangs the grate, the base also forming the ash-pit.

FIGURE 86.

These boilers are jacketed with cast-iron cases up to the centre of the second section, B. Above this point a sheet-iron case is used, the lower edge of which rests in the cast-iron case at the bottom, and reaches to the projecting flange at the head of the finishing section, D.

On the base rests the fire-pot, section A, with four openings for the upward circulation of the water. These openings *w w* can be plainly seen in the details, B and C, and correspond in all the sections.

The section B is the next above the fire-pot: giving additional height to the furnace. Then follows *three* or more sections, of the wheel pattern shown in plan at C, in the upper right hand corner of the Figure 86, these sections form the flue-surface ; the arms *a* being heart-shaped in section, with the point upwards, the object being to form an upper surface on which no considerable quantity of ashes can lodge, the under side of the same tubes being coved so as to offer as great a surface as possible to the fire. The water-tubes *a a* are staggered so as to force the gases of combustion from tube to tube in their upward passage.

Above these flue-sections, which may be of any number, is a cap or finishing section D, from which the flow-pipes start and which forms an upper smoke connection, with the drop flues *d d*, seen both in the section and plans B, C. The gases of combustion are again turned upwards between an iron case and the outside of the boiler, as shown by the arrows in the sectional illustration.

Side magazines are used on these boilers as shown at M, and the cleaning-door extends the full height of the flue sections, admitting the introduction of a flue brush at any state of the fire through openings or slots between the sections. The internal resistance of this boiler is very small.

Figures 87 and 88 show the " Mahoney " boiler, made by Mr. M. Mahoney, of Troy, N. Y. It is simple and efficient, and

is made of cast iron in but two pieces, the outer shell *a* and the inner casting *b*, Figure 88. The internal casting contains the entire fire surface forming no less than the fire-box and the flue surface above it. It is practically an upright-tubular boiler of cast iron, the water being in the leaves *c*, and the

FIGURE 88.

FIGURE 87.

triangular spaces *d* between them forming the upright tubes. Figure 88 is a cross-section through the magazine and flues above the fire-box.

Figure 89 shows the "Plaxton" hot-water boiler made by R. McDougall & Co., Galt, Canada.

It is made in vertical sections, and has the coil principle in-volved in it.   The principle is so apparent with regard to the direction and movement of the gases of combustion, as well as of the water, that no comment is necessary.

The Eclipse Manufacturing Company of Chicago handle an

FIGURE 89.

FIGURE 90.   FIGURE 91.

entirely different class of boilers from anything so far shown. They are wrought-iron welded-boilers, and were first made in England, where they are used to a considerable extent.

Figures 90 and 91 show one of the ordinary forms of this class of boilers.   Figure 90 is the boiler in perspective with-

FIGURE 92.

out setting. Figure 91 shows it in section with brick setting.

There are many modifications of this boiler made by Hart-
ley & Sugden, Halifax, Eng. They developed from the sim-
ple saddle boiler *a*, Figure 92, into boilers like *b*, *c*, *d*, *e*, *f*, and
many other forms that it is not necessary to show here.

The form of saddle boiler shown in Figure 93 has been
made in this country for greenhouse heating for many years,
by Messrs. Hitchings & Co., of New York. Boilers of this

FIGURE 93.

class are set in connection with an ordinary horizontal flue
extending through the greenhouse as shown, and the hot-
water pipes are carried from the boiler to the side of the
house opposite that occupied by the flue, or placed where
the heat is most desired, so as to equalize the heat of
the house.

The " Champion " boiler, made by Messrs. Warden, King
& Son, of Montreal, is a type not readily classified. It is shown
in Figures 94, 95 and 96. It has the advantage of presenting a

Figure 95.

Figure 94.

Figure 96.

large surface in a small space, however, and may, no doubt, present ideas not suggested by any of the former types. A point about it, which is not purely its own, but which is not apparent in any of the others, is the double grate, where ashes and cinders can be separated and the latter thrown back on the

FIGURE 97.

fire, the former being removed at the lower door. There is another and probably greater advantage, however, in the second grate of having the air pass through it and the ashes, etc., it contains on the way to the fire. It results in warming the air on its way to the fire and cooling the ashes and cinders, thereby prolonging the life of the upper or fire grate.

Figure 94 shows the general appearance of the boiler with the cleaning door, etc., open. Figure 95 is a back view,

and Figure 96 is a view showing the details of construction.

Before leaving the subject of boilers, or "heaters," as they are often called, I want to refer to a type of small heaters sometimes met with. They are properly water-backs, from which one or two rooms may be fairly well warmed. The one shown, Figure 97, is a novel arrangement of parlor grate and hot-water heating apparatus, manufactured by the Philadelphia Exhaust Ventilator Company, and is simply a suitable open fire-place grate of appropriate design, in which the fire burns, warming the room in which it is placed, but instead of having the back, sides and top of fire-brick tiles, they are a hollow casting, which properly forms a hot-water boiler.

From this boiler is an ordinary flow pipe of a water-circulating apparatus, as shown at the top in the illustration. A similar return pipe enters the back at the bottom, and from these pipes a system of three or four coils or hot-water radiators can be warmed in a manner exactly similar to that from a regular heating boiler. Usually a room on the second floor of the house can be warmed by the hot water, and when it is necessary to warm a room on the same floor, large diameter pipes and a coil may be used.

To one acquainted with hot-water apparatus, it is enough to say that an open-tank system may be maintained with it in any usual manner, but it should never be used with a closed tank, on account of the flat sides.

In the first edition of this work I omitted to mention a special type of vertical water tube boiler that was then before the public and known as the Bolton Heater, but which I was not acquainted with. It is made by the Detroit Heating and Lighting Company, of Detroit, Mich., and is shown in the Appendix in Figures 1 and 2. I also avail myself of the opportunity to show a more recently designed boiler, known as the "Expert," and made by Sherman S. Jewett & Co., of Buffalo, N. Y., Figures 3, 4, 5 and 6 in the Appendix, and one made by the Richmond Stove Co., of Norwich, Conn., shown in Figures 7, 8, 9, 10 and 11 of Appendix.

DEVELOPMENT OF COILS AND RADIATORS.

THE earliest hot-water radiators were coils of cast iron
pipe carried about the sides of rooms or greenhouses in
the most primitive manner. Usually they formed a continuous
circuit from the boiler through the consecutive rooms of the
building and back to the boiler again, the water from one
coil passing into another, and so on to the end ; each being
somewhat cooler than the one preceding it. This is technically
known as a positive circulation, meaning that it must circulate
in a certain direction if it moves at all.

This principle required pipes of a large diameter, otherwise
the resistance would be so great from so much pipe and so many
elbows the water would not pass around the circuit in sufficient
volume to keep the last part of the circuit or heating pipe at

anything like a sufficiently high temperature to be of service as heating surface.

The objection to such a system, aside from its appearance and bulk, was that no part of the circuit could be interrupted without stopping it all, and therefore it was put up without valves, as a total interruption of the circulation by their use would cause the formation of steam in the boiler, the consequence of which it is not necessary to go into here. Figure 58

FIGURE 98.

page 223, is a sufficient example of this style of work, and, of course, it is obsolete now and only used for some special purpose.

The fact of being unable to shut off part of the circuit next suggested the system and principle shown in Figure 98.

When the occupant of a room or section required to shut off his coil he closed the cock *a*, and opened the cock *b*, still maintaining what may be considered a positive circulation, and simply cutting his coil out of the circuit.

This arrangement, though accomplishing one object—that of shutting off the radiators or heating surface of a room—resulted often in the closing of one valve without opening the other, so that the circulation was entirely stopped, and trouble followed.

To obviate this a three-way cock was substituted at the junction of the upper pipe of the coil with the flow pipe, so that the act of closing one pipe always opened the other. This cock is shown in Figures 99 and 100 in detail.

FIGURE 99.   FIGURE 100.

Figure 99 shows the current going to the coil, and Figure 100 shows it going through the mains only, the coil being shut off. All the pipes, of course, are of the same diameter in such an apparatus throughout its whole length.

It was soon found, however, that it was unnecessary to have a continuous circuit for the purpose of circulation, and an apparatus on the principle shown in Figure 101 was the result, with a single valve at *a* on each coil ; part of the current going through the coils when the valves were open or partly open, while a main circuit was maintained through the flow-pipe, tank and return pipe shown by the dotted lines.

The same large uniform diameters, however, were used for some time longer, and the result was the upper coils of a system would be warmer than the lower ones, on account of the greater length of the respective columns of water, and the direct action of the flow of the water past the lower branches. Various devices were tried to get a uniform distribution

FIGURE 101.

without regard to the diameter of the pipes, and Figure 102 shows the general principle used to divide the current.

With a straight rising pipe of uniform diameter the water passed to the upper coil, on the principle shown in Figure 101, more readily than to the lower ones ; the current of the water holding its straight course. The resistance caused by the change of direction at *a a* and at *b b*, Figure 102, by the arrange-

ment of the fittings, diverted and divided this current so that more equable results were obtained in the coils; the extra bends and turns favoring the lower coils by dividing the currents at *a a*, and retarding the upper coil currents at *b* and *b*.

FIGURE 102.

The proper proportioning of the diameters of the pipe for the different levels, of course, would obviate the difficulty, but as there were very few sizes of the pipe used at the time, and those principally cast iron, this was not practicable.

Pipes of a very large diameter throughout would result in carrying sufficient water through the circuits, so that the differ-

ences of temperature at different points would be inconsiderable and there would be no necessity for the arrangement shown in Figure 101 ; but they would have to be so very large they could not be tolerated in ordinary buildings. It is ancient history, however, to be repeating this to the trade now, and it is only referred to in a cursory manner as a preface to the present practice.

FIGURE 103,

From the crude apparatus of forty and more years ago, and the idea that "the power of the boiler" was necessary for circulation, we have developed modern types of various common-sense forms, and demonstrated that the pipes of a hot-water apparatus can be branched with as much impunity as the pipes of a steam apparatus, provided strict attention is paid to relative diameters of parts, and that the power or difference of weight between the legs of the syphons formed within the branch or radiators is sufficient to keep the water circulating, irrespective of the direct power from the boiler or main circuit ; in other words, it was seen that when an apparatus was designed to give equal resistance to the flow of the water at all points,

all radiators would act alike, and give very nearly equal
temperatures at all points. Previous to this nothing but the
coil principle was applied to the radiators, as the general idea
prevailed that the continuity of the current could not, or at
least should not be broken.

Changes in types of radiators for hot water were made
cautiously, however, at first. They passed from the flat or wall
coil class, Figures 32 and 33, into the box-coil, Figure 104;
thence to wrought iron vertical tube radiators, connected top
and bottom with chambers, and lately into cast iron loops of
almost as many various forms as there are of steam radiators,
each maker of steam radiators being anxious to supply the
hot-water trade as well.

The box-coil radiator is largely used for indirect work, and
though it is fast disappearing for direct radiation, for indirect
radiation it is still used, and modifications of it that are made
of cast iron are likely to have a prominent place in present and
future practice.

INDIRECT RADIATORS.

The box-coil shown in Figure 103 is the one used by Messrs.
Bartlett, Hayward & Co. in the State, War and Navy De-
partment building for indirect radiation. They are made
of cast-iron pipe three inches in diameter, with bell and
spigot ends, the spigot end being a bend, and the sec-
tions are connected to make a box-coil with cast-iron headers.
The pipes are set with 5-inch centres in both directions, and
the joints are made with hemp ropeyarn saturated with lead
paint, driven into place with a hand tool. They are suspended
within the coil-chamber on T-irons built into the walls.

Rust joints may be used if desired, and when once set with-out splitting the hubs make a more desirable joint, as they are as permanent as the pipe. They require care and judgment, however, in the making, as the rust swells and splits the hubs if not properly prepared and used.

FIGURE 104.

These coils are usually set in brick chambers as shown in Figure 104, which is introduced here as being typical of all brick settings for indirect work.

The chambers are built of brick with 8-inch walls, and run to the ceiling of the cellar. The valves are ordinary gate-valves, and one is used on both flow and return pipe, the ob-ject of the second valve being to permit of shutting off the coil for repairs without interrupting the remainder of the apparatus.

An advantage of large diameter coils is their low resistance to the flow of the water, and their capacity to retain heat after the fire goes out on account of the large amount of water they contain.

The wrought-iron box coil, made of pipe and cast-iron fittings, is too well known to all persons interested in the

FIGURE 105.

construction of warming plants to require anything more than a mere allusion to here. It would be better, however, when using them for hot-water purposes to make them larger in diameter than the conventional 1-inch pipe, it lessens the

FIGURE 106.

resistance to the flow of the water through them, and makes them less likely to be frozen should the fire go out.

Figures 105 to 108 show a class of indirect radiators that may be said to be modifications of a box-coil. They are made of cast iron, and are usually two pipes high by any required number in width, and the heating surfaces are increased by flanges or fins called extended surface. These

projections or fins interlock so as to compel the air to be diverted from one to the other in its upward passage between them.

Figure 105 shows the "Clogston" cast-iron box radiator made in Boston, and considerably used in the New England States. There are two modifications of it—one with centre connections and one with end connections; the latter being shown in the illustration as being better adapted to hot-water heating.

FIGURE 107.

FIGURE 107'.

It is connected with R and L nipples between the sections, as plainly shown in the illustration, and set in any manner suitable to a box-coil for indirect radiation. The ribs or flanges which form the extended surface run in an unbroken ring about the pipe.

Figure 106 is a section of the "Climax," made by the A. A. Griffing Iron Co. of Jersey City. The sections are made into a box-coil by 2-inch right and left nipples, and the radiator is

set and boxed in the usual manner. The boxing, etc., is applicable to all radiators alike, therefore it is unnecessary to show more than a radiator, or a section thereof, in the examples of this class.

Figure 107 shows the "Eclipse" indirect hot-water radia-tor made in Chicago by the Eclipse Manufacturing Company. Figure 107' is a side view of a single section of the same. It differs very little from the "Clogston" except in the arrange-

FIGURE 108.

FIGURE 108'.

ment of the fins or flanges. In this radiator they run but half way round the section, and interlock when the sections are connected side by side. The sections are connected at opposite ends by right and left nipples, as will be seen in the illustration Figure 107'.

Figure 108 shows the "Excelsior" indirect radiator, made by the Pierce Steam Heating Co. of Buffalo, N. Y. It and the Eclipse are almost identical in appearance, and the method of joining the sections is the same

Figure 109 shows another class of extended surface. It is known as the "Compound Coil," on account of it being formed by winding a helical coil of No. 14 square iron wire about the wrought-iron pipe of a plain coil. The headers and return bends are covered with "pin" extended surface, and the

FIGURE 109.

FIGURE 110.

mode of boxing is similar to any box-coil. It is made by the Gold Car Heating Co. of New York.

Figure 110 shows the "pin" hot-water radiator. It is known as the "Utica" pattern, on account of being connected at the ends of the sections so as to give a continuous passage to the water from inlet to outlet. It is made by the H. B Smith Co. of New York.

Figure 111 shows an early type of extended surface hot-water radiator made by the Morris Tasker Co. of Philadelphia. It is called their " Ribbed Radiator for Hot Water." It is held together with long bolts, and paper or rubber gaskets are used in the joints. It answers for very low pressure work.

FIGURE 111.

Wrought Iron Radiators for Direct Radiation—Cast Iron Radiators With Bases—Cast Iron Sectional Radiators.

DIRECT RADIATORS FOR HOT-WATER HEATING.

THE impetus lately given to the hot-water business in the United States is, no doubt, largely due to the invention of modern types of upright radiators that differ nothing in appearance from modern steam radiators.

The use of direct box-coils for hot-water heating were undesirable in any furnished room or residence, and when they were covered with cast-iron fretwork screens with marble tops, etc., they became repositories for dust, etc., and were neither conducive to health or cleanliness, and in public buildings they became sarcophagii—which they so closely resemble—for ancient tobacco and general filth.

Flat coils, when used as direct hot-water radiators, were not objectionable so far as cleanliness was concerned, but they were never considered ornamental. Their capacity with regard to surface being limited—without using large and objectionable diameters—and the wall space they occupied made their use in furnished rooms very rare; and unless in small

bed-rooms or bath-rooms, they are not much used in residences by American architects.

The advent of the vertical tube or loop hot-water radiator however, did away with this objection, and placed hot-water radiators on the same footing as steam radiators, so far as their general appearance is concerned ; and with most types of vertical radiators at the present time there is no difference

FIGURE 112.   FIGURE 113.

between those used for hot water and those used for steam, that is apparent to the casual observer, who is not an expert.

There is no doubt many ideas have been conceived from time to time, and some of them put in limited operation, wherein the present types have been anticipated ; and in the order of the production of many of the present radiators I may not be quite clear, as they are all the production of the last two or three years, with a few exceptions, and therefore if the order in which they are mentioned or shown here is not the order in which they were first introduced to the public, the individuals who had the honor of producing them will

know that it was through a lack of data on the subject that*
they are not so presented.

Quite early in the history of vertical tube wrought-iron
radiators Messrs. Bartlett, Hayward & Co., of Baltimore, made
the hot-water radiator shown in Figure 112.

The "top" or entablature is a hollow cast-iron casing into
which wrought-iron tubes are screwed, the same as into the
base of a steam radiator. The free ends of these pipes, how-
ever, are left open, and are passed through corresponding holes
in the upper side of a radiator base and there expanded, some-
what like a boiler tube. The bottom of this base is then at-
tached with screws and a joint made on a copper or other
suitable gasket; and the detail, Figure 113, shows this con-
struction plainly.

Water can be admitted to the base at one end and passed
out at the other; and so long as the air is drawn from the radi-
ator at its uppermost point, so as to allow it to fill properly
with water, it is found that the temperature at any point varies
so little that it is not necessary to supply it at the top; an idea
that was prevalent some few years ago.

The Kelly & Jones Company, of New York, have more
recently made a radiator on this principle, also screwing the
tubes into the top and expanding them into the base.

To Samuel D. Tompkins, Treasurer of the A. A. Griffing
Iron Co., I believe belongs the credit of joining cast-iron
loops of the Bundy pattern with a hollow top casting, and
making the first cast-iron modern loop hot-water radiator.
Had he considered the matter solely in the light of pre-
vious workshop practice, he would perhaps not have under-

taken it, as such a method of joining loops for steam pur-
poses had always proved a failure, on account of the difficulty of
keeping the joints tight, through the trouble from differential
expansion of the pipes due to sudden differences of tempera-
ture when letting on steam.

He, however, found that for hot-water work the changes
of temperature were not sufficiently sudden to strain the
metals beyond their elastic limits ; and this is so clearly defined
now that all makers join their hot-water loops with rigid
connections at the upper end as well as at the lower end.

FIGURE 114.

Figure 114 clearly shows the construction of the "Bundy-
Tompkins" hot-water radiator. The loops are screwed into
the base the same as in the steam radiator. The cap, or top
a, however, is cast hollow, with a series of tapped openings, b
and c, through it. The upper opening, b, is sufficiently

large to permit the passage of short brass nipples that
are shown joining the head of the loops with the holes *c c*.
The holes *c c*, and the holes in the heads of the loops are tapped
at one operation of the tap, so they coincide in taper and thread
register. The short threaded taper tube or nipple, which is made
of brass with a square hole in it for the wrench, is then forced
into the hole *c* and into the head of the loop ; when the hole *b* is
plugged with a hollow plug, after which an entablature of fret-
work is put over the whole to cover the plugs and give an or-
namental finish.

FIGURE 115.

Figure 115 shows the radiator as it was first constructed,
with a partition at *a*. It was first thought necessary to intro-
duce this barrier to the current of the water, so as to turn it
into the head of the radiator and prevent its passing through
the radiator from inlet to outlet.

This was to carry out the old idea that a continuous cur-
rent was necessary for circulation. It was soon discovered,
however, that the circulation was better when the division *a*

was broken through.   The resistance to the passage of the water, caused by forcing it upwards through the end tubes of the radiator and their nipples, as seen in Figure 115 by the arrows, before it could get over into the remaining tubes, was so great that to get relief for the circulation the workmen punched out the division *a*, and the improvement was manifest. The hand when passed over the tubes then indicated that the water being allowed to take its own easy course, according to

FIGURE 116.

its weight, flowed upwards through the first two or three tubes (or sets of tubes when the radiator was more than one tube wide) and passed along in the cap, circulating downwards in the remaining tubes.   At present they are made without the partition and the water diffuses according to its temperature ; the colder particles falling to the base and passing out by the return-pipe.

The second prominent cast-iron vertical loop radiator for hot water to appear was the "Union Radiator," the invention of John R. Reed, shown in Figure 116, and made by the H. B. Smith Company, of Westfield, Mass.

This radiator is made up of three-column sections as shown to the left of Figure 116. The sections are joined to each other at the top and bottom by taper nipples of soft iron, and they are pressed together by special machinery.

FIGURE 117.

Figure 117 shows the radiator broken away so as to present a section through the centre columns, showing the nipples *a a*. The holes in the sections which receive the nipples are reamed with a special machine so as to secure uniformity of diameter and taper, and also a fixed distance between the centres of the holes. If the holes are not absolutely true it matters not with the soft iron nipples as they take a permanent though somewhat elastic set to accommodate themselves to

slight inequalities. This method of connecting was also a new departure from old ideas that were based on steam practice. Constant use has demonstrated its practicability and overcome the prejudice to it for hot-water work.

FIGURE 118.

Short rods are used top and bottom, in such a manner as to be unobserved, their purpose being to prevent a disturbance in the joints when handling. In short radiators they are run from end to end, but in long ones they "break joints;" so the difference of expansion between the warm cast-iron and the

comparatively cold wrought-iron rods is inconsiderable and not sufficient to overcome the elasticity of the metals.

In general appearance they resemble steam radiators, and in some cases I believe they are used in combination apparatus for both purposes. They have the advantage of having no base, and an open fret-work entablature is set over the top to give an appropriate finish.

Figures 118 and 119 show respectively the "Bundy Elite"

FIGURE 119.

and the "Triumph" radiators, made by the A. A. Griffing Iron Company.

The "Triumph" is comparatively an old pattern as designed for steam. As hot-water radiators, with upper connections, they are both, however, recent productions. The "Triumph" is plain, with cast-iron fret-work cap, and resembles the "Union" radiator in all but design and the manner of joining the sections. The "Bundy Elite" is ornamented

in relief, and belongs to the more recent class of hot-water radiators, being without base or entablature.

In these radiators the lower connection is made by screwing the sections of the radiator round and round on 2-inch taper nipples, allowing them to become tight on the taper of the threads just before the faces come together. The upper joints are made with special vulcanized fibrous packings,

FIGURE 120.

pressed together by a long bolt through the water space and finished at the outer ends with ornamental nuts. The method of joining the "Triumph" is the same as that used in the "Elite."

In the radiators of the class of the "Union," "Triumph," and "Elite," in which there are three columns to a section, the course of the circulation is supposed to be upwards through the centre passage, and downwards in the outer columns. This

would be the natural course for the water to take, and in cases where the writer had an opportunity to test the matter, this is the course the water took ; and at the sections near the inlet its course was well defined just after turning the hot water into the radiator.

Figure 120 shows the "Eclipse" hot-water radiator made by the Eclipse Manufacturing Company, of Chicago, Ill. It is made of cast iron and is without base or entablature. The

FIGURE 121.

sections or loops have two columns, but in other respects it resembles the last class of radiators. The method of joining the sections is the same, the lower ends being joined with 2-inch threaded nipples, and at the top with faced joints held together with bolts.

Figure 121 shows the "Ideal" hot-water radiator made by the Pierce Steam Heating Company, of Buffalo, N. Y.

In almost every respect, except ornamentation and the method of connecting the sections, it is the same as the last radiator (Figure 120). It differs, however, from all others of its class in the manner of making the joints between the sections.

A special 2-inch right and left handed malleable iron nipple is used both at top and bottom of sections. In the use of a right and left nipple there is nothing new, but in this case the

FIGURE 121'.

novelty consists in disguising the fact of there being nipples between the sections by making them appear as part of the general design, and not materially increasing the distance be-between the centres of the sections.

Ordinarily a nipple requires sufficient length between the threads to allow of its being grasped with a wrench or tongs. In this case the threads on opposite ends of the nipples come

within one-quarter of an inch of each other, and a flange projects and overhangs the threads, as shown in Figure 121'. On the left, three sections are shown, two of which are cut away, top and bottom, to show the right and left nipples, *a a*. One element or section is shown complete to give an idea of the appearance of the nipples when the radiator is finished. A

FIGURE 122.

special wrench is used to screw the nipples into place and the sections are drawn together parallel.

The radiator shown in Figure 122 is called the "Perfection," and is made by the Michigan Radiator Co. of Detroit, Mich. It is of the same class as the two foregoing, its only material difference being in the manner of joining the sections. Right and left-handed nipples are used without shoulders, and the method

of screwing them together is with a special tool from the in-
side through openings left in the last section that is added to
the radiator. The final openings at the top are then plugged

FIGURE 123.

and the lower ones are used for the inlet and outlet pipes.

Figure 123 shows the "Whittier" extended-surface cast-iron
radiator. It is made by the H. B. Smith Company, and is

FIGURE 123'.

much used in the Eastern States for either steam or hot-water.
It is a comparatively old radiator, being patented in 1868.
It is what is known as a positive radiator—that is, the circu-

lation is continuous; the same as in a coil, which is fully shown by the arrows in Figure 123'. It is usually three sections high, as shown in cut, and one section is joined to another with a

FIGURE 124.

2½ screwed nipple, as seen at *a a*, Figure 123. The opposite points at *b b* are keyed together by a double dovetailed key, as shown at *b'*.

FIGURE 125.

These radiators have a low resistance, and will circulate until the water falls below the inlet *i*.

Figure 124 shows a horizontal hot-water radiator made by Messrs. Bartlett, Hayward & Co. It is made of wrought-iron

pipes, screwed into a hollow casting, with return bends on the opposite end of each pair of pipes. Over the bends is placed a hollow casting of the same general appearance as the opposite one.

Figure 125 shows the detail of the construction of this radiator. The water enters the upper pipe and returns by the lower one, diffusing within the loops by presumably entering the upper pipe and returning by the lower one.

In a general way the radiators from Figures 114 to 122 inclusive, belong to the same class. Both upper and lower connec-

FIGURE 126.

tions form a water-way. The upper connection also forms a passage for the egress of the air to a single point, which is a necessity of all hot-water radiators.

The general idea prevailed not long since that hot-water radiators should be supplied at the upper connection, so the flow of the water would be downwards from this point. Now, however, it is known to be unnecessary, as the water

will rise to the head as rapidly within the first few tubes of the radiator as it will in an outside connection. It has also been found that when the air has been neglected and not drawn off regularly in this class of radiators that a circulation will go on from inlet to outlet, and that the efficiency of the heater is not entirely destroyed.

The writer has found that as long as the water remains above the level *a*, Figure 126, a circulation will go on by passing up on one side of the loop and down on the other, some little condition favoring one side ; while the main circulation passes through the base.

I also found that through months of neglect to draw the air from the head of the radiator the water fell below the top of the loop to a position about at *b*, Figure 126. Even then the water in the sides of the loops did not become cold, but that a circulation or diffusion went on in each side of loop sufficient to keep the water to all appearances about as hot as in the base.

This applies to all this class of radiators, and though their efficiency must be impaired when they are so neglected, it is still a point in their favor over coil radiators, which latter will stop circulating the moment the air collects to any considerable degree in the upper header or pipes.

The internal resistance to the flow of the water through radiators with a base is small, and I have therefore not considered it necessary to take it into account in designing the mains of an apparatus. In the radiators whose water-way at the bottom is small, however, the resistance may become great, and therefore in all radiators joined with nipples their diameters should be as great as possible, especially in long radiators.

CHAPTER XXIII.

*Air Traps in Pipes—Their Effect on the Flow of the Water
—Top Connections From Main Flow Pipes—Bottom
and Side Connections From Flow Pipes—System
of Piping for High Buildings—Valves on
Radiators—Main Circuits of Uniform
Diameter Throughout.*

NOTES ON RUNNING MAIN PIPES.

THE most important thing in relation to running the pipes of an apparatus is to guard against the lodgment of air within them at points that may be called " air-traps."

When running pipes for steam, "water-traps" are to be avoided, and by a water-trap is meant a sag or downward deflection of the pipe from its perfect alignment.

Air-traps are upward deflections of the flow or return-pipes of a hot-water apparatus from their perfect alignment, and they may be classed under the heads of accidental and necessary.

In a horizontal pipe, or one that is nearly horizontal, such as go to make up the mains of an apparatus, but with pitch sufficient in some direction to carry the air to some particular point of egress, the pipes should always be straight and perfect in alignment when viewed from the side. This is absolutely necessary, as the least

irregularity or bend of sufficient magnitude to hold air
will impair the circulation in a measure far beyond what any
one is likely to suppose who has not had practical experience
in the matter.

Let *a b*, Figure 127, represent the level line of a floor, and *c d*
a flow or return pipe hung thereto, with considerable down-

FIGURE 127.

ward pitch in the direction of the arrow. Should this pipe
have a bend or trap in it at *e* equal to the diameter of the pipe
as shown, it will entirely stop the circulation, either by pre-
venting it at the commencement, by not being able to expel

FIGURE 128.

the air, or by the air accumulating thereat in a short time, even
if it has been expelled, although the end of the pipe *c* is higher
than the top of the trap *e*.

Should the bend or trap *e* be only half the diameter of the
pipe as shown in Figure 128, then just half the pipe will be shut

off with air as effectually as though we closed it with a valve, and consequently only half the water will pass at this point that the diameter of the pipe would warrant, and therefore only half the work will be done and the temperature of the water in the radiators cooled or lowered twice as many degrees as it would if the pipe was straight.

Many imagine the pressure should expel this air, but this is erroneous as it has no more possibility of doing so than pressure has of expelling the air from an air-chamber on the side of a pipe as shown in Figure 129. It will compress the air

FIGURE 129.

somewhat, but the air that is liberated from the water being under the same pressure, passes into the trap or chamber by difference of gravity and remains there, displacing an equal bulk of water.

With an open ended pipe the passage of the water under considerable head would push the air before it, but in the circuits of an apparatus this cannot follow.

When going upwards within buildings with lines of rising pipe every line or radiator helps to take air from the boiler

or mains, and consequently air-vents must be used on the heads of the lines or on the radiators where they will do the most good, so that for ordinary pipe work for direct radiation it is hardly necessary to more than advise the fitter to run straight pipes and pitch them so the air will be safely carried to the point of exit.   Therefore, it is probably nearly always proper to take the rising lines and radiator connections from the top of the main as shown in Figure 130.

It is a good plan to use the top outlet, *a*, of the *tee* one size larger than the pipe *b*, so as to have a reducing elbow at

FIGURE 130.

c. It favors the water entering the rising-line or connection as it assists the change of direction of the proportion of water that should pass into the branch, by lessening the obstruction presented to it by the ends of the pipes, etc.

There is no particular objection to a side connection, except that under such condition the air must be carried further along the main, or that the convenience of a swinging joint is not obtained.

Care must be taken in making connections for indirect radiators however. The indirect radiators are usually in places that are inconvenient to enter to attend to air-cocks, and the penalty of the neglect of so doing is apt to be the freezing of the coils or radiators, not to take into consideration the interruption to the supply of warm air.

If a line of main pipe is near the ceiling, then the coils are apt to be below the main, in which case of course the air from the main cannot find egress through the coils, no matter how they are piped, and the connection shown by the dotted lines

FIGURE 131.

(Figure 131) must be strictly avoided, and either a bottom connection, as shown, or a side connection used, with the upward pitch from the coils towards the main as shown by the straight arrows, the waved arrows showing the direction of the flow of the water.

If indirect radiators are higher than the main flow pipe, it makes an exceedingly unfortunate arrangement, as in such a case the air will go to the indirect radiators or coils, and there is nothing to be done except careful attention to the operation

of hand vents at the coils, or the use of reliable automatic air-vents.

When the air is carried to the end of a flow main, as ·it properly should in the case of indirect work—unless it is let escape into rising lines—the highest end of the main should have a chamber on it for the collection of the air, and on this cham-

FIGURE 132.

ber an air-vent should be placed ; or if desirable and practicable a small open pipe may be run upwards in the building until it is above the top of the expansion tank.

For direct radiation at the present time the flow mains are usually run through the basements or cellars.

When direct and indirect radiation are combined it is almost necessary that they should be so run as to reach the indirect work without showing pipes in the rooms above the basements.

For direct radiation alone, however, the flow-pipes may be carried to the top of the house and run in the attic, or at the ceiling of the upper story, and for high buildings this system appears to have decided advantages over the basement or cellar system.

Figure 132 shows the scheme of pipes involved in such an apparatus.

The air is relieved at the highest point through an open pipe which bends over the edges of the tank, and beyond this the fall of every piece of pipe and its direction is with the downward flow of the water ; so that the darts and arrows show not only the downward pitch of the pipes, but the direction of the flow of the water, in all except the main rising pipe q.

The circuit formed by the main pipes a, b, c and d would be best if of a uniform diameter and proportioned to pass as much water through it—when all the radiators are closed—as is required for all the radiators when they are in use, or nearly so.

If this circulation is maintained, it accomplishes two things : (1) it provides a relief to the boiler when many of the radiators are closed, as they must be expected to be in office buildings ; and (2) it always maintains a hot-water supply ever ready to flow into the risers and radiators when the latter are turned on. In fact, with this circulation going on, the conditions are almost as good as though the water for a single rising line was drawn direct from the head of the boiler.

With apparatus as they are ordinarily constructed, with mains in the cellar and rising lines starting therefrom, there is no circulation unless through the rising lines and radiators; and should only a single radiator on a line be opened, there would probably not be sufficient water pass through the circuit and the line to make the heater of any practical value ; as the quantity might be too small to counteract the cooling effect of the surface of the riser and circuit.

This brings us to the question of the advisability of using valves in all cases on hot-water radiators.

In small apparatus in private houses under one management valves may be either used or omitted with perfect safety. If they are used the owner soon finds it is much easier to control the heat of the house by attending to the fire than by using the valves on the radiators, and consequently the valves, as a general thing, are always wide open, unless in the case of some particular room where heat is not required, or where a modified temperature is desired, where they can be choked down until the circulation is reduced to the desired quantity, or until it is entirely cut off.

In office buildings, where there are persons of different temperaments who have no control of the firing, valves must be used to allow each person to adjust the heat to his own liking. It is in cases of this kind that main circuits, independent of the radiators, are most required.   They give vent to the main circulation of the apparatus and maintain heat at distant points, although the greater part of the radiators may be closed.

A small hole through the disk of every valve can also be provided, and consequently a feeble circulation maintained at all

times through every radiator, which will accomplish about the same purpose; and in fact, it is good practice to do this in all cases, as it prevents trouble at the boiler and lets the air pass

FIGURE 133.

forward at all times, when it is disengaged in quantities.

In the case of the flow-pipe being in the cellar, and consequently when it is below the radiators, there is some question as to

FIGURE 134.

whether these main circulating pipes are practicable. They are practical and proper in indirect work, where the main is above the coil and the return below, as seen in Figure 133 at *a;* but

in cases where the radiators are on floors higher than the mains,
as seen in Figure 134, there is some question as to their utility.
In such a case they lessen the head that causes the flow
through the radiators, and some say the return water frequently
backs up in a certain radiator and the circulation goes on the
wrong way within them : still I am of the opinion this is caused
by the scanty size of the flow and return pipes, as it always hap-
pens at the last radiator, if at all ; and, therefore, I advise the use
of the pipe in this case with a gate valve in it at *a*, Figure 134,

FIGURE 135.

that can be choked down or closed entirely if necessary when
the apparatus is in use.

When we make a large diameter main circuit in this man-
ner, taking flow from the upper pipe and returning to the lower
one, our radiators are in almost the same relation to the boiler
they would be in if we took a single flow pipe from its top and
returned to near its bottom, as in Figure 135. Therefore the more
rapidly the circulation goes on from the flow *b* to the return *c*
through the pipe *a*, Figure 134, the hotter the water will reach
the radiators.

CHAPTER XXIV.

Expansion Tanks—Open Tanks—Closed Tanks—The Danger of Closed Tanks—Safety Valves on Closed Tanks—Table of Size of Tanks to be Used with Apparatus—Diagram Showing the Expansion of Water—Table of the Temperatures and Pressures of Steam and Water—Diagram of Temperatures and Pressures of Water.

EXPANSION TANKS.

THE question of the position of an expansion tank on an apparatus is one of importance, and requires to be considered in its different aspects.

The ease with which sketches and diagrams are now reproduced by photo-engraving and other inexpensive processes puts it within the power of a writer to appeal to his readers—especially the purely practical ones—in a manner that is eminently more comprehensive than pages of description. It places him in almost the same relation to the reader as a lecturer or teacher occupies who makes use of the chalk and blackboard, a few crude lines often conveying more information to the observer by way of the eye than pages of type or hours of description, which require an extra mental effort to form the picture in the mind's eye.

I will therefore introduce diagrams of the ordinary methods of using tanks, as they occur to me, and refer to them briefly, pointing out their good points and their objectionable ones, and explaining why compromises must frequently be made in the selection of their positions, and how they are attached, etc.

The commonest position for the expansion tank is at the highest point of the flow pipe, as in Figure 136.

FIGURE 136.

This method is often seen in greenhouses, and is probably the most simple and effective when a single boiler is used with temperature less than 212 degrees.

The air can fly to the tank and escape from the water, and if all the pipes that lead away from the tank, to supply or form the heating surface, begin to fall from this point, no air can lodge within them, and should steam form either by strong firing or the closing of the circuits or radiator valves, no other damage can follow than the escape of the steam from the top

of the tank, which in all probability would be discovered before sufficient water could be evaporated from the apparatus to permit of the burning or other injury to the boiler.

To prevent damage within the house by the escaping vapor, an escape pipe *a* can be run from the upper part of the tank to the outside of the house, or where overflow pipes are used the pressure or vapor can escape through them.

By this method the temperature of the water can never go above 212° Fah., except that just within the boiler it may slightly advance beyond this point on account of the head of water that is above it in many cases, but as this hot water rushes upwards in the flow-pipe and the pressure becomes less, some of it bursts into steam and is lost by escaping at the tank, unless it becomes sufficiently cooled in its passage through the pipe so as to be below 212° Fah. when it reaches the tank.

To utilize this heat, or rather as it may appear to some to be cooling the steam within the water, and to allow them to carry somewhat higher temperatures, the tank is sometimes placed at the further end of the coils or circuits, which must then be the highest part of the apparatus, so that the water, though warmed above 212 degrees at the boiler, may be so far cooled by passing through the pipes that it will not give off steam when it reaches the tank.

Figure 137 shows how this is usually accomplished. The excess of heat above 212 degrees is given off through the sides of the pipe *f* before the water reaches the tank T ; therefore no steam is liberated and the water returns through the pipe *r* to the boiler.

For equal perpendicular heights the apparatus shown in Figure 136 will circulate more rapidly than the one shown in Figure 137, other things being the same, as with the tank placed so far from the boiler the cooling done by the pipe *f* makes the rising column so dense there is but a small preponderance of density or power in favor of the pipe *r*. Whereas in Figure 136 the water reaches the tank without cooling perceptibly and all but a small part of the cooling is done in the pipes *r r*, so that the difference of density between the rising and falling columns is at a

FIGURE 137.

maximum instead of at the minimum, as in Figure 137. Therefore to gain a little in the question of the temperature of the heating surface, much is lost in motive power, and larger pipe would have to be used to have an equal quantity of water pass around the circuit in the same time, so that from a purely philosophical point of view, the tank, as in Figure 136, is in a better position than in Figure 137.

The third position for the tank is to place it on the boiler as shown in Figure 138. In this case the tank simply takes care of the expansion of the water and does not assist the drawing away of the air from anything but the boiler. Consequently

an air vent must be put at the highest part of the pipes as at *a*.
I do not consider this as good a position as that shown in the
Figure 136. The objections to it are : If the steam is formed in
quantities sufficient to make a pressure at *a*, an amount of
water will be forced out of the boiler through the pipe *b* and
the tank and all the water in the apparatus may be forced out
and down to the level of the line *c* at the head of the boiler if
the fires are very strong, the steam taking the place of the

FIGURE 138.

water. The tank in this position, however, acts as a safety-
valve, but it would be equally advantageous as such if it con-
nected with the pipe at *a* instead of with the boiler ; in which
position the tank will also take care of the air—provided no
valve is used in the main pipe between it and the boiler.

The fourth position is, as shown in Figure 139, with the
tank pipe *b* attached to the bottom of the boiler.

When in this position an air vent is also required at *a* for
the purpose of taking care of the air which enters the main.

but with the tank as shown in Figure 139 it becomes possible to drive every drop of the water out of the boiler, if steam is formed in sufficient quantity.

Of course, when a tank pipe joins a return pipe it is subject to the same objections as when it joins the lower part of the boiler, and the foregoing remarks apply to it.

The tank question is complicated when more than one boiler is used if either of the boilers can be shut off from the apparatus by valves.

FIGURE 139

There are two sufficient reasons why more than one boiler is used in an apparatus. The *first* is, when one boiler has not sufficient capacity for the whole apparatus, and consequently one or more must be used, in which case there is no great necessity for stop valves between the boilers and it is probably better to omit them. The *second* is, when it is desirable to have a spare or extra boiler for emergencies, in which case, of course, it is necessary to shut it off from the apparatus when not in use, and valves must then be used.

In the first of these cases of which a simple illustration is shown in Figure 140, the tank is best at the highest point, as in Figure 136. It acts as an air valve and an escape for pressure and steam, as the latter can go very little above 212° Fah. without giving trouble with an open tank.

All that has been said of tanks in connection with a single boiler applies also to two boilers connected without valves (as in Figure 140) and therefore requires no further illustrations ; but should valves be introduced into Figure 140, as shown in

FIGURE 140.

Figure 141, at V V V V, it then requires only a little forgetfulness on the part of the operator to cause the destruction of a boiler.

Should the boiler B be cut out of the circuit by having both valves closed, then the water will be shut up within it, and should a fire be accidentally or otherwise started within it, it would be ruptured by the expansion of the water, and, of course, destroyed. If it were only partly filled with water and the valves tightly closed, then steam would be formed and as

disastrous an explosion from over pressure would follow as
with a steam boiler, as it is analgous to one without a safety
valve.

Of course, if the object of having more than one boiler is
simply to proportion the boiler surface and grate to the require-
ments of the weather, then a single valve may be introduced
into either the flow or the return pipe, as shown in Figure 142,
but never into both, when the tank may be placed as shown in
Figure 140, as the expansion of the water can then find its
way into the pipes of the apparatus through the pipe and is

FIGURE 141.

without a valve, and the most that could follow through a blun-
der of management would be of little inconvenience, and per-
haps the interruption of the apparatus for a short time.

The question sometimes arises as to whether it is better to
put a single valve of this kind into the flow or the return pipe.
I favor the return pipe, as by that means only the increment of
the expansion of the water can be forced from the boiler;

whereas if the valve is in the upper pipe the boiler may be forced empty simply by the formation of steam.

Valves are sometimes used with a hole bored through the disk to prevent the bursting of the boiler ; in which case an upper and lower valve may be used, the upper one having the hole.   This stops the circulation into the boiler, but it does not admit of cleaning or repairing without tight valves.

The question now arises as to how tanks should be applied in two or more boilers with tight valves, as in the State, War and Navy Department building, elsewhere referred to, and others.

FIGURE 142.

Boilers may be piped as shown in Figure 143 with tight stop valves, so that a single tank takes away the air and takes care of the increment of expansion, in which case the boilers are connected to a single tank by pipes *a* and *a* at the highest points of the mains, the valve in the main being beyond the junction. By this arrangement the boiler that is not in use is not affected, and any change of temperature allows the water to pass either in or out of the boiler through the pipe *a*.   Should it be

necessary to shut off a boiler absolutely then valves must be used on the pipes *a a*, and trouble may follow by neglecting them ; so that it would be better not to use the valves, but to have a means of disconnecting the pipes *a a* from the boiler that is not in use.

A tank to each boiler, however, as in Figure 144, is the only positively safe manner for the inexperienced ordinary user, if valves must be used in the flow pipes.

Of course when there is more than one boiler with valves on both pipes, as in Figures 143 and 144, then tanks cannot or

FIGURE 143.

should not be used on the pipes of the apparatus at the further ends of the lines or at any point outside the valves.

I presume I have said sufficient on this subject so that any intelligent man can form other combinations and consider their respective operations.

The prime use of a tank is to provide for the expansion of the water ; its secondary use is to take away the air from the apparatus and to let off steam when it is formed. The air,

however, may be taken away by air-vents in any suitable position, and in any kind of an extensive apparatus—not green-house work—it would be almost impossible to take care of all the air by the use of the tank.

There is one method, however, of using the tank whereby the air may be taken from the heads of the rising lines or from the principal divisions of a house, and where box-coils are used for radiators, or any form of radiators used wherein the water enters at the uppermost point, provided all the pipes of the

FIGURE 144.

division have an upward inclination to one point it can be used to good advantage, and will prevent the trouble of attending to the air-vents. The principle is shown in Figure 145, and it simply consists of small vent-pipes *a a a a*, or a system of them, rising from the heads of the lines or the highest point of the divisions to above the level of the tank. It is a good and safe method also to carry the end of this pipe over the tank so that a rush of confined air or steam will not discharge the water where it can become a nuisance or where it will be lost to the apparatus.

Pipes run in this manner should not have too small a diameter as the resistance to the bubbles of air is considerable, and therefore ½-inch pipe is probably as small as should be used unless to make a very short connection.

The pipes should also be carefully run so the alignment and pitch of the pipe will be upwards towards the tank. A slight

FIGURE 145.

trap of one-half the diameter of the pipe will make the whole abortive, and very little horizontal pipe should be used if possible, but if it is unavoidable, the diameter should be increased. If a pipe must be used in a nearly horizontal position, give it all the pitch possible, and see that its alignment is straight, etc.

Figure 146 shows the method of using the tank in the U. S. Barracks, David's Island, New York Harbor, erected under the direction of Capt. George H. Cook, U. S. A.

The pipe *a* starts from the highest part of the flow-pipe inside the valves, so the closing of the latter will not affect the contraction or expansion of the water in the boiler, or the rise or fall of the water within the tank, or cut off the water supply. At the same time the pipes *b* and *b* act both as expansion and air pipes from the main circuits.

FIGURE 146.

Should the pipe *a*, Figure 146, be extended past the flow pipe to join the return-pipe R instead of the flow-pipe F, the closing of both set of valves might prove disastrous should a fire be burning, as the water would be thrown out of the boiler through the tank should steam form; as it is shown, it cannot.

CAPACITY OF EXPANSION-TANKS.

In proportioning an expansion-tank for an apparatus it must be born in mind that its capacity between its cold-water level

line, and its overflow-pipe level must be something in excess
of the increment of expansion due to all the water in the
apparatus.

For instance, in Figure 147, the cold-water level line is at
a, the point at which the apparatus must be filled to before the
fire is started. At this point, of course, a ball-cock should
be placed when one is used. The line *b* is the level of the over-
flow-pipe at which an apparatus overflows through the failure

FIGURE 147.

of the ball-cock to close, or through the undue expansion of
the water or the accidental omission to close the feed-water
valve when the apparatus is full, should one be used.

This range between *a* and *b* requires to be not only suffi-
cient to provide for the increment of expansion, but also to
allow some factor for safety beyond this point, say not less than
10 per cent. of the calculated expansion.

In an apparatus that is open to the atmosphere and run at
temperatures not exceeding 212° Fah., it is usual to provide a

tank that has a capacity between the points a and b equal to $\frac{1}{20}$ the whole capacity of the apparatus. This provides for the expansion of the water from maximum density (40.—) to 212° Fah., and is found thus : Cold water to fill the apparatus = say 100. gallons, or any other suitable quantity. Volume of water at 40° Fah. = 1. Volume of the same weight of water at 212° = 1.043, the increase being $4\frac{3}{10}$ per cent., or just under $\frac{1}{23}$ of the original bulk. The proportion, therefore, of $\frac{1}{20}$, the capacity of the apparatus, forms an ample tank for the ordinary conditions of house warming.

Referring to Figure 147, it is proper to say here that it is better that all pipes which run between boilers and tanks, such as the pipe e, should be branched near the tank, so the direct branch d passes over the top of the tank and the branch c enters its bottom. This allows the air, vapor or steam to rise and go over into the tank without aggitating or lifting the water in the tank, as it would if obliged to pass through the pipe c, causing a waste through the overflow, or throwing the water out of the tank.

TANK FOR HIGH PRESSURES.

With high-pressure apparatus, however, more ample tanks must be provided, or disaster will follow. When proportioning a tank for a high-pressure apparatus, it must be remembered there must not only be the spare room necessary to hold the increment of the expansion of the water, but it is also necessary there should be room in the tank (which is, of course, a tight one), above the water when the latter is expanded to its utmost, sufficient to hold all the air there was originally in the tank, without its being compressed to a dangerously high pressure.

There is an occasional experiment now with some fitters who have not carefully considered this question to close the ordinary tank—proportioned by the $\frac{1}{20}$ rule—that always ends in the destruction of the weakest part of the apparatus, generally the boiler. No boiler that I know of can stand such usage

FIGURE 148.

unless it happens to be a welded coil, and then it is the tank or some weaker part of the apparatus that gives way.

To see this in its proper light, we have to consider an ordinary apparatus with an expansion tank one-twentieth of the whole capacity, or sufficient to take care of the increment of the expansion of water from 40° to 212° Fah. If we close this

tank so the air cannot escape, the accompanying diagram, Figure 148, will show the additional increment of pressure caused by the expansion of the water and the compression of the air.

When the surface of the water is at *a* the water in the apparatus is cold, say with a temperature of 40° Fah. When it is warmed to about 155 degrees, it rises until it reaches the position *b*, or half way up, and has compressed the air above it until it has a pressure of two atmospheres (by which must be understood the pressure of the atmosphere and 15 pounds additional). At a temperature of about 185 degrees it is at *c*, and the pressure of the air is *four* atmospheres, or 45 pounds gauge pressure ; at 200 degrees, or thereabouts, it reaches *d*, and the pressure is *eight* atmospheres, and at *e*, *sixteen* atmospheres, and at *f*, *thirty-two* atmospheres, or 480 pounds pressure per square inch (465 pounds above atmosphere), and, as yet, the water has not reached a temperature of 212° Fah. This is sufficient to account for the bursting and leakage of some hot water boilers and the escape of the water from the apparatus.

With a tank of twice the capacity, of course, the danger is very much lessened, as then one extra atmosphere only can be added to the pressure caused by the water-head, for a range of temperature between 40 degrees and 212 degrees. But the practice generally of closing a tank should be condemned for house warming, as a mistake in the amount of water let into the apparatus will upset all calculations ; and where high temperature is an absolute necessity, the designing of such an apparatus should be entrusted to one thoroughly conversant with the subject.

It is almost impossible to estimate the pressures that can be obtained with a closed tank. With steam the temperatures and pressures always bear a fixed relation to each other—when in the presence of water—so that knowing the one, the other can always be found. With water in a closed non-elastic vessel, however, and subjected to heat, the pressure may become enormous, although the temperature is comparatively low. Should water, at a temperature of three or four hundred degrees, burst its envelope, a large part of it will instantly fly into steam, and the damage that will follow will be just as disastrous as though a steam boiler blew up with steam at a pressure corresponding to the temperature we have supposed for the water.

It is evidently not necessary to compress air for the purpose of keeping a pressure on the water until it—the water— reaches 212 degrees. It is then necessary to advance pressure on the surface of the water in the same or a slightly greater ratio than the pressure of steam advances with its temperature (see Table XI), otherwise part of the water will be converted into steam. To proportion an apparatus for high-pressure hot-water, in which the pressure can be kept just ahead of the temperature in this relative manner would be next to impossible. It might be done for some constant temperature of the water, but would be practically impossible with varying temperatures, therefore, the only safe way to arrange for a high pressure apparatus is to provide a tank sufficiently large to take care of the increment of the water with some space above it, in which air can be compressed or steam allowed to form, but with a safety valve arranged on it to let off the excess of pressure whether of air or steam.

It is immaterial whether air or steam rests on the surface of the water in the tank for the purpose of keeping the pressure on the water, and the circulation goes on just as well with the one as with the other ; therefore, the idea of the absolutely closed tank should be abandoned as dangerous in *all* cases, and a tank with a well-made safety valve used instead. Figure 149 shows a tank with safety valve arranged for pressure above atmosphere and temperature above 212 degrees—high pressure.

FIGURE 149.

As such apparatus are generally small, the tank may be made of wrought-iron pipe with welded ends, or it may be cf cast iron and always with rounded ends.

The following table, No.XI, shows the increase of volume of water for each one hundred degrees of temperature between

40° Fah.—its greatest density—and 600 degrees ; water at 40 degrees being unity.

TABLE XI.

Temperature.	Bulk of Volume.	Safe Proportion for Tank.
40°	1.0000	. . . .
100°	1.0075	. . . .
200°	1.0380	
300°	1.0860	
400°	1.1480	
500°	1.2230	
600°	1.3100	
1	2	3

The third column gives the least safe proportion of the total cubic contents of the rest of the apparatus that it is necessary to provide in the expansion tank, for the temperatures given in the first column. For temperatures up to the boiling point the tank should be open, and for higher temperatures it should be provided with an efficient safety valve. The relative capacity of that part of the tank between *a* and *b*, Figure 147, should be proportioned to the decimal portion of the amounts in column 2 ; the capacity of the rest of the apparatus being taken as unity.

The accompanying diagram, Figure 150, shows the whole matter in a graphic manner. The dark shading—forming the wedge—to the right of the perpendicular line *a b*, shows the increase of volume of water as the temperature is advanced between 40° and 600° Fah. The light shading to the left of line *a b*, shows the constant relative volume at maximum density

so that the proportion of increase for any temperature, and con-
sequently the least capacity of the tank, is the horizontal dis-
tance between the perpendicular line *a b*, and the ordinates of
the curved line *a c*, compared with a horizontal line through the
light shading on the left. The increase of volume for tem-

FIGURE 150.

perature intermediate to those shown at the left of the diagram
can be approximated by the assistance of the other ordinates of
the curve *a c*. The total volume of the water for any tem-
perature is proportional to the distance from the perpendicular

at the left of the diagram to the curve *a c* measured on a horizontal line corresponding to the given temperature.

I wish to add, before leaving the question of tanks, that unless the water in an apparatus is to be heated above the temperature of 212° Fah., nothing can be gained by using a closed tank.   The circulation will be no faster thereby, and for house apparatus for simple warming purposes, this practice of closed tanks should not be tolerated, as it make an apparatus, which is otherwise absolutely safe, *dangerous*, and liable to burst and scald people.

Let me also add that if a closed tank is not sufficiently large to take care of the increment of expansion, under all conditions, something is sure to burst, as the expansion of the water is practically irresistible, and enormous pressures that are sure to rupture any boiler or radiator, will be obtained, and the only safeguard lies in the use of a safety valve, with a tank not only sufficiently large to take care of the increase of volume, but also to hold air enough to allow for its compression within reasonable limits.

It may happen also that a closed apparatus is started with too much water in it, in which case the expansion will fill the remaining part of the tank no matter how large it is relatively ; and, therefore, a safety valve becomes necessary to let off this superabundance of water, and the only chance of guarding against accident is to provide a reliable safety valve in every case where the tank is not an open one.

Attention must be drawn to the rapidity with which pressures increase with the temperatures.

Up to 212 degrees we may say we have no pressure.   This is not absolutely correct, as we are under the pressure of our

TABLE No. XII.

REGNAULT'S TABLE.—*From Prof. Charles A. Smith's work "Boiler Practice," with interpolations, and with fractions omitted :*

Temperature of water or steam, degrees Fah.	Pressure per square inch above atmosphere.	Temperature of water or steam, degrees Fah.	Pressures per square inch above atmosphere.	Temperature of water or steam, degrees Fah.	Pressure per square inch above atmosphere.
212	0	307	60	397	225
215	1	312	65	400	233
219	2	316	70	401	235
222	3	320	75	404	245
225	4	324	80	408	255
227	5	328	85	411	265
230	6	331	90	414	275
233	7	334	95	417	285
235	8	338	100	430	335
237	9	341	105	445	385
239	10	344	110	457	435
242	11	347	115	467	485*
244	12	350	120	487	585
246	13	353	125	500	670
248	14	355	130	504	685
250	15	358	135	519	785
252	16	361	140	534	885
254	17	363	145	547	985
256	18	366	150	....	....
257	19	368	155	....	....
259	20	371	160	...	....
262	22	373	165	....	....
266	24	375	170	...	....
269	26	377	175	....	....
272	28	380	180	....	....
274	30	382	185	....	....
281	35	384	190	....	....
287	40	386	195	....	....
293	45	388	200	....	....
298	50	390	205	....	....
300	51	393	210	....	....
303	55	394	215	....	....

* Temperatures above 485 pounds are calculated, the others are experimental.

own atmosphere.   The power to burst vessels or cylinders, however, commences at atmosphere, and counts therefrom ; therefore, up to a temperature of 212 degrees in an open apparatus the walls are not strained by the addition of heat.   Beyond this point, however, to secure any given increment of temperature we must also have an increment of pressure, and consequently must have either a closed tank in which to compress air or form steam, or be under a head of water equivalent to the pressure we desire.

Up to a temperature of 300° Fah. the necessary pressures cannot be said to be very dangerous, as with a properly proportioned and operated tank they will not exceed 51 pounds per square inch, as will be seen by Table XII.

Beyond this, however, the pressure advances very rapidly ; so that at a temperature of 400 degrees the pressure is 233 pounds per square inch, requiring an advance of 182 pounds per square inch for an increase of 100 degrees of temperature ; while at 500 degrees it is about 670 pounds per square inch, requiring an increment of 437 pounds per square inch for an advance of 100 degrees of temperature.

The following diagram (Figure 151), based on the above table, I have constructed to illustrate graphically the natural increase of pressures due to the advance of temperatures of water or steam.

The line e f is the zero of pressures in this case—atmosphere.   The ordinates of the curved line c d, to the right of the perpendicular line e f, show the increments of pressures per square inch above atmosphere, corresponding to the increments of temperatures shown on the left by the line a b, so that the

FIGURE 151.

horizontal lines measured each way through the shading, from the line *e f* show the relative increments of both temperatures and pressures.

It is probably well to remark here that horizontal ordinates of the line *e d* also represent the pressures of steam corresponding to the temperatures of steam or water, as shown by the corresponding ordinates of the line *a b*.

CHAPTER XXV.

Gate Valves—Butterfly Valves—Angle Valves—
Angle Cocks.

VALVES FOR HOT-WATER APPARATUS.

THE valves to be used in a hot-water apparatus should receive some little consideration in this book.

It is not very important as to what they are composed of so long as they will not corrode and become inoperative.

The most essential thing in the matter of valves for an apparatus is to select those that cause the least resistance to the flow of the water. Therefore, it is probable that gate valves are the best that are to be obtained in open market. Nothing but a gate valve should be tolerated in the main pipes of an apparatus unless it is a butterfly valve of good design and thin, wedge-shaped disk, that will offer little resistance to the flow of the water.

A well-designed butterfly valve for this purpose should swell in the body, Figure 152, so the area about the disk should be greater than the area of the pipe. By so doing the injury caused to the flow of the water by the obstruction of the disk and spindle will be compensated for.

When absolutely light valves are necessary about boilers, etc., so that a circuit or other part of the apparatus can be shut off for repairs or alteration, there is then nothing better than a merchantable gate valve.

When an interruption of the current only is required a butterfly valve may be used.

It would be well in the construction of either gate or butterfly valves for hot-water apparatus to have a hole in the disk with a screw plug in it, so the fitter can have the means

FIGURE 152.

of making a "pass-by" through the disk without taking the valve to a machine shop; and it also allows him the opportunity of being able to close the aperture with a plug when he thinks it necessary. Gate valves with single disks are more suitable for hot water than those with a double disk especially if they are to have a pass-by through the disk.

The gate valve is too well known to require an illustration here. Figure 152, however, shows a common form of butterfly valve with swelled body.

Globe valves should never be used in a hot-water appara-
tus on account of the obstruction they offer to the passage of
the water. Angle valves are not much better, still they are
about the only thing obtainable for radiators or coils. Gate
or butterfly valves can be used for radiators where appear-
ance is not considered. In the formation of a neat connec-
tion, however, they cannot be used, therefore the ordinary
angle valve is used instead.

FIGURE 153.

Angle valves, in which the disk will rise against the "nut"
—sometimes called the "bonnet" of the valve—are better
than ordinary steam angle valves, as the disk is withdrawn from
the centre of the current of water when they are wide open.

Figure 153 shows the manner in which the disk hinders the
flow of the water in an ordinary angle valve, by being stopped
in the middle of the globe, and Figure 154 shows the improve-

ment for hot water, when the disk is run further up. It requires a longer stem with more thread on it, in the latter valve. The pitch of the thread can be quickened, however, so the same number of revolutions will open it to the fullest extent that it is necessary to give to an ordinary steam valve.

FIGURE 154.

As it is not necessary to have that degree of tightness— called in the workshop " fit "—between the parts of hot-water valves that there is required for steam valves, as the difference of pressure between the sides is so inconsiderable, a valve like that shown in Figure 155 can be used to advantage on the inlet to radiators.

It is in a measure a plug cock of special design with the inlet at the bottom, and when the plug is in the position shown it offers a very low resistance to the flow of the water, much

less than an elbow and probably not over one-tenth what a common angle valve will offer, as there are no abrupt shoulders, and the radius of the bend is comparatively long, giving a resistance of probably less than twenty diameters of the pipe.

FIGURE 155.

A slight change of the plug from the position shown will present abrupt corners to the flow of the water, and materially check its flow when required. Less than $\frac{1}{4}$ of a turn will entirely shut off the passage of the water. The taper of the plug should be such that it will not jamb in the barrel, and a helical spring of brass wire is sufficient to keep it in its place against the slight pressure of the water, even when the valve is closed.

CHAPTER XXVI.

Air-Vents for Hot-Water Apparatus—Scollay's Automatic Air Vent for Hot-Water Radiators, Etc.

THE air-vent most in use for hot-water radiators, etc., is a simple compression wheel air-cock of small dimensions, similar to that shown in Figure 156.

They are made in various ways, but generally the small angle-valve type is preferred. They may have metal handles of the lever or the T-pattern, though the wooden wheel handles are to be preferred when they are well made, the wood being a non-conductor of heat. They are usually polished, and plated throughout in either silver or nickel, the latter being the most serviceable, as it will keep its color better.

When children have access to the air-valves of a radiator the valves can be provided with short spindles that are squared for the reception of a small socket wrench or key.

With regard to the use of air valves all that it is necessary to say is that they should be used at the very highest point of the radiator, and that usually when they are used at the end of a radiator there is a considerable air pocket above them by the fact of the tap-hole being in almost every case from one-half to one inch below the inside of the top of the casting.

The only automatic air-valve for hot-water tnat I am acquainted with is the one made by Mr. John A. Scollay, a hot-water engineer of Brooklyn, N. Y. It is shown in Figure 157. Its general appearance being that of a small brass cylinder, with a small perforated cap on the upper end, the lower end being provided with a threaded tail-piece by which to attach it to the highest point of the radiator or air chamber. The detail is a vertical section through its centre. The outer case *a* is made of brass and within it is a float *e*. To the upper side of the float there is attached a small valve *d* which forms a seat against an adjustable tube *b*, which fits into the

FIGURE 156.

head of the cylinder. A small guide stem top and bottom keeps the float in a central position. Its operation, which is plainly suggested by the diagram, Figure 157, is : Should air be disengaged from the water it will pass into the case *a*, displacing the water therein, when, of course, the valve drops away from its seat by gravitation, letting the air escape through the holes in the side of the cap. The return of the water into the cylinder after the air escapes buoys up the float, bringing the valve to its seat again and closing the point of egress.

The valves are also made to close under the effect of heat as well as floatation. The ends of the float *e* are concentrically

corrugated, so that they can move in the direction of the axis of the cylinder under internal pressure. When a quantity of alcohol, therefore, is placed within the float and the latter properly closed the expansion of the vapor of alcohol will thrust the valve to its seat if steam or hot vapor is formed sufficient to boil the alcohol.

FIGURE 157

Instead of perforations in the cap for the liberation of the air after it passes the valves a small pipe is sometimes attached to the head of the cylin der below the cap, with suitable passages so the air or vapor or accidental leakage of water can be carried to a place where it can do no damage, in the manner usual to automatic air valves on steam apparatus.

For indirect radiators, when set in such relation to the main flow-pipe (as shown in Figure 131 by the dotted lines) that the air will not escape backward through the inlet pipe to the main flow pipe, automatic valves are almost indispensably necessary and at all points in any apparatus that they are troublesome to reach or that are likely to be neglected they can be used to advantage.

Automatic vents depending on the principle of expansion alone are not reliable for hot-water purposes and the float principle is the only one that I have any knowledge of that is reliable, other than the open pipe carried higher than the tank, which, of course, is always reliable in low-pressure work when of sufficiently large diameter and untrapped. Practical reasons, that are unnecessary to explain, are likely, however, to be interposed to the promiscuous running of these open-air pipes, and, of course, they cannot be used in high-pressure work.

CHAPTER XXVII.

Automatic Door and Damper Regulators— The Nason Regulator—
The Hawkins Regulator— The Open- Tank Regulator—
The Tasker Regulator— The Haynes Regu-
lator— The Blake Regulator.

THE question of the automatic regulation of doors and dampers of hot-water apparatus is one that requires some consideration.

Mr. Joseph Nason, of New York, gave the subject considerable attention twenty or twenty-five years ago, and at that time devised a very simple practicable apparatus, which is shown in Figures 158 and 159.

His first practical use of the apparatus was in the residence of Mr. William A. Perry, M. Am. Soc. M. E., and of the firm of Henry R. Worthington, New York, in the year 1868, at Bay Ridge, L. I., in which house it is in working operation at the present time.

Figure 159 shows it in principle as applied to the chimney damper of Mr. Perry's house, and Figure 158 is a detail showing the method of compounding the levers, etc., and attaching it to the main pipe of the apparatus.

Every pipe of an apparatus is subject to some change of length when subjected to a change of temperature. The expansion of wrought iron is not great, however, being about the $\frac{1}{150000}$ of its length for each degree Fahrenheit that it is warmed —nevertheless, this is ample if the pipe has any considerable length, and it was this expansion or change of length that was taken advantage of by Mr. Nason, who conceived the idea of utilizing the expansion and contraction of any convenient run of main pipe or large branch of the same near the boiler, the longer it might happen to be, within certain practicable limits, the better for the purpose, and I believe he did not consider

FIGURE 158.

25 feet as too great a length, though he was satisfied to do with less, 10 feet or thereabouts, when he could not obtain a more favorable run of pipe.

His principle was to fix the clamp A, on the Figure 158, main pipe at some convenient point from the boiler, and also to clamp the part of the apparatus B to the pipe close to the boiler. Within the box or casing B, there is arranged a system of compound levers as shown, the multiplication of the movement between the hook a and the damper-rod d being 200—in other words the levers are so pivoted that a movement by expansion of the

$\frac{1}{500}$ part of an inch in the direction of the arrow at F on the main pipe will move the rod *d* and the end of the lever *c* in an upward direction one inch.

The steel hook *a* is connected by a rod *a'* to the clamp A. This rod being two inches from the flow-pipe is not materially affected by any change of temperature in the water, therefore when the main pipe elongates, the tendency is to put a tensile strain on the rod and hook, which latter engaging with the lever *b* gives motion to the remaining moving parts.

FIGURE 159.

The necessity for a considerable distance between A and B becomes plainer, when we consider that it is necessary to operate doors or dampers on small changes of temperature. If we desire to adjust an apparatus to keep the temperature of the water at 180° Fah., it is plain the temperature must advance a little beyond this to close the damper and also fall somewhat below it to open it again, therefore the best we can hope to do is to keep it as near 180 degrees as we can and control our

damper by the smallest difference of temperature possible, so
that we should be satisfied if we can prevent the water from
advancing above 183 degrees or going below 177 degrees,
giving us a range of temperature of six degrees.

If we control, therefore, with a change of six degrees, and
our pipe between the clamps is 25 feet long, the change of
length is $\frac{6}{160000}$ parts of the whole length, and in the case of a
25-foot pipe, it is the $\frac{1}{1000}$ part of a foot or the $\frac{1}{83}$ of an inch,
which in a decimal fraction is .012 of an inch.

Now as the multiplication is 200 times we have

$$.012'' \times 200 = 2.4 \text{ inches}$$

as the movement at the rod d for a change of six degrees when
the clamps are 25 feet apart on the pipe.

In the above apparatus, it will be noticed, the principle
involved is to take advantage of the difference of two iron rods,
or more particularly a rod and a pipe, one of them only being
subject to a sudden change of temperature and length. The
apparatus must be kept from sudden draughts of cold air and
both pipe and rod should be covered with non-conducting
materials, if the most satisfactory results are to be expected.
They should not be wrapped in the same envelope, however,
as the change of temperature in the pipe should not affect the
rod. An adjusting screw is attached to the end of the rod at
the clamp A, so the tension on the rod may be regulated.

Carleton W. Nason, M. Am. Soc. M. E., the President of
the Nason Manufacturing Company, New York, some years
ago, suggested to the writer the advantage there might be in
subjecting two strips of metal of as widely different coefficients
of expansion as possible to uniform changes of temperature,
and proposed the thermostat shown in Figure 160.

He suggested making a hollow cone of brass and another of iron and slipping the brass within the iron one, in which position to rivet them closely in a spiral manner. They were then to be cut in a lathe, between the spiral of rivets, so that when completed they formed a tapered spiral coil.

FIGURE 160.

This coil is enclosed within a case A (Figure 160), and fastened to the bottom plate *a*. To the apex of the coil· is attached a spindle *b* which passes through a stuffing box at the top of the case, as shown. Upon the end of this spindle is a cross lever with chain and pulley, the former connecting with the door or damper in the usual manner.

The brass coil of the conical spring being within the iron one and having a greater coefficient of expansion, unwinds the coil under an advance of temperature, turning the spindle and giving motion to the lever.   In like manner a fall of tempera ture contracts the coil reversing the motion of the lever.   A

FIGURE 161.   FIGURE 162.

counterweight should be used to balance the weight of the door or damper so as to lessen the work of the spring.

Mr. John T. Hawkins, M. Am. Soc. M. E., and President of the Campbell Printing Press Company, read a paper at the Nashville meeting of the American Society of Mechanical Engineers in May, 1888, on the subject of " Automatic Regulation for Hot-Water Heating-Apparatus," in which he describes a

thermostat involving the same principle as the foregoing for automatically opening and closing the doors and dampers of a hot-water boiler.

Quoting from the transactions of the American Society of Mechanical Engineers, he says :

FIGURE 163.

" Figures 161, 162 and 163, show respectively a plan view and a front and side elevation of the apparatus as attached to a hot-water system. 1 is the heater ; 2, the flue leading to chimney ; 3, a pipe leading from the top of the heater to a radiator ; 4, a return-pipe from the radiator, delivering the cooled water into the lower part of the heater. Surrounding pipe 4 is a helical-coil thermostat, constituted of two strips of

dissimilar metals, having widely different coefficients of expansion, as brass and iron, riveted, soldered, or brazed together. This helical thermostat fits over the pipe 4 easily, with the more expansible metal on the inside, and the less expansible on the outside, exposed to the temperature of the surrounding air. The lower end of the helix is secured to a lever 6, having in one arm an arc of pin-holes, the outer arm constituting the handles. A lug 7 is attached to the heater, having the single hole meeting the arc of holes in the lever 5. A pin 8 may be placed· in either of the holes in the arc, and thus the lever 6 be rigidly held in either position determined by the given hole used.

" To the upper end of the helix is secured a lever 10, having at its free end a pin 11. 13 is a damper of the flue-pipe ; and 12 a lever secured to its axis. 15 is the ash-pit or inlet damper. 19 is a strip of metal containing a series of holes fitting the pin 11. 16 is a chain passing over one of the leading pulleys 20, with one end connected to the strip 19 and the other to the inlet damper 15. 17 is a similar chain passing over another leading pulley 20, and connecting the other end of the strip 19 with the free end of the damper lever 12. 18 is a weight suspended from the lever 12, to counterbalance the weight of the damper 15 and the surplus vertical chain leading from it.

" In this construction it will be obvious that the expansible helix, having the more expansible metal exposed to the fluctuations of the temperature of the pipe within it, while the less expansible one is in contact with the surrounding air, and therefore only partially heated by conduction from the inner one, will undergo a considerably greater straightening or

unwinding for a given elevation of temperature of the pipe within it than if it were merely immersed wholly in the medium whose variation of temperature was to operate upon it, as with the ordinary thermostat ; and that, the lower end of the helix being fixed, and the helix being of considerable length, such a straigthening or unwinding by elevation, or coiling up by reduction of temperature of the pipe, will cause the upper lever 10 to move through a considerable arc for a small variation in temperature of the pipe within it, and that the force exerted to move the lever 10 will be a very positive one.   The pin holes in the plate 19 serve merely to regulate the relative position of the dampers 13 and 15, and the lever arc 6.   The same, however, may be accomplished by hooking the chains directly to the lever 10, and taking them up or letting them out, as may be required.   The adjustment of the position of the lever 6 will determine the temperature of the pipe 4, at which the dampers 13 and 15 will become closed or remain in any desired position of partial opening ; and, in any given weather, it will be only necessary to put the pin 8 in such hole of the arc of lever 6 as will keep the water returned down the pipe 4, and consequently that circulating through the radiator, at the required temperature.   This adjustment decides what temperature the apartment will be maintained at, the apparatus thereafter automatically maintaining that temperature.   *   *   *

" The helical thermostat is shown as surrounding a return pipe, but it will be equally efficient, and is generally most desirable, if placed upon an ascending or delivery pipe ; the only difference being that in one case the regulation is made to conform to the fluctuations of the temperature of the water passing

from the heater to the radiator, and in the other case to those of the water returned from the radiator to the heater."

Occasionally engineers endeavor to control the doors and dampers of an apparatus by the height of the water in the expansion tank. As the water in the apparatus warms and cools it flows and ebbs in the tank, so that a float suspended

FIGURE 164

therein, as shown in Figure 164, will rise and fall with the water and control the doors by the intervention of the chain over pulleys. It seems a simple and positive method, but for some reason it has not received the recognition it would appear to deserve. Like almost everything else of the kind, it has a

weak point, which in this case is the trouble to keep the desired level of water in the expansion tank, as evaporation and leak-age interferes and disarranges the adjustment.

A ball-cock in the tank does not help matters, as it will not come into operation until the lowest cold-water level is reached,

FIGURE 165.

so that it is necessary for some one to watch the level of the water constantly. In the hands of one who will look after the careful regulation of the height of the water it should give good results as it can be made very positive.

The Pascal Iron Works of Philadelphia used this principle to control their hot-water furnace before 1870, as I find the apparatus as shown in **Figure 165** in one of their books bearing that date.   In the illustration *a* is the expansion tank, or any open tank on the same level with it.   Through its bottom extends a tube of equal height with the tank.   Within this tank

DAMPER REGULATOR FOR HOT WATER BOILER

FIGURE 166.

is an annular float, a rod from its centre extending through the tube and connecting with the "break draught" door *c*, which door is in turn connected with a cold-air door *d* above the fire and a draught door *e*.

As the float is elevated it first opens the door *c* and closes the draught door *e*, shutting off the air from the fire.   Should this

not be sufficient its further rise opens the door c to a greater extent. If the expansion of the water is still continued, by the heat of a heavy fire, then the door d is brought into action by the further movement of the crank and stud on the right of the door c, working in the slot at the end of the rod.

Mr. E. A. Haynes, of the firm of Haynes & Kidder, Franklyn Falls, N. H., uses the expansion of water in a different manner to control the doors, etc., of an apparatus. The principle involved is to take advantage of the expansion of water or any other liquid when confined within a tight vessel, but with an elastic top that will rise and fall with the expansion and contraction of the liquid.

Figure 166 shows the apparatus in section. An outer casing of cast iron, C, of any suitable shape or dimension is connected with the boiler by the flow-pipe C' and the return-pipe C^2. This case is connected the same as any radiator or heater, so the water of the boiler can readily and properly flow through it, and it is usually placed a foot or so above the head of the boiler.

Within the case C is a smaller chamber, D, with a pipe, d, extending from its upper end, and passing through the top of the outer case. On the end of this pipe is screwed an ordinary regulator bowl with rubber diaphragm, and in all other respects the apparatus is the same as a steam regulating bowl, with levers, chains, etc.

When the water in the outer chamber, C, becomes warm it heats the water in the inner chamber, D, and expands it, driving the excess through the pipe into the bowl beneath the rubber

diaphragm, and forcing the latter upwards, operating the levers, and consequently the draft or fire-door, or both, as in a steam apparatus.

A pet-cock is used on the outer chamber to draw off the accumulated air.   A tube to fill the inner chamber to the desired height is also used, though not shown in the cut.   Adjustment is secured by running the stud *t* up or down and holding it in place by the jam-nut *t'*.

A practical difficulty attending this style of regulator is, when the water in the chamber D becomes hot by contact with the water in the case C it closes the door or damper.   A fall of temperature, however, of the water in C is not responded to quite rapidly enough by the water in D on account of the mass of water and the limited heat-transmitting surface, therefore this class of regulator can be made more sensitive by the use of a coil at D, or some other receptical that will have a large surface compared to the amount of water it holds ; or, if instead of using the apparatus as shown, the regulating bowl at the top is screwed on a long closed pipe, that is projected directly into the water of the boiler, the regulation will be closer than at present.

The principle involved, however, is a good one, and is deserving of close consideration with regard to its practical development.

Figure 167 shows the thermostatic regulator lately invented by Mr. George W. Blake, of the firm of Rutzler & Blake, of New York, and used by that firm.

The principle involved is to take advantage cf the differential expansion between a brass pipe *a* through which

the water flows, and an iron rod *b* that is kept cool
and is protected from undue changes of temperature
by being covered with a slip tube, etc. The rod *b* is

FIGURE 167.

under tension, and the pipe *a* under compression when the
temperature of the water is advancing. The upright *c* is a
beam or truss balanced against a knife edge at *d* on the end

of the brass pipe *a*. Two inches above the knife edge *d*, the rod *b* is fastened to the beam *c* in such a manner that the tension of the rod may be adjusted. To the top of the beam *c* is attached a flat steel strip or spring *f*, and to the opposite end of this spring is fastened the link *e*, the other end of which holds the lower end of the beam *c*. The upright at the right of the cut, opposite the beam, is simply a support for the end of the stirrup and the spring. The action is as follows :. When the brass pipe *a* is elongated it thrusts the lower end of the beam from it and forces the upper end to compress the spring *f* at one end while the stirrup is drawn against the opposite end of the spring by the outward movement of the lower end of the beam, the resultant action being to compress the spring from each end and deflect it into a bow which presses on the grooved wheel *g*, depressing it. The depression of the wheel gives a four fold motion to the other end of the lever at *h*, so that a depression at *g* of two inches, which can be secured by a change of about ten degrees in the water at the pipe *a*, is sufficient to move the damper chain eight inches.

The damper is weighted to remain open, which may be called its normal position, so that during the contraction of the pipe *a* while cooling, the weight *w* closes the damper, and the weight *h* restores the lever to its normal position and takes up the slack of the apparatus.

Nearly all the attachments that can be made to operate a damper may be used either on the ash-pit or draught-door, or may be employed to open or close cold-air inlets, and when used for the latter purpose are placed in direct circuit with the indirect coils or radiators.

*Walworth Manufacturing Company's Special Fittings—Provi-
dence Steam and Gas Company's Special Fittings—
Durham Company's Special Fittings.*

SPECIAL FITTINGS FOR HOT-WATER ENGINEERS.

THE ordinary steam and gas elbows and tees for wrought-
iron pipe are badly adapted for hot-water fitting. A
reference to pages 70 to 73 will show the great loss of head,
and consequently flow, of water due to common elbows with
short radii and rough ends.

The Walworth Manufacturing Company's (Boston) long-bend
water fittings, shown in Figures 177 and 178, and the Provi-
dence Steam and Gas Pipe Company's special fittings, shown in
Figures 179 and 180, are a great improvement over the common
fitting for this class of work. This company makes this class
of fitting in four forms : Elbows, tees, end tees and crosses,
from ¾ of an inch to 6 inches in diameter, and threaded or
standard iron pipe in all the branches. They also make fittings
of this class threaded in one end and flanged on the other, rang-
ing from 2 inches to 6 inches, inclusive, or they can be obtained
with flanges at all the openings for use with cast-iron flanged
pipes.

A great many of the Durham House Drainage Company's special fittings are admirably adapted to hot-water work. A group of them are selected and shown on page 355, Figure 181, and which suggest their own fitness for hot-water work.

FIGURES 177 AND 178.

A special feature of this class of fittings is shown in Figure 182. They are so formed on the inside that the alignment of the inside diameter of the pipe and the fittings agree at the

FIGURES 179 AND 180.

joints, so there is no considerable shoulder one way or the other, and if care is taken in the use of standard taps and dies, the end of the pipe can be screwed so near the bottom of the thread of the fitting that a very small space only will be left at

FIGURE 182.

these points of juncture. In the cut the pipe is shown fully screwed to the bottom of the recess of the fitting. This, of course, is well known to operative mechanics to be what is sometimes called a "practical" impossibility, without an immense loss of time and labor—meaning that ordinarily it would not be properly done, not that it could not be properly done, but that the chances would be against its being so, as it would be necessary to have the proper degree of tension on the threads just at the moment of bottoming. It is possible, however, to make a proper degree of tightness on the threads

FIGURE 182.

when the pipe is within one-quarter of an inch or thereabouts of the bottom, and not lose more time than is ordinarily consumed with common fittings. From the practical side of the question, also this space is an advantage, for should pipes be fitted to bottom tightly and then be unscrewed for any purpose, it is difficult to secure a tight joint in the thread on the second screwing, and dependence would have to be placed on the pressure at the end of the pipe, which would not be reliable, and would be impracticable for these reasons.

The small space of one-quarter of an inch in large diameter pipes, with a depth no greater than the pipe is thick, is not a serious matter, and the gain caused by maintaining a constant diameter, and the avoidance of abrupt shoulders is great.

A special eccentric fitting is shown on page 193. The Walworth Manufacturing Company, of Boston, and Bartlett, Hayward & Company, of Baltimore, make fittings of this class that are eccentric on both the " run " and the branch.

Eccentric fittings can also be formed by using eccentric bushings on the ordinary unreduced tees. They, however, do not form as good an alignment at the top of the pipe as the special eccentric fitting, for the reason that some appreciable thickness must intervene between the outside and inside diameter of the bushing at its thinnest side.

CHAPTER XXIX.

TESTING HOT-WATER RADIATORS.

I AM often asked by practical men the best method for test-
ing the comparative value of hot-water radiators.

In my judgment, the subject admits of but a single reply,
and that is : There is but one method of testing the efficiency
of a radiator for hot-water heating that will be accepted by a
scientific investigator.

Many practical men hang thermometers at a fixed distance
above the radiators that are to be compared, and note the rise
of the mercury. This may be a slight guide in a general way
as tending to indicate the temperature at which the air leaves
the radiator, but as to how much of the rise of temperature is

due to radiation, and how much to the warm current is difficult to determine, and therefore such tests have no value.

Take a radiator without a top and let the thermometer be exactly over a tube, and then both the direct radiation and the centre of the warm current of air will act on it. Let the top of the same tube be flat, and the influence of direct radiation against the bulb will be greater than with a pointed top, the distance of the thermometer from the top of the tube being the same. Take radiators with fret-work tops, and in like manner a hot current from a favorable round hole in the top of one may impinge on the bulb, while in another the thermometer may be over a solid or close part of the fret-work through which the air comes poorly, and by which direct radiation is almost entirely shut off.

Again, take radiators made without tops, or box or flat coils, and try and compare them with radiators with marble tops, or with each other. How can it be accomplished in this manner when everything is so dissimilar?

Aside from all this, it is impossible to get anything like quantitative analyses by such a method, and it would be no surprise to me if it were found that a radiator apparently doing the highest duty was really the lowest in efficiency, when tried by a method that measured and accounted for the units of heat given off in a certain time.

When dealing with steam radiators the water of condensation can be collected and weighed, and the work or duty that is done computed with great accuracy in the hands of a competent person. When dealing with hot-water radiators close'

approximations to the truth can be obtained (1) by knowing the weight of iron in the radiator and its specific heat ; (2) by knowing the number of pounds of water the radiator contains, and (3) by noting the number of degrees the whole radiator and contents will cool in a given time, counting from the moment the passage of hot water is interrupted on its way through the radiator.

Presumably the proper way to appeal to practical men in this matter is to go through an example with them, describing in detail, as we progress, the *modus operandi* :

(1) Let us assume, therefore, that we have a radiator of 100 square feet of surface, and that we desire to measure its efficiency under conditions of ordinary practice.

(2) Assume that the water enters the radiator at 205 degrees and leaves it at 195° Fah., so as to have its *mean* temperature while passing through the radiator 200° Fah.

(3) Assume the temperature of the room in which the experiment is to be conducted to be 60 degrees, and that this temperature is kept constant during the experiment, or that the room is so large that the heat imparted by the radiator is not sufficient to materially change its temperature; or, if this cannot be done on account of the room being small, then the temperature of the room at the commencement and end of the trial must be taken and a mean or average struck ; but, if possible, select a room where the temperature can be kept uniform.

The radiator or radiators should be placed in positions exactly alike and as near to the conditions of ordinary use and practice as possible, though for comparative tests, if they

are arranged on broad platforms near the centre of the room, and as far distant from each other as convenient or possible, it will be better than if they are against walls. They must also be so far from each other that the radiation of one cannot materially influence the other, and for this reason if a screen of white cloth is placed midway been them (but in such a manner that it will not prevent the air from coming freely in contact with the radiators) it will be of advantage as tending

FIGURE 183.

to make the test more equable, and as preventing error by more nearly eliminating the possibility of one radiator conflicting with the other. Positions, of course, should be transposed and the tests made over again when comparing rival radiators to find how closely the second test agreed with the results of the first trial, and to judge whether the difference found to exist between the radiators was not due to some

local cause rather than to the kind and form of the radiating
surface.

Taking the radiator then of 100 square feet, as at first
assumed, we should screw both nipples into it and put one
valve on it, after which it should be weighed carefully and the
weight noted, which weight we will assume to be 450 pounds.

FIGURE 184.

We will also assume it is made of cast iron, so as to determine
its specific heat hereafter, as the specific heats of cast and
wrought iron are somewhat different.

The reason for weighing but one valve is that on the sup-
position that when the valve on each end of the radiator is
closed and the current of water interrupted, as it will be here-

after, but one-half of each valve will enter into the weight of the radiator that is cooling, the water being divided by the disk of each valve.

Having found the weight of the metal of the radiator we should then fill it with cold water at a temperature of say 40° Fah., or whatever we can obtain and note the temperature, taking care that all the air is out of the radiator. Then weigh the radiator and the water, and by deducting one weight from the other we have the exact number of pounds of water the radiator will contain at 40° Fah., which we will assume to be 300 pounds.

We then connect the radiator as shown in Figure 183 with thermometers T T at inlet and outlet, let into the nipples as shown in Figure 184.

The radiator is then connected and filled, the air being expelled, and the water allowed to warm and circulate. After being in operation a sufficient time to leave no doubt but that the iron is as hot as the water, or as nearly so as it will ever become, the temperatures as shown by the thermometers at the inlet I and at the outlet O should be taken and noted, the valves being instantly and simultaneously closed and the time noted.

Previously we had assumed the water to be 205 degrees at inlet and 195 degrees at outlet, so the mean temperature of the water at the moment of closing the valves will be 200° Fah.

We now wait and note the cooling of the water that has been thus shut up within the radiator, and we know the iron of the radiator is cooling in the same ratio, so that we have 450

pounds of cast iron, and something less than 300 pounds of water cooling and giving off heat.

At the end of say 45 minutes we find that the water, etc., has cooled to a mean temperature of 150° Fah. That is, we find that since the water was shut off it has equalized in temperature between the ends of the radiator, and that the thermometers now show a temperature of about 151 degrees and 149 degrees, respectively, or they may be closer ; but what is most necessary to observe is that when the reading of the thermometers added together and divided by 2 gives an answer of 150 degrees or any other suitable temperature, the experiment can be stopped and the lapse of time noted.

I said there would be somewhat less than 300 pounds of water in the radiator at the moment of closing the valves, although we found it took 300 pounds to fill it at the commencement of the experiment.   This is due to the fact that water at 200 degrees occupies more space than water at 40 degrees, the volume in the former case being 1.039, and the specific gravity .9622, while in the latter case it is 1.000, and the specific gravity 1.000, or if we desire to represent the matter more plainly to a practical man we may say that the weight of a cubic foot of water at 40° Fah. is 62.4 pounds, whereas at 200° Fah. it is 60 pounds, and that the 300 pounds of water at 40 degrees decreases in weight in the ratio of 62.4 and 60. for this particular difference of temperature.   Therefore we have

$$\frac{300 \text{ lbs.} \times 60}{62.4} = 288.46$$

pounds as the weight of water that was in the radiator when the valves were closed.

We have also, however, 450 pounds of cast iron to cool, and we are at liberty here to figure the units of heat in 450 pounds of cast iron cooled 50 degrees and proceed accordingly ; but if we are to make a number of experiments with any particular heater, it is better that we should reduce the iron to the equivalent of water, and add it to the 288.46 pounds already obtained, and figure the whole as so much water.

The specific heat of cast iron is .1298 (according to Regnault) where water is unity. Therefore 450 pounds of cast iron multiplied by .1298, and divided by 1. — its equivalent in water, which is

$$\frac{450 \text{ pounds} \times .1298}{1} = 58.41 \text{ pounds.}$$

Add together then the actual pounds of water in the radiator (288.46 pounds), the equivalent in water of the iron which forms the radiator (58.40 pounds), and we have 346.86 pounds as the total equivalent of the radiator and its water when reduced to the common value of water in its capacity to store heat.

We have accordingly 346.86 pounds of water cooled from a mean temperature of 200 degrees to a mean temperature of 150 degrees, which of course is 50 degrees. Therefore 347 pounds × 50 degrees = 17343. heat units as the sum total of the heat given off by the radiator for 45 minutes.

To use this for standard comparison (as with other radiators or other conditions the time and amount of heat abstracted from the water will in all probability be different) we had better find the units of heat given off per square foot

of surface, per degree difference of temperature between the air of the room and the temperature of the radiator.

The temperature of the air of the room we assumed or found to be 60 degrees.   The temperature of the water in the radiator at the commencement of the test was 200 and at the finish 150 degrees.   So that we have

$$\frac{200° + 150°}{2} = 175°$$

as the mean temperature of the radiator during the trial.

The temperature of the room being 60 degrees, we then have $175° - 60° = 115°$ as the difference between the radiator and the air of the room.

Divide this difference (115 degrees) into the total heat (17343. heat units), and we have 150.8087 as the units of heat given off in forty-five minutes by the whole radiator (100 square feet) for each degree that the radiator is warmer than the air.

Divide 150.808 heat units by 100 square feet and we have 1.50808 as the units of heat given off by a single square foot of surface for each degree that the radiator is warmer than the air, the time being still forty-five minutes.

If, therefore, the radiator gives off 1.50808 heat units per degree of difference of temperature between the radiator and the air for forty-five minutes, it gives off 2.0116 heat units for an hour, as thus obtained

$$\frac{1\ 50808 \times 60 \text{ inches}}{45''} = 2.01077 \text{ heat units.}$$

As I remarked at the commencement, this result is a close approximation to the truth.   Errors in mercurial thermometers

and the expansion of the iron envelope of the water are likely
to cause slight differences, however, and therefore from tne
point of scientific research the result is not perfect.   For com-
parative purposes, however, with the same instruments well
compared and the differences noted, pretty accurate work can
be accomplished in the hands of an experienced person, and
the errors confined to within one or two per cent.

The following is a table of the specific heat of metals and
other substances likely to be used for radiators or experimental
purposes, which will prove useful in making tests :

TABLE No. XIII.—*Specific Heat of Metals, Etc.*

Cast Iron	.1298*	Regnault.
Wrought Iron........................	.1138	"
Zinc.................	.0955	"
Copper .'............................	.0950	"
Tiu	.0569	"
Glass................................	.1770	"
Water....	1.000c	"

Tables by other authorities may show slightly different
results.

The weight of a unit of water at different temperatures is
also of importance in these calculations as was shown before.
I therefore append a table of the weights of a cubic foot of
water at different temperatures, advancing by ten degrees from
40° to 500° Fah.

---

* These numbers are very close approximations to the truth, however, and
will do for our purpose.

TABLE No. XIV.—*Table of the Weights of a Cubic Foot of Water at Various Temeperatures.*

Temperature of water.	Pounds per cubic foot.	Temperature of water.	Pounds per cubic foot.
40	62.408	200	60.096
50	62.380	210	59.866
60	62.332	212	59.824
70	62.264	220	59.620
80	62.170	230	59.37
90	62.062	240	59.12
100	61.944	250	58.86
110	61.808	275	58.17
120	61.660	300	57.44
130	61.502	325	56.70
140	61.334	350	55.94
150	61.148	375	55.14
160	60.958	400	54.32
170	60.768	450	52.67
180	60.544	500	51.02
190	60.324	....	....

The weight of any fixed bulk of water must vary as the weight of a cubic foot of the same varies at different temperatures. Therefore, knowing the number of pounds of water that will fill any space or radiator at some stated temperature, the number of pounds weight of water which the same space will hold at a different temperature can be found by multiplying the original weight by the number opposite the new temperature and dividing by the number opposite the original temperature in the table.

Example : Assume a box filled with water at 80° Fah. to weigh 300 pounds, what will it weigh when filled with water at 275° Fah. Opposite 80 degrees is 62.17 and opposite 275 degrees is 58.17.

WEIGHTS OF A CUBIC FOOT OF WATER IN LBS. AT DIFFERENT TEMPERATURES.

FIGURE 185.

Therefore,

$$\frac{300 \text{ pounds} \times 58.17}{62.17} = 279.09 \text{ pounds.}$$

The accompanying diagram (Figure 185) shows the curve of the weight of a cubic foot of water for different temperatures from 40° to 500° Fah.

By the aid of the decimal lines close approximations can be made in the matter of weights per cubic foot in the case of temperatures not found in the table. Thus for a temperature of 245 degrees the weight is very nearly 59 pounds, as can be seen by observing where the curve crosses the 59 pound line, though the intersection shows the weight to be rather less than 59 pounds.

CHAPTER XXX

THE attachment of a thermometer to a pipe appears such a simple matter at first thought, that one who has not considered it carefully is likely to imagine it is a waste of words to dwell on it.

The object of using a thermometer on a hot-water pipe is to find the temperature of the water within the pipe, and to record this temperature with anything like accuracy the thermometer must be properly located.

The bulb of a thermometer should dip into the moving current of the water in a flow or return pipe, if reasonable accuracy is required. It must also offer little or no resistance to the flow of the water, especially in pipes of small diameter.

The ordinary bulb has not sufficient magnitude of itself to offer any considerable resistance to the passage of the water, unless in a very small pipe. The brass casing which covers it and protects it from fracture, however, is about an inch in diameter—three-quarters of an inch, pipe measure, or 1.05

inches actual—and this offers resistance when screwed
through the side of a pipe. Therefore, in pipe of 2 inches in
diameter, or less, the effect on the water of passing it directly
through a pipe must not be overlooked.

The thermometer shown on page 362 in the chapter on Test-
ing Hot-Water Radiators is a special one, in which the bulb is
not protected, but in the regular commercial thermometers for
hot-water the safety tube passes below the bulb, as shown in
section in Figure 186 at *a*.

FIGURE 186.

To avoid presenting an obstruction to the flow of the water,
and also because it is more convenient to the fitter, a *tee* is often
used in the pipe and the thermometer is screwed into it, as
shown in Figure 187.

This presents no material obstruction to the flow of the water,
but it forms an air pocket, and in a short time the ball of the
thermometer is not surrounded by water but by air, and the
true temperature of the water is not recorded.

It sometimes happens the fitter will use an upper corner of the flow pipe, say just above the boiler, and insert a T instead of an elbow, as shown in Figure 188. He probably has not a tee that is reduced on "the run," and he therefore uses a bushing or perhaps two of them and puts his thermometer in this improvised arrangement, with the result of having a deeper air pocket than before and a greater difference existing between the actual temperature of the water and what the

FIGURE 187.

thermometer shows, than with the arrangemet shown in Figure 187.

Should he only conceive the idea of putting a valve between the thermometer, T, Figure 188, and the bushing, B, using two nipples, one above and the other below the valve, for the purpose of getting at the thermometer without drawing the water from the apparatus he has a still deeper air pocket, and the thermometer will be indicating something far from the temperature of the water.

The remedy is to either put the bulb in the water through the side of the pipe as in Figure 186, or to use a tee as in Figure 187 and place it on its side, or nearly so, as shown in Figure 189, in which position the air cannot be collected or held by the *tee*.

FIGURE 188.

If a thermometer must be so placed on an apparatus that it can be cut off with valves, then it is better to place it in a small shunt circuit, with a valve on each side of it, as in Figure 190 at T, and carry the bulb well down.

Sufficient water will pass through this circuit to give a close

approximation to the true temperature of the water in the main pipe.

It is sometimes desirable to know the temperature of the water in an apparatus at distant points and in places where a permanent thermometer is not required. In such cases the

FIGURE 189.

writer has found that when an ordinary glass thermometer, but without a metal case—such as is used for testing the temperature of liquids—is placed against a pipe as shown in Figure 191, and a ball of soft putty pressed over the bulb, so as to make a close contact with the pipe, the thermometer

FIGURE 190.

will register within one degree of the actual temperature of the water within the pipe.

The putty heats rapidly and the oil, etc., of which it is made conducts the heat to the bulb. Over the putty I place cotton waste, so as to reduce the cooling action of the air to a minimum. One point of the bulb also comes in direct contact

with the iron of the pipe, and while the putty is fresh good results can be obtained.

When comparing the temperatures of radiators in a new

FIGURE 191.

apparatus this method will be found convenient, as it saves time and expense, and for comparative purposes is presumably as good as any other.

CHAPTER XXXI.

House of Notre Dame—Table of Contents of Pipes—Table of the Coefficients of Expansion of Water.

MISCELLANEOUS MATTERS AND TABLES.

O N page 196 allusion was made to the system of piping used in the House of Notre Dame, Toronto, pointing out its impracticability for very large buildings.

This building has probably less than 200,000 cubic feet of space and yet it requires twenty separate circuits of main pipes, all starting from and returning to the boilers, to secure the necessary circulation of the water for about fifty radiators. The system has its advocates, however, and in the present instance the work is well arranged and forms a good guide to any one desirous of using two or more boilers with such a system. I, therefore, give it in full as it appeared in *The Engineering and Building Record*, April 21, 1888, from a correspondent while investigating the methods of warming buildings by hot water in Canada.

HOT-WATER BOILERS AND FLOW-PIPES IN THE HOUSE OF NOTRE
DAME, TORONTO, ONTARIO.

He writes : " The extraordinary small space occupied by the boilers in this building compared to the space required for steam boilers for the same sized building surprised me.   The actual floor-space of the two boilers was only 7 feet 3 inches by 4 feet.   This, of course, did not include the fire-room and the space taken up by the connections.   The latter, however, take up a great deal more room than the boilers, although they occupy much less space than any steam boilers that would be suitable for such a building.   I was unable to find the amount of heating surface in the building on account of the difficulty of going through the rooms, but I was enabled to make sketches and measurements of the boilers and the pipes, which you will see in Figures 192 and 193.

"As all the valves on the flow-pipes were tagged and numbered, and the rooms they controlled marked on them, I by this means approximated the surface as given hereafter.

" It will be noticed a 6-inch valve controls the main flow and return pipe of each boiler.   To each valve is joined a header or manifold, and from these manifolds the flow and return pipe for each subdivision of the house is taken in pipes ranging from 3 inches to 1½ inches in diameter, as will be seen by reference to Figure 1.   Each couple or circuit is numbered from 1 to 20, inclusive, and the size of the pipes, with the rooms of the building they supply, and an approximate estimate of the surface is given in the following list by one who is accustomed to heating apparatus.

FIGURE 198.

"Circuit No. 1.—Size, 2½ inches; rooms supplied are chapel, practice-room and bath-room ; square foot surface probably not under 400 feet.

"Circuit No. 2.—Size, 2 inches ; large bath-rooms ; surface, 150 square feet.

"Circuit No. 3.—Size, 1½ inches ; bath-room ; surface, 75 square feet.

"Circuit No. 4.—Size, 1½ inches ; two coils in chapel ; surface, 100 square feet.

"Circuit No. 5.—Size, 2 inches ; coil, south-west corner sitting-room, first floor ; 120 square feet.

"Circuit No. 6.—Sitting-room, second floor, and girls' dormitory ; size, 2½ inches ; 250 square feet.

"Circuit No. 7.—Size, 1½ inches ; breakfast-room and room C ; 100 square feet.

"Circuit No. 8.—Size, 2 inches ; rooms 2 and 4 and water-closet ; 150 square feet.

"Circuit No. 9.—Size, 2 inches ; room A and parlor ; 200 square feet.

"Circuit No. 10.—Size, 2½ inches ; reception-room and two vestibules ; 300 to 400 square feet.

"Circuit No. 11.—Size, 3 inches; top floor and new hall ; 400 or 500 square feet.

"Circuit No. 12.—Size, 2 inches ; rooms 29, 30, 31, and corridor ; 150 square feet.

"Circuit No. 13.—Size, 2 inches ; rooms 6, 7 and 8 ; 150 square feet.

"Circuit No. 14.—Size, 2½ inches ; corridor 1 and room D ; 200 square feet.

"Circuit No. 15.—Size, 1½ inches; corridor 2 and room 14; wall coil, 120 square feet.

"Circuit No. 16.—Size, 1½ inches; top floor; wall coil, 100 square feet.

"Circuit No. 17.—Size, 2 inches; back hall and office; 150 square feet.

"Circuit No. 18.—Size, 2 inches; north wing, library and reading-room; 150 to 200 square feet.

"Circuit No. 19.—Size, 2½ inches; north wing, first floor; 300 to 400 square feet.

"Circuit No. 20.—Size, 2 inches; corridor, north wing, closets, etc.; 150 square feet.

"The total surface in this building cannot be much short of 3,700 square feet, and a room 12 by 12 feet is certainly more than ample for the plant, so far·as boilers and valves aie concerned.

"The necessity for so many small pipes or circuits I cannot see the philosophy of. Still it is the result of practice here, and men who have tried a branched system instead say they cannot get as good results and are not as sure of the results they will obtain as with the system shown here.

"The heat from these mains is, as a general thing, not lost. It warms the halls and rooms of the basement and their influ· ence is felt through the whole house, and correspondingly less surface is required in many of the upper parts of the building.

"The means of drawing the water from any single circuit is shown in Figure 193. A pipe of small diameter is joined with the flow and return pipe just above the return stop-valve in each case."

The fuel used in this building was given at *three* tons per week in cold weather.

CONTENTS OF PIPES OF AN APPARATUS.

In designing expansion tanks for a hot-water apparatus it is not only necessary to be able to ascertain the increment of

HOT-WATER BOILER

FIG·2

FIGURE 193.

the expansion of the water due to the greatest rise in temperature, but it is also necessary to be able to give some correct estimate of the amount of water it contains ; or, in other words, the cubic contents of the apparatus, which of course consist of boiler, pipes and radiators or coils of all descriptions.

TABLE No. XIV.—*Contents of Standard Wrought-Iron Pipes.*

Nominal internal diameter of pipe.	Length of pipe containing one cubic foot.*	Cubic feet in one foot length of standard pipe.	Weight of water in one foot of pipe. Pounds.
¾-in.	270.00	. . . .	.25
1-in.	166.90	.006	.37
1¼-in.	96.25	.010	.647
1½-in.	70 66	.014	.881
2-in.	42.91	.023	1.45
2½-in.	30.10	.032	2.97
3-in.	19.50	.051	3.20
3½-in.	14.57	.069	4.28
4-in.	11.31	.088	5 50
4½-in.	9.02	.111	6.92
5-in.	7.20	.138	8.63
6-in.	4.98	.197	12.25
7-in.	3.72	.27	16.87
8-in.	2.88	.34	21.616
9-in.	2.29	.44	27.25
10-in.	1.82	.55	34.50
11 in.	1.51	.660	41.50
12-in.	1.27	.785	49.00
13-in.	1.04	.957	59.85
14-in.	.903	1.107	68.93
15-in.	.77	1.300	82.20
16-in.	.68	1.47	91.70
17-in.	.61	1.56	102.05
1st col.	2d col.	3d col.	4th col.

* A pipe seldom contains less water than the quantity given in the table. It may, however, contain somewhat more, for when pipe has not the full thickness, and its outside diameter remains of standard size, the internal diameter must be greater than the nominal.

In estimating boilers it is either necessary to take the maker's rating of their cubic contents or figure it out for yourself, according to the mensuration of solids if you have any doubt as to the correctness of their figures.

The above also applies to all radiators of any class whatsoever not made of merchantable pipe.

The water contained in the mains and pipes of an apparatus, however, and by radiators made of ordinary wrought-iron pipe can best be estimated by the quantities of water given in the standard table of wrought-iron pipe used by all the manufacturers in the United States and from which I take the second column in Table XIV., the remaining columns (3d and 4th) are calculated.

COEFFICIENTS OF THE EXPANSION OF WATER.

Different formulæ for the expansion of water give slightly different results, and as a consequence tables to be found in popular hand-books seldom agree.

The difference, however, is not great, and the result as a whole simply goes to prove that the separate investigators arrived at results practically the same, as shown by the following table (No. XV.):

TABLE No. XV.

Temperature of water.	COEFFICIENTS OF THE EXPANSION OF WATER FROM VARIOUS SOURCES.				
	From Haswell's Tables by Dalton's method. Water at 72 degrees expands this.	From Table in Nystrom's Mechanics.	Thomas Box's Table, calculated by Tredgold's rule.	From Hood's Treatise on Heat. Dr. Young's formula.	D. K. Clark by Rankins' formula.
39	....	1.0000	....	1.00000	....
40	1.000	1.000002	1.00000	....	....
46	....	....	....	....	1.0000
50	....	1.000254	....	....	1.00015
52	1.00021	1.000353	1.0005123	1.00036	1.00029
60	....	1.000901	....	....	1.00074
62	1.00083	1.001075	1.0014070	....	1.00101
70	....	1.001909	....	1.00198	1.00160
72	1.00180	1.002151	1.002627	....	....
80	....	1.003249	....	....	1.00299
82	1.00312	1.003554	1.004143	1.00371	....
90	....	1.004894	....	....	1.00459
92	1.00477	1.005258	1.005901	....	....
100	....	1.006822	....	1.00718	1.00639
102	1.00672	1.007240	1.007911	....	....
110	....	1.009032	....	....	1.00889
112	1.00880	1.009479	1.010150	1.01001	....
120	....	1.011442	....	....	1.01139
122	1.01116	1.011956	1.01261	....	....
130	....	1.014098	....	1.01490	1.01390
132	1.01367	....	1.01527	....	....
140	....	1.016962	....	....	1.01690
142	1.01638	....	1.01814	1.01835	....
150	....	1.020021	....	....	1.01989
152	1.01934	....	1.02120	....	....
160	....	1.023262	....	1.02441	1.02340
162	1.02245	....	1.02443	....	....
170	....	1.026672	....	....	1.02690
172	1.02575	....	1.02788	1.02856	....
180	....	1.030242	....	....	1.03100
182	1.02916	....	1.03148	....	....
190	....	1.033960	....	1.03501	1.03500
192	1.03265	....	1.03526	....	....
200	....	1.037819	....	....	1.03889
202	1.03634	....	1.03922	1.03939	....
210	....	1.041809	....	....	....
212	1.04012	1.042622	1.04333	1.04306	1.0444

APPENDIX.*

THE BOLTON BOILER.

FIGURES 1 and 2 show the Bolton Water Tube Heater. It consists essentially of an upper and lower cast-iron chamber, *a* and *b*, forming, respectively, the top and base of a

Fig. 1   **Fig. 2**

boiler that are connected by wrought-iron water tubes (*c*), screwed into the bottom casting and connected with the top casting by the ordinary running thread and lock nut. All the pipes are vertical except one row, which passes nearly hori-

zontal from just above the fire door to the back of the lower
chamber, thus forming, as it were, a crown sheet to the top of
the fire box. Above these horizontal pipes is an arrangement of
vertical pendent pipes, or drop tubes (*d*), which form the larger
part of the heating surface of the boiler. The drop tubes are
screwed directly into the upper casting, and inside of each is

Fig. 3

Fig. 4

sustained a circulating tube, extending from top to bottom,
through which the local circulation in the heating tube is main-
tained and intensified. The upper chamber of the boiler is
pierced with a number of flue holes for the escape of the gases
of combustion into the chimney, seen in Figure 3. These
holes are covered with sliding dampers for the regulation

of the draught.   The boiler is set in brick-work in the manner shown, with numerous hand-holes for cleaning, etc.   The tubes are brushed or cleaned through a large door directly above the fire door, which also gives access for the removal or the renewal of the tubes directly acted on by the fire, without removing the brick-work.   The grate used is of the special shaking pattern, easily removed through the fire and ash-pit doors.   The flow-pipe starts from the upper chamber and the return pipes enter the lower one, so that the water is compelled to pass from the bottom to the upper chamber in the continuous tubes, local or return circulation going on only within the drop tubes, mak-ing, it is claimed, a positive circulator.   The boiler is made by the Detroit Heating and Lighting Company, of Detroit, Mich.

THE EXPERT BOILER.

Figures 5 and 6 show a new hot-water boiler just put on the market by Sherman S. Jewett & Co., of Buffalo, N. Y.   It is to be known to the trade as the " Expert," and can be made up in any number of sections greater than two.   The cuts show the boiler in its different aspects.   Figure 5 represents a 3-section boiler complete, with the doors thrown open, ex-posing the ash-pan, fire-box, and flue-passages, and Figure 6 is a sectional cut, showing the water-ways of the boiler and the shaking grate.

The boiler belongs to a class of vertical sectional boilers that practically form a return flue horizontal boiler, when made up in many sections.   As the boiler is increased in size the grate surface is proportionally increased.   No headers are used to join the sections.   A peculiarity of a section is that

it is made up of two elements that are exactly alike, they
being made from the same pattern.   By reversing, say, the one
on the right, it becomes a left element, and will interlock with
the right element forming the section.   The joint thus formed
at the top is somewhat like a hinge, and can be noticed in

Fig. 5   *Fig. 6*

Figure 6 when attention is called to it.   Waterways of 3½ to
4 inches are formed between the legs and heads of the sections,
and joined with bolts. Each section is six inches deep, and the
back of the fire-box is formed with fire-brick.   The direction
of the flame and products of combustion is backward through
the furnace, thence upward and forward through the middle
passages, and backward again to the chimney. The local

water circulation within the boiler is upwards and towards the center column of an element over the fire, and returns through the upper passage from the head to the side of the leg.　It is proposed with this boiler to fill a want for a comparatively low priced hot-water heater for residences.　It has a shaking grate, and is usually set without brick-work.　The illustrations show other details of construction, such as door linings, etc.

RICHMOND HEATER.

Figures 7, 8, 9, 10 and 11 show the Richmond sectional steam and hot water heater, which is manufactured by the Richmond Stove Company, Norwich, Conn.　The claims made for this heater are not for any new creation of external form,

FIGURE 7

but for the special construction, arrangement and quality of
the fire and flue services, and the system of water-ways, em-
bodying the principle of vertical circulation.

Figure 7 shows a view of the heater in its ordinary form,
but broken, showing the arrangement of the water-ways, fire
surface, combustion chamber and flues, and the course of the
products of combustion to point of exit.

Figure 8 shows the front section, which is also a water
section, in front of which is placed a shield or front connec-

FIGURE 8.   FIGURE 9.

tion, as shown in Figure 7, and on which the doors are hung
When the heater is to be brick-set a shield or front is fur-
nished, recessed with a flange extending beyond the sides
of the heater.

Figure 9 is a view of leg section, showing the form and
arrangement of the surface, placed directly above the fire.
This cut also serves to illustrate the system of water-ways and
the course of circulation.

Figure 10 is a view of an intermediate section, which is
the first section, placed at the back end of the fire-box, the
lower end having a corrugated surface exposed to the direct

action of the fire and forming a bridge wall over which the products of combustion pass.

FIGURE 10.   FIGURE 11.

Figure 11 illustrates a back section, forming the back wall of the heater, and presenting a corrugated fire surface to the products of combustion in their passage to the flues.

The grate is called the " Duplex," which is used in all of the heater constructions of the Richmond Stove Company's manufacture. The Richmond sectional heater is equally adapted for steam or hot water heating, the steam trimmings being dispensed with, and the necessary provision made for flows and returns when used for hot water.

The heater for steam is made in six sizes, ranging in capacity from 1,000 to 2,700 square feet direct radiation. The hot water heater is also made in six sizes, with capacity ranging from 1,500 to 4,000 square feet direct radiation.

INDEX.

ADVERTISEMENTS.

A STANDARD PRACTICAL WORK.

STEAM-HEATING FOR BUILDINGS;

OR,

HINTS TO STEAM FITTERS.

Being a description of Steam-Heating Apparatus for Warming and Venti-
lating Private Houses and Large Buildings, with Remarks on Steam, Water,
and Air in their relation to Heating; to which are added Useful Miscellaneous
Tables.

By WILLIAM J. BALDWIN, M. E.,

Steam-Heating Engineer.

SUBJECTS OF CHAPTERS:

Gravity Circulating Apparatus—Radiators and Heating Surfaces—Classes of
Radiation—Heating Surfaces of Boilers—Boilers for Heating—Forms of
Boilers—On Boiler Setting—Proportion of Heating Surfaces of Boilers to
Surfaces of Buildings—Relations of Grates and Chimneys to Boilers—
Safety-Valves—Draft Regulators—Automatic Water Feeders—Air-Valves
on Radiators--Wrought-Iron Pipe—Main Pipes—Steam—Heat of Steam—
Air--High-Pressure Steam—Exhaust Steam and Its Value—Boiling and
Cooking by Steam, and Apparatus—Dry by Steam—Steam Traps--Boiler
Connections and Attachments, etc.—Specification for a Steam-Heating Appa-
ratus, including Cooking, with many Illustrations and Tables.

IMPORTANT DAʻI A.

1. The size Radiators to use.
2. The size of Main-Pipes and Returns.
3. The Boiler Surface for any building.
4. The Class of Boiler to use.
5. How to Set a Boiler.
6. Grate Surface for a Builder.
7. Safety-Valve for Boilers, and their
   size.
8. Draught Regulators, and How to
   Set Them.
9. Water Feeders.
10. Air-Valves, and Where to Apply
    Them.
11. Useful Information about Iron-
    Pipe.
12. The Philosophy of Steam

PAVEMENTS

AND

ROADS;

Their Construction and Maintenance. Reprinted from THE ENGINEER- ING RECORD. Compiled by E. G. Love, Ph. D.

· This book is a compilation of articles which have appeared in recent volumes of THE ENGINEERING RECORD, edited with a view of eliminating whatever was of timely or local interest, and arranged by divisions for convenience of use.

TABLE OF CONTENTS.

. *8vo.* 410 *pp. Cloth,* $5.00.

Address, BOOK DEPARTMENT,

THE ENGINEERING RECORD,

(Prior to 1887, *The Sanitary Engineer.*) *277* PEARL STREET, NEW YORK.

STEAM-HEATING PROBLEMS;

OR,

Questions, Answers and Descriptions Relating to Steam-Heating and Steam-Fitting,

FROM

THE ENGINEERING RECORD,

ESTABLISHED 1877.

(Prior to 1887, THE SANITARY ENGINEER.)

With 109 Illustrations.

PREFACE.

THE ENGINEERING RECORD, while devoted to Engineering, Architecture, Construction, and Sanitation, has always made a special feature of its departments of Steam and Hot-Water Heating, in which a great variety of questions have been answered and descriptions of the work in various buildings have been given. The favor with which a recent publication from this office, entitled "Plumbing and House-Drainage Problems," has been received suggested the publication of "STEAM-HEATING PROBLEMS," which, though dealing with another branch of industry, is similar in character. It consists of a selection from the pages of THE ENGINEERING RECORD of questions and answers, besides comments on various problems met with in the designing and construction of steam-heating apparatus, and descriptions of steam-heating work in notable buildings.

It is hopéd that this book will prove useful to those who design, construct, and have the charge of steam-heating apparatus.

CONTENTS:

WM. B. DUNNING'S
PATENT HOT-WATER BOILER.

(Sectional View.)

PERFECT CIRCULATION. BEST IN USE. These Boilers are made in the most
thorough and substantial manner of the BEST WROUGHT IRON or STEEL (as preferred)
and are tested to 100 pound pressure per square inch before leaving the factory. NO CAST
IRON RINGS TO WARP AND CRACK. NO ASBESTOS JOINTS TO LEAK.

MANUFACTURED AT THE

NEW YORK CENTRAL IRON WORKS GENEVA, N. Y., U. S. A.

Also Steam Heating Boilers, both Portable and Brick Set. Send for Illustrated
Catalogue with full Description and Price List.

Warming churches (plan of placing a coil in each
pew).
Warming churches.

PIPE AND FITTING.

Steam-heating work—good and indifferent.
Piping adjacent buildings: pumps *vs.* steam-
traps.
True diameters and weights of standard pipes.
Expansion of pipes of various metals.
Expansion of steam-pipes.
Advantages claimed for overhead piping.
Position of valves on steam-riser connection.
Cause of noise in steam-pipes.
One-pipe system of steam-heating.
How to heat several adjacent buildings with a
single apparatus.
Patents on Mills' system of steam-heating.
Air-binding in return steam-pipes.
Air-binding in return steam-pipes, and methods
to overcome it.

VENTILATION.

Size of registers to heat certain rooms.
Determining the size of hot-air flues.
Window ventilation.
Removing vapor from dye-house.
Ventilation of Cunard steamer "Umbria."
Calculating sizes of flues and registers.
On methods of removing air from between ceiling
and roof of a church.

STEAM.

Economy of using exhaust steam for heat-
ing.
Heat of steam for different conditions.
Superheating steam by the use of coils.
Effect of using a small pipe for exhaust steam-
heating.
Explosion of a steam-table.

CUTTING NIPPLES AND BENDING PIPES.

Cutting large nipples—large in diameter and
short in length.
Cutting crooked threads.
Cutting a close nipple out of a coupling after a
thread is cut.
Bending pipe.
Cutting large nipples.
Cutting various sizes of thread with a solid die.

RAISING WATER AUTOMATICALLY.

Contrivance for raising water in high buildings.
Criticism of the foregoing and description of
another device for a similar purpose.

MOISTURE ON WALLS, ETC.

Cause and prevention of moisture on walls.
Effect of moisture on sensible temperature.

MISCELLANEOUS.

Heating water in large tanks.
Heating water for large institutions and high city
buildings.
Questions relating to water-tanks.

Faulty elevator-pump connections.
On heating several buildings from one source.
Coal-tar coating for water-pipe.
Filters for feeding house-boilers. Other means
of clarifying water.
Testing gas-pipes for leaks and making pipe-
joints.
Will boiling drinking-water purify it?
Differential rams for testing fittings and valves.
Percentage of ashes in coal.
Automatic pump-governor.
Cast-iron safe for steam-radiators.
Methods of graduating radiator service according
to the weather.
Preventing fall of spray from steam-exhaust
pipes.
Exhaust-condenser for preventing fall of spray
from steam-exhaust pipes.
Steam-heating apparatus and plenum (ventila-
tion), system in Kalamazoo Insane Asylum.
Heating and ventilation of a prison.
Amount of heat due to condensation of water.
Expansion-joints.
Resetting of house-heating boilers—a possible
saving of fuel.
How to find the water-line of boilers and position
of try-cocks.
Low-pressure hot-water system for heating
buildings in England (comments by *The
Sanitary Engineer*).
Steam-heating apparatus in Manhattan Com-
pany's and Merchants' Bank Building, New
York.
Boilers in Manhattan Company's and Merchants'
Bank Building, with extracts from specifica-
tions.
Steam-heating apparatus in Mutual Life Insur-
ance Building on Broadway.
The setting of boilers in Tribune Building, New
York.
Warming and ventilation of West Presbyterian
Church, New York City.
Principles of heating-apparatus, Fine Arts Exhi-
bition Building, Copenhagen.
Warming and ventilation of Opera-House at
Ogdensburg, N. Y.
Systems of heating houses in Germany and
Austria.
Steam-pipes under New York streets—difference
between two systems adopted.
Some details of steam and ventilating apparatus
used on the continent of Europe.

MISCELLANEOUS QUESTIONS.

Applying traps to gravity steam-apparatus.
Expansion of brass and iron pipe.
Connecting steam and return risers at their tops.
Power used in running hydraulic elevators.
On melting snow in the streets by steam.
Action of ashes street fillings on iron pipes.
Arrangement of steam-coils for heating oil-stills.
Converting a steam-apparatus into a hot-water
apparatus and back again.
Condensation per foot of steam-main when laid
under ground.
Oil in boilers from exhaust steam, and methods
of prevention.

Address, BOOK DEPARTMENT,   *Sent Post-paid on Receipt of* 3.00.

THE ENGINEERING RECORD,

P. O. BOX 3037.   277 PEARL STREET, NEW YORK.

Sent postpaid on receipt of $6.00.

Over 500 pp.—210 Illustrations.

VENTILATION AND HEATING.

By JOHN S. BILLINGS, A. M., M. D.,

LL. D. Edinb. and Harvard. D. C. L. Oxon. Member of the
National Academy of Sciences. Surgeon, U. S. Army, etc.

FROM THE PREFACE.

IN preparing this volume my object has been to produce a book which will not only be useful to students of architecture and engineering, and be convenient for reference by those engaged in the practice of these professions, but which can also be understood by non-professional men who may be interested in the important subjects of which it treats; and hence technical expressions have been avoided as much as possible, and only the simplest formulæ have been employed. It includes all that is practically important of my book on the Principles of Ventilation and Heating, the last edition of which appeared in 1889; but it is substantially a new work, with numerous illustrations of recent practice. For many of these I am indebted to THE ENGINEERING RECORD, in which the descriptions first appeared.

I am also indebted to Dr. A. C. Abbott for much valuable assistance in its preparation, and to the architects and heating engineers who have furnished me with plans and information, and whose names are mentioned in connection with the descriptions of the several buildings, etc., referred to in the text.

WASHINGTON, D. C.,   JOHN S. BILLINGS.
December, 1892.

TABLE OF CONTENTS.

ADDRESS, BOOK DEPARTMENT,

THE ENGINEERING RECORD,

277 PEARL STREET, NEW YORK.

WATER-WASTE PREVENTION.

By HENRY C. MEYER, Editor of THE ENGINEERING RECORD.

PRESS COMMENTS.

" Mr. Meyer is competent authority to speak on a subject of very great importance in all cities and one regarded with too much apathy by the public. Furthermore he has given the matter special study, and the facts detailed are the results of investigation. * * * His suggestions are eminently practicable and sensible, and should commend themselves to the judgment of every one interested in the subject."—*Troy Times.*

" The economies of this subject deserve the steady attention of tax-payers end municipal officers. It should be borne in m. d that waste of water is more than prodigal. It is dangerous to the safety of a city."—*Cincinnati Commercial Gazette.*

" The autnor of this timely book is particularly adapted to deal with the questions he discusses. But few have given the subject so much attention, and no one could treat it more impartially. He is not only intimately acquainted with the water-supply of American cities, but has personally investigated the plans adopted for curtailing water-waste in various cities in Great Britain, the results of these investigations appearing in this work.

" As our cities increase in population, and new cities spring up, the demand for more water correspondingly increases. At the same time the water-supply is diminishing, and that which would otherwise be available is rendered unfit for use by the contamination of sewage and the refuse of manufactories. It is conceded that the inhabitants of a city shou'd be supplied with all the water they can use. It is not with the *use*, but with the *waste* of water that the author deals.

" No patented appliances, are recommended, but such simple means as are free to all. We recommend the careful reading of this little book to every resident of a city who is interested in its water-supply, and particularly to those who, by virtue of vested authority, have to some extent the matter of water-waste prevention in their hands."—*American Machinist.*

" A valuable work, which really affects every urban resident. * * * There is not a city in he world in which the rate-payers are not taxed unnecessarily to pay for pumping water which .uns to waste, and any work throwing light upon this problem, without subjecting the community as a whole to inconvenience, must be a valuable treatise."—*Ottawa Daily Press.*

" A little work whose worth cannot be justly estimated. * * * It presents an interesting subject for examination and reflection to every citizen."—*Houston Post.*

" A work that should be read and studied by every one."—*Savannah News.*

" Though small in size it is a work which represents a good deal of solid work. With the amount of information which it contains it ought to prove of no small use to the city governments of the country. It is a *vade mecum* for water commissioners, and will be a valuable little text-book for every water board in America. Briefly, Mr. Meyer's object is to show by a comparison between the systems and results in different cities in America and England how much money is annually wasted in the shape of water in our larger cities for the want of proper precautions and how those precautions had best be taken. * * * Mr. Meyer's book is well got up, his arguments concisely stated, and his facts and figures well tabulated and arranged, the result being the production of a work which carries conviction with it, and which ought to be of no small value to the larger cities of the country in the future.—*Minneapolis Tribune.*

" 1 his volume is a most seasonable contribution to hydraulic and economic literature. Its author has personally and carefully investigated the problem from a practical standpoint in both England and America, and speaks with authority and backs his statements by official figures.

" The work treats generally of the condition of the water-supply of New York, and the methods tested or adopted for the prevention of waste in Glasgow, Manchester, and Liverpool, and in our own cities of Providence, Cincinnati, Boston, and New York. The data are derived from the most authoritative sources, and presented in a shape that must carry conviction with it."—*Engineering News.*

" Once get a property-owner convinced of the evils of water-waste, and this book will tell him all he wants to know about preventing it."—*Philadelphia Bulletin.*

" One of the best and most useful publications now before the public. * * * A copy of this timely publication ought to be in the hands of all water company and city officials and plumbers, and even water consumers might read it with profit."—*Memphis Appeal.*

"It is worthy of close attention. Mr. Meyer discloses the true spirit of the disinterested investigator."--*Hartford Evening Post.*

" As a brief, concise treatise upon this subject the work is of the utmost value, the author making no unproven assertions, but bringing the systems and experiences of other cities to illustrate and enforce his statements. In giving this book to the public the author is deserving of praise as a true and practical economist, whose efforts will be appreciated by thinking men, if not by the public at large."—*Inland Architect and Builder*

Cloth, $1.00.   Post-paid.

Address, Book DEPARTMENT,

THE ENGINEERING RECORD,

277 PEARL STREET, NEW YORK.

Compound Coil Indirect Hot-Water Heater. Perfect circulation with least friction; thus ensuring rapid circulation. Air currents thoroughly broken and heated.

Compound Coil Indirect Heater cased ready for connecting. These heaters are furnished cased, thus saving expense of carpenter work. The cases are made of 1″ boards, tongued and grooved, firmly held together by bolts, they are lined with tin, and the pipe openings are protected by cast-iron sleeves.

FOR PRICES, SIZES AND FURTHER INFORMATION, SEND
FOR CATALOGUE,

GOLD CAR HEATING COMPANY,

COR. FRANKFORT & CLIFF STS.,

New York.

"RUTZLER & BLAKE'S THERMOSTAT."

G. W. Blake's Patent, August 28, 1888.   Patented in England and Canada.

For Automatically Controlling the Draft of Hot-Water Boilers.   Perfect Regulation.   Positive Action.

MANUFACTURED BY

RUTZLER & BLAKE,

176 & 178 Centre Street,   NEW YORK.

STEAM AND WATER-HEATING SPECIALTIES,

BOILERS, RADIATORS, PIPE, FITTINGS AND GENERAL SUPPLIES.

Write for Special Catalogue and Prices.

PLUMBING PROBLEMS;

OR,

Questions, Answers and Descriptions,

FROM

THE ENGINEERING RECORD,

ESTABLISHED 1877.

(Prior to 1887, THE SANITARY ENGINEER.)

With 142 Illustrations.

"A feature of THE ENGINEERING RECORD (prior to 1887, *The Sanitary Engineer*), is its replies to questions on topics that come within its scope, included in which are Water-Supply, Sewage Disposal, Ventilation, Heating, Lighting, House-Drainage and Plumbing. Repeated inquiries concerning matters often explained in its columns, suggested the desirability of putting in a convenient form for reference a selection from its pages of questions and comments on various problems met with in house-drainage and plumbing, improper work being illustrated and explained as well as correct methods It is, therefore, hoped that this book will be useful to those interested in this branch of Sanitary Engineering."

TABLE OF CONTENTS :

Corrosion of Lead Lining.
Size of Flush Tank to deal with Sewage of a Small Hospital.
Details of the Construction of a House-Tank. *Illustrated.*
The Construction of a Cistern under a House.
To Protect Lead Lining of a Tank, and Cause of Sweating.
Stains on Marble. ●
Lightning Strikes Soil Pipes.
Will the Contents of a Cesspool Freeze ?
Bad Tasting Water from a Coil. *Illustrated.*
How to Fit Sheet Lead in a Large Tank.
Why Water is " Milky " When First Drawn.
Material for Water Service Pipes.
Carving Tables. *Illustrated.*
Is Galvanized Pipe Dangerous for Soft Spring Water.
How to Arrange Hush Pipes in Cisterns to Prevent Syphoning Water Through Ball Cock.
Depth of Foundations to Prevent Dampness of Site.
Where to Place a Tank to get Good Discharge at Faucet.
Self Acting Water Closets. *Illustrated.*
Wind Disturbing Seal of Trap.
How to Draw Water from a Deep Well.
Cause of Smell of Well Water.
Absorption of Light by Gas Globes.
Defective Drainage. *Illustrated.*
Fitting Basins to Marble Slabs. *Illustrated.*
Intermediate Tanks for the Water Supply of High Buildings. *Illustrated.*
How to Construct a Filtering Cistern. *Illustrated.*
Objections to Running Ventilating Pipe Into Chimney-Flue.
Size of Water Supply Pipe for Dwelling House.
Faulty Plan of a Cesspool. *Illustrated.*
Connecting Refrigerator Wastes with Drains. *Illustrated.*
Disposing of Refrigerator Wastes. *Illustrated.*
Pumping Air From Water Closet into Tea Kettle as Result of Direct Supply to Water Closets. *Illustrated.*
Danger in Connecting Tank Overflows with Soil Pipes.
Arrangement of Safe Wastes. *Illustrated.*
The kind of Men Who do not Like the *Sanitary Engineer*
What is Reasonable Plumbers' Profit.

HOT WATER CIRCULATION IN BUILDINGS.

Bath Boilers. *Illustrated.*
Setting Horizontal Boilers. *Illustrated.*

How to Secure Circulation Between Boilers in Different Houses. *Illustrated.*
Connecting One Boiler with Two Ranges. *Illustrated.*
Taking Return Below Boiler. *Illustrated.*
Trouble with Boiler.
An Ignorant Way of Dealing with a Kitchen Boiler. *Illustrated.*
Returning into Hot Water Supply Pipe. *Illustrated.*
Where should Sediment Pipe from Boiler be connected with Waste-Pipe ?
Several Flow Pipes and one Circulation Pipe. *Illustrated.*
How to Run Pipes from Water Back to Boiler. *Illustrated.*
Hot Water Circulation when Pipes from Boiler pass under the Floor. *Illustrated.*
Heating a Room from Water Back.
The Operation of Vacuum and Safety Valves. *Illustrated.*
Preventing Collapse of Boilers.
Collapse of a Boiler. *Illustrated.*
Explosion of Water Backs.
A Proposed Precaution against Water Back Explosions. *Illustrated.*
The Bursting of Kitchen Boilers and Connecting Pipes. *Illustrated.*
Giving out of Lead Vent Pipes from Boilers in an Apartment House. *Illustrated.*
Connecting a Kitchen Boiler with One or More Water Backs. *Illustrated.*
New Method of Heating Two Boilers by One Water Back. *Illustrated.*
Plan of Horizontal Hot Water Boiler. *Illustrated.*

HOT WATER SUPPLY IN VARIOUS BUILDINGS.

Kitchen and Hot Water Supply in the Residence of Mr. W. K. Vanderbilt, New York. *Illustrated.*
Kitchen and Hot Water Supply in the Residence of Mr. Cornelius Vanderbilt, New York. *Illustrated.*
Kitchen and Hot Water Supply in the Residence of Mr. Henry G. Marquand, New York. *Illustrated.*
Kitchen and Hot Water Supply in the Residence of Mr. A. J. White. *Illustrated.*
Hot Water Supply in an Office Building. *Illustrated.*
Kitchen and Hot Water Supply in the Residence of Mr. Sidney Webster. *Illustrated.*
Plumbing and Water Supply in the Residence of Mr. H. H. Cook. *Illustrated.*

Large 8vo. cloth, $2.00.

Address, BOOK DEPARTMENT,

THE ENGINEERING RECORD,

Some Details of Water-Works Construction.

By W. R. BILLINGS, Superintendent of Water-Works at Taunton, Mass.
WITH ILLUSTRATIONS FROM SKETCHES BY THE AUTHOR.

INTRODUCTORY NOTE.

Some questions addressed to the Editor of THE ENGINEERING RECORD by persons in the employ of new water-works indicated that a short series of practical articles on the Details of Constructing a Water-Works Plant would be of value ; and, at the suggestion of the Editor, the preparation of these papers was undertaken for the columns of that journal. The task has been an easy and agreeable one, and now, in a more convenient form than is afforded by the columns of the paper, these notes of actual experience are offered to the water-works fraternity, with the belief that they may be of assistance to beginners and of some interest to all.

TABLE OF CONTENTS.

Large 8vo.   Cloth, $2·00

Address, BOOK DEPARTMENT,

This is the only return flue Boiler with the interior surface accessible for cleaning.

There is a saving in fuel of at least 25% over direct draft Boilers.

This Boiler embraces the economy of the surface burning Boiler, with the efficiency of the magazine Boiler.

Can be taken through an ordinary door-way.

D. F. MORGAN,

AKRON, OHIO.

TH7511
B2